

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201561																			
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	1525000000-E	SP	680	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	4485000000-E	1170	1,204	LF	PORTABLE CONCRETE BARRIER	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	1560000000-E	620	70	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4500000000-E	1170	995	LF	RESET PORTABLE CONCRETE BARRIER	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
0001000000-E	200	Lump Sum		CLEARING & GRUBBING ... ACRE(S)	1693000000-E	654	85	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	4685000000-E	1205	2,896	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
0008000000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES	4686000000-E	1205	2,800	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
0022000000-E	225	20	CY	UNCLASSIFIED EXCAVATION	2367000000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.29	4695000000-E	1205	282	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	6132000000-N	SP	8	EA	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (24+18 -L-)	2556000000-E	846	280	LF	SHOULDER BERM GUTTER	4810000000-E	1205	10,850	LF	PAINT PAVEMENT MARKING LINES (4")	7060000000-E	1705	1,300	LF	SIGNAL CABLE
0036000000-E	225	500	CY	UNDERCUT EXCAVATION	3030000000-E	862	625	LF	STEEL BM GUARDRAIL	4835000000-E	1205	48	LF	PAINT PAVEMENT MARKING LINES (24")	7120000000-E	1705	4	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
0106000000-E	230	3,500	CY	BORROW EXCAVATION	3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	4850000000-E	1205	900	LF	REMOVAL OF PAVEMENT MARKING LINES (4")	7252000000-E	1710	70	LF	MESSENGER CABLE (1/4")
0156000000-E	250	1,300	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT	3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	4870000000-E	1205	24	LF	REMOVAL OF PAVEMENT MARKING LINES (24")	7264000000-E	1710	1,180	LF	MESSENGER CABLE (3/8")
0177000000-E	250	725	SY	BREAKING OF EXISTING ASPHALT PAVEMENT	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	4900000000-N	1252	35	EA	PERMANENT RAISED PAVEMENT MARKERS	7300000000-E	1715	80	LF	TRENCHING (UNPAVED)
0195000000-E	265	1,500	CY	SELECT GRANULAR MATERIAL	3380000000-E	862	287.5	LF	TEMPORARY STEEL BM GUARDRAIL	6000000000-E	1605	985	LF	TEMPORARY SILT FENCE	7324000000-N	1716	2	EA	JUNCTION BOX (STANDARD SIZE)
0196000000-E	270	1,000	SY	FABRIC FOR SOIL STABILIZATION	3387000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A	7360000000-N	1720	8	EA	WOOD POLE
0206000000-E	SP	2,540	SF	TEMPORARY SHORING - BARRIER SUPPORTED	3389100000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6090000000-E	1610	155	TON	STONE FOR EROSION CONTROL, CLASS B	7372000000-N	1721	4	EA	GUY ASSEMBLY
0241000000-E	SP	2,400	SY	GENERIC GRADING ITEM FABRIC FOR EMBANKMENT STABILIZATION	3649000000-E	876	5	TON	PLAIN RIP RAP, CLASS B	6099000000-E	1610	155	TON	STONE FOR EROSION CONTROL, CLASS B	7408000000-E	1722	1	EA	1" RISER WITH WEATHERHEAD
0314000000-E	SP	600	TON	SELECT MATERIAL, CLASS ***** (VI)	3656000000-E	876	1,160	SY	FILTER FABRIC FOR DRAINAGE	6012000000-E	1610	300	TON	SEDIMENT CONTROL STONE	7420000000-E	1722	4	EA	2" RISER WITH WEATHERHEAD
0314000000-E	SP	1,725	TON	SELECT MATERIAL, CLASS ***** (VII)	4412000000-E	SP	128	SF	WORK ZONE SIGNS (STATIONARY)	6015000000-E	1615	0.5	ACR	TEMPORARY MULCHING	7444000000-E	1725	400	LF	INDUCTIVE LOOP SAWCUT
0318000000-E	300	46	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	4412100000-E	SP	192	SF	WORK ZONE SIGNS (PORTABLE)	6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING	7456000000-E	1726	1,320	LF	LEAD-IN CABLE
0366000000-E	310	112	LF	15" RC PIPE CULVERTS, CLASS III	4412200000-E	SP	70	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING	7636000000-N	1745	2	EA	SIGN FOR SIGNALS
0546000000-E	310	320	LF	*** CAA PIPE CULVERTS, ***** THICK (36", 0.075")	4430000000-N	1130	30	EA	DRUMS	6029000000-E	SP	300	LF	SAFETY FENCE	7768000000-N	1751	1	EA	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)
0995000000-E	340	80	LF	PIPE REMOVAL	4435000000-N	1135	30	EA	CONES	6030000000-E	1630	370	CY	SILT EXCAVATION	7780000000-N	SP	1	EA	DETECTOR CARD (TYPE 2070L)
1011000000-N	500	Lump Sum		FINE GRADING	4446100000-E	SP	80	LF	BARRICADES (TYPE III)	6042000000-E	1632	835	LF	1/4" HARDWARE CLOTH					
1121000000-E	520	255	TON	AGGREGATE BASE COURSE	4450000000-N	1150	128	HR	FLAGGER	6048000000-E	SP	107	SY	FLOATING TURBIDITY CURTAIN					
1489000000-E	610	600	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4465000000-N	1160	2	EA	TEMPORARY CRASH CUSHIONS	6084000000-E	1660	0.5	ACR	SEEDING & MULCHING					
					4470000000-N	1160	4	EA	RESET TEMPORARY CRASH CUSHIONS	6087000000-E	1660	0.5	ACR	MOWING					
					4480000000-N	1165	2	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)										