

PROJECT NO.	SHEET NO.
37613, 37814	1-D

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	15" PIPE END SECTION EA	24" PIPE END SECTION EA	PIPE REMOVAL LF	INCIDENTAL STONE BASE TON	SHOULDER RECONSTRUCTION SMI	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, TYPE B25.0C TON	INTERMEDIATE COURSE, TYPE I19.0C TON	SURFACE COURSE, TYPE S9.5C TON	PG 64-22 PLANT MIX TON	PG 70-22 PLANT MIX TON	PATCHING EXISTING PAVEMENT TON
37613	Randolph	2	US 64	FROM DAVIDSON/RANDOLPH COUNTY LINE TO 0.2 MILE WEST OF SR 1401 (KENNEDY FARM ROAD)	1,2,4				100	1.42			317	158	2,560	21	154	166
37613	Randolph	3	US 64	FROM 0.2 MILE WEST OF SR 1401 (KENNEDY FARM ROAD) TO 0.1 MILE WEST OF SR 1344 (OLD US 64)	1,2,4			105	100	2.80			557	482	4,955	47	297	284
37613	Randolph	4	US 64	FROM 0.1 MILE WEST OF SR 1344 (OLD US 64) TO 475 FEET WEST OF SR 1807 (KINDLEY ROAD)	1,2,4	1		12	100	2.44		311	1,239	731	5,395	88	324	302
37613	Randolph	5	US 64	FROM 475 FEET WEST OF SR 1807 (KINDLEY ROAD) TO 330 FEET WEST OF SR 1382 (TABERNACLE SCHOOL ROAD)	1,2,4			40	100	0.80		311	830	400	2,640	55	158	129
37613	Randolph	6	US 64	FROM 330 FEET WEST OF SR 1382 (TABERNACLE SCHOOL ROAD) TO 0.13 MILE WEST OF SR 1416 (OLD LEXINGTON ROAD)	1,2,4				100	3.27		622	225	195	5,025	19	302	297
37613	Randolph	7	US 64	FROM 0.13 MILE WEST OF SR 1416 (OLD LEXINGTON ROAD) TO 280 FEET WEST OF SR 1418 (SPENCER MEADOW ROAD)	1,2,4		1		100	1.26	23,091		1,030	580	6,968	72	418	
37613	Randolph	8	US 64	FROM 280 FEET WEST OF SR 1418 (SPENCER MEADOW ROAD) TO 310 FEET WEST OF SR 1419 (LOWE COUNTRY ROAD)	1,2,4	1		22	100	0.92	4,083		201	81	2,035	12	122	
37613	Randolph	9	US 64	FROM 310 FEET WEST OF SR 1419 (LOWE COUNTRY ROAD) TO SR 1420 (BACK CREEK ROAD)	1,2,4				100	0.81	7,603	622	106	67	2,334	8	140	
37613	Randolph	10	US 64	FROM 0.13 MILE WEST OF SR 1420 (BACK CREEK ROAD) TO 0.14 MILE WEST OF SR 1424 (WESTCHAPEL ROAD)	1,2,3						27,434				8,439		506	
37613	Randolph	11	US 64	FROM 0.14 MILE WEST OF SR 1424 (WESTCHAPEL ROAD) TO 0.2 MILE EAST OF SR 1323 (OAKLEAF ROAD)	1,2,4	18		941	100		28,160	200	3,878	1,916	4,793	257	288	
TOTAL FOR PROJ NO. 37613						20	1	1,120	900	13.72	90,371	2,066	8,383	4,610	45,144	579	2,709	1,178
37814	Davidson	1	US 64	FROM 0.13 MILE WEST OF SR 2098 (KINDLEY ROAD) TO DAVIDSON/RANDOLPH COUNTY LINE	1,2,4				100			156	498	207	620	31	37	23
TOTAL FOR PROJ NO. 37814									100			156	498	207	620	31	37	23
GRAND TOTAL						20	1	1,120	1,000	13.72	90,371	2,222	8,881	4,817	45,764	610	2,746	1,201