

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+41.66)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	420 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	21 TON		
0011	0345000000-E	310	24" SIDE DRAIN PIPE	36 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	84 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		
0014	0995000000-E	340	PIPE REMOVAL	32 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	665 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	360 TON		
0018	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	280 TON		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	64 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	6 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0029	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	24 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	587.5 LF		
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3 EA		
0035	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0038	3635000000-E	876	PLAIN RIP RAP, CLASS II	140 TON		
0039	3649000000-E	876	PLAIN RIP RAP, CLASS B	194 TON		
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	690 SY		
0041	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0042	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	733 SF		
0043	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	725 SF		
0044	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	84 SF		
0045	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0046	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0047	4425000000-N	1125	WARNING FLAG SETS	6 EA		
0048	4430000000-N	1130	DRUMS	52 EA		
0049	4435000000-N	1135	CONES	15 EA		
0050	4446100000-E	SP	BARRICADES (TYPE III)	112 LF		
0051	4450000000-N	1150	FLAGGER	120 HR		
0052	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	2 EA		
0053	4510000000-N	SP	POLICE	42 HR		
0054	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	192 LF		
0055	4847000000-E	SP	POLYUREA PAVEMENT MARKING LINES (4")	8,727 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4847220000-N	SP	POLYUREA PAVEMENT MARKING SYMBOL	12 EA		
0057	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	96 LF		
0058	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	63 EA		
0059	6000000000-E	1605	TEMPORARY SILT FENCE	550 LF		
0060	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	145 TON		
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	185 TON		
0063	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0064	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0065	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0066	6029000000-E	SP	SAFETY FENCE	220 LF		
0067	6030000000-E	1630	SILT EXCAVATION	600 CY		
0068	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000 SY		
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	300 LF		
0070	6070000000-N	SP	SPECIAL STILLING BASINS	2 EA		
0071	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0072	6087000000-E	1660	MOWING	0.5 ACR		
0073	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0074	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0076	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0077	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0078	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		
0079	7060000000-E	1705	SIGNAL CABLE	650 LF		
0080	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	7 EA		
0081	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	1 EA		
0082	7264000000-E	1710	MESSENGER CABLE (3/8")	500 LF		
0083	7300000000-E	1715	TRENCHING (UNPAVED)	900 LF		
0084	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	8 EA		
0085	7360000000-N	1720	WOOD POLE	3 EA		
0086	7372000000-N	1721	GUY ASSEMBLY	6 EA		
0087	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0088	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0089	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,060 LF		
0090	7456000000-E	1726	LEAD-IN CABLE	1,990 LF		
0091	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0092	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	6 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0093	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+41.66 -L-)	Lump Sum	L.S.	
0094	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	22.5 LF		
0095	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	32 LF		
0096	8113000000-N	SP	SID INSPECTION	1 EA		
0097	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0098	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,450 CY		
0099	8161000000-E	420	GROOVING BRIDGE FLOORS	6,436 SF		
0100	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	69.6 CY		
0101	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+41.66 -L-)	Lump Sum	L.S.	
0102	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,767 LB		
0103	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,446 LB		
0104	8364000000-E	450	HP12X53 STEEL PILES	210 LF		
0105	8391000000-N	450	STEEL PILE POINTS	21 EA		
0106	8475000000-E	460	TWO BAR METAL RAIL	279.74 LF		
0107	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 3'-3 1/2")	295.33 LF		
0108	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	720 TON		
0109	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	800 SY		
0110	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0112	8753000000-E	SP	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	569.02 LF		
0113	8753200000-E	SP	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,349.02 LF		
0114	8892000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	5,390 SF		
1415/Mar03/Q58774.21/D55572510000/E114			Total Amount Of Bid For Entire Project :			

C201490 (B-4110)  
COUNTY: Durham

2/16/99

Contract No: C201490  
County: Durham

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General