

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	2,500 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15 + 81.00)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18 + 34.00)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22 + 85.00)	Lump Sum	L.S.	
0009	0036000000-E	225	UNDERCUT EXCAVATION	9,200 CY		
0010	0106000000-E	230	BORROW EXCAVATION	5,075 CY		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	2,360 SY		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	11,360 CY		
0013	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0014	0199000000-E	SP	TEMPORARY SHORING	11,500 SF		
0015	0206000000-E	SP	TEMPORARY SHORING - BARRIER SUPPORTED	400 SF		
0016	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VI)	250 TON		
0017	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	13 TON		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	116 LF		
001F	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
002C	1121000000-E	520	AGGREGATE BASE COURSE	215 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0022	1330000000-E	607	INCIDENTAL MILLING	250 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,202 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	360 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	345 TON		
002E	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	1,216 TON		
0027	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	171 TON		
002E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	12 TON		
002F	2556000000-E	846	SHOULDER BERM GUTTER	130 LF		
003C	3030000000-E	862	STEEL BM GUARDRAIL	1,700 LF		
0031	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	15 EA		
0033	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, SHOP CURVED)	2 EA		
0034	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	10 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0037	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
003E	3345000000-E	864	REMOVE & RESET EXISTING GUARDRAIL	262.5 LF		
003E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,300 LF		
004C	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	50 LF		
0041	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0042	3577000000-N	SP	GENERIC FENCING ITEM RESET EXISTING METAL GATE & RESET TWO EXT METAL POLES	Lump Sum	L.S.	
0043	3635000000-E	876	PLAIN RIP RAP, CLASS II	3,780 TON		
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,750 SY		
004E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	77.5 SF		
004E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	7 SF		
0047	4082000000-E	903	SUPPORTS, WOOD	244 LF		
004E	4102000000-N	904	SIGN ERECTION, TYPE E	10 EA		
004E	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
005C	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	2 EA		
0051	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	2 EA		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8	EA	
0053	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	16	EA	
0054	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	264	SF	
0055	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	256	SF	
0056	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
0057	4430000000-N	1130	DRUMS	76	EA	
0058	4435000000-N	1135	CONES	76	EA	
0059	4446100000-E	SP	BARRICADES (TYPE III)	80	LF	
0060	4455000000-N	1150	FLAGGER	20	MD	
0061	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0062	4485000000-E	1170	PORTABLE CONCRETE BARRIER	300	LF	
0063	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	189	LF	
0064	4507000000-E	SP	WATER FILLED BARRIER	1,788	LF	
0065	4508000000-E	SP	RESET WATER FILLED BARRIER	877	LF	
0066	4615000000-E	1205	REMOVABLE TAPE PAVEMENT MARKING LINES (4")	776	LF	
0067	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	44,739	LF	
0068	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	782	LF	
0069	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	350	LF	
0070	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	18	EA	

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,600	LF	
0072	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	100	LF	
0073	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	2	EA	
0074	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	41	EA	
0075	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	85	TON	
0076	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	85	TON	
0077	5771000000-E	1520	GENERIC UTILITY ITEM 10" HDPE FORCE MAIN SEWER PIPE ,SDR 9, 200# WP BY DIRECTIONAL BORE	1,615	LF	
0078	5882000000-N	SP	GENERIC UTILITY ITEM 10" x 6" TAPPING SLEEVE, VALVE , AND VALVE BOX, 200# WP	1	EA	
0079	5882000000-N	SP	GENERIC UTILITY ITEM 6" IN-LINE CHECK VALVE AND VAULT	1	EA	
0080	5882000000-N	SP	GENERIC UTILITY ITEM 6" IN-LINE CLEAN-OUT AND VAULT	1	EA	
0081	5882000000-N	SP	GENERIC UTILITY ITEM 8" GATE VALVE AND VALVE BOX, 200# WP	2	EA	
0082	5882000000-N	SP	GENERIC UTILITY ITEM 8" IN-LINE CHECK VALVE AND VAULT	1	EA	
0083	5882000000-N	SP	GENERIC UTILITY ITEM 8" IN-LINE CLEAN-OUT AND VAULT	1	EA	
0084	5888000000-E	SP	GENERIC UTILITY ITEM 6" DI RESTRAINED JOINT FORCE MAIN SEWER PIPE, PC 350	40	LF	

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI RESTRAINED JOINT FORCE MAIN SEWER PIPE, PC 350	84.54	LF	
008E	5906000000-E	SP	GENERIC UTILITY ITEM DI RESTRAINED JOINT FORCE MAIN PIPE FITTINGS, 250# WP	540	LB	
0087	6000000000-E	1605	TEMPORARY SILT FENCE	7,605	LF	
008E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	175	TON	
008E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	525	TON	
009C	6012000000-E	1610	SEDIMENT CONTROL STONE	345	TON	
0091	6015000000-E	1615	TEMPORARY MULCHING	5	ACR	
0092	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200	LB	
0093	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1	TON	
0094	6029000000-E	SP	SAFETY FENCE	6,000	LF	
009E	6030000000-E	1630	SILT EXCAVATION	520	CY	
009E	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,485	SY	
0097	6042000000-E	1632	1/4" HARDWARE CLOTH	1,030	LF	
009E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	450	SY	
009E	6084000000-E	1660	SEEDING & MULCHING	5.5	ACR	
010C	6087000000-E	1660	MOWING	3	ACR	
0101	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0102	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150 LB		
0104	6102000000-E	1664	SODDING	4,700 SY		
010E	6105000000-E	1664	WATER	79 M/G		
010E	6108000000-E	1665	FERTILIZER TOPDRESSING	4 TON		
0107	6114000000-N	SP	SPECIALIZED HAND MOWING	5.5 HR		
010E	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	16 EA		
010E	6135000000-E	SP	GENERIC EROSION CONTROL ITEM WETLAND GRASS PLANTING	0.9 ACR		
011C	7060000000-E	1705	SIGNAL CABLE	3,260 LF		
0111	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	18 EA		
0112	7264000000-E	1710	MESSENGER CABLE (3/8")	2,680 LF		
0113	7300000000-E	1715	TRENCHING (UNPAVED)	476 LF		
0114	7360000000-N	1720	WOOD POLE	21 EA		
011E	7372000000-N	1721	GUY ASSEMBLY	16 EA		
011E	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2 EA		
0117	7420000000-E	1722	2" RISER WITH WEATHERHEAD	12 EA		
011E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,700 LF		
011E	7456000000-E	1726	LEAD-IN CABLE	4,420 LF		
012C	7636000000-N	1745	SIGN FOR SIGNALS	4 EA		
0121	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	2 EA		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	5 EA		
STRUCTURE ITEMS						
0123	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 69.00 -L-)	Lump Sum	L.S.	
0124	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 34.00-L-)	Lump Sum	L.S.	
012E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22 + 85.00-L-)	Lump Sum	L.S.	
012E	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15 + 69.00 -L-)	Lump Sum	L.S.	
0127	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18 + 34.00-L-)	Lump Sum	L.S.	
012E	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (22 + 85.00 -L-)	Lump Sum	L.S.	
012E	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	204.2 CY		
013C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 69.00 -L-)	Lump Sum	L.S.	
0131	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18 + 34.00-L-)	Lump Sum	L.S.	
0132	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22 + 85.00-L-)	Lump Sum	L.S.	
0133	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	34,493 LB		
0134	8333000000-E	450	16" PRESTRESSED CONC PILES	5,375 LF		

County : Hyde

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
013E	8433000000-E	452	*** STEEL SHEET PILES (18")	7,253.1 SF		
013E	8475000000-E	460	TWO BAR METAL RAIL	726 LF		
0137	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-9")	771.75 LF		
013E	8594000000-E	876	PLAIN RIP RAP CLASS B	233 TON		
013E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	260 SY		
014C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0141	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	5,278.63 LF		
0142	8867000000-E	SP	GENERIC STRUCTURE ITEM PRECAST CONCRETE "L" BARRIER	180 LF		
0143	8897000000-N	SP	GENERIC STRUCTURE ITEM PDA ASSISTANCE	3 EA		
0144	8897000000-N	SP	GENERIC STRUCTURE ITEM PDA TESTING	3 EA		
0955/Mar10/Q203830.32/D691966800000/E144				Total Amount Of Bid For Entire Project :		

C201593 (B-3348/B-3349)
COUNTY: Hyde

2/16/99

Contract No: C201593
County: Hyde

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General