

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200857					STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200857					STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200857				
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	3317000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77	6000000000-E	1605	1,305	LF	TEMPORARY SILT FENCE
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	3380000000-E	862	50	LF	TEMPORARY STEEL BM GUARDRAIL	6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
0008000000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	3389100000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6009000000-E	1610	105	TON	STONE FOR EROSION CONTROL, CLASS B
0022000000-E	225	500	CY	UNCLASSIFIED EXCAVATION	3635000000-E	876	2,680	TON	PLAIN RIP RAP, CLASS II	6012000000-E	1610	65	TON	SEDIMENT CONTROL STONE
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+81.00)	3656000000-E	876	1,000	SY	FILTER FABRIC FOR DRAINAGE	6015000000-E	1615	0.5	ACR	TEMPORARY MULCHING
0036000000-E	225	300	CY	UNDERCUT EXCAVATION	4025000000-E	901	10	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
0106000000-E	230	775	CY	BORROW EXCAVATION	4082000000-E	903	26	LF	SUPPORTS, WOOD	6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
0156000000-E	250	230	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT	4102000000-N	904	2	EA	SIGN ERECTION, TYPE E	6029000000-E	SP	1,000	LF	SAFETY FENCE
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION	4155000000-N	907	4	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6030000000-E	1630	120	CY	SILT EXCAVATION
0206000000-E	SP	400	SF	TEMPORARY SHORING - BARRIER SUPPORTED	4155000000-N	907	4	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6036000000-E	1631	1,185	SY	MATTING FOR EROSION CONTROL
0314000000-E	SP	180	TON	SELECT MATERIAL, CLASS ***** (VI)	4158000000-N	907	4	EA	DISPOSAL OF SIGN SYSTEM, WOOD	6042000000-E	1632	190	LF	1/4" HARDWARE CLOTH
1011000000-N	500	Lump Sum		FINE GRADING	4412000000-E	SP	140	SF	WORK ZONE SIGNS (STATIONARY)	6048000000-E	SP	100	SY	FLOATING TURBIDITY CURTAIN
1220000000-E	545	50	TON	INCIDENTAL STONE BASE	4412000000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)	6084000000-E	1660	0.5	ACR	SEEDING & MULCHING
1330000000-E	607	250	SY	INCIDENTAL MILLING	4420000000-N	1120	2	EA	CHANGEABLE MESSAGE SIGN	6087000000-E	1660	0.5	ACR	MOWING
1489000000-E	610	320	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4430000000-N	1130	35	EA	DRUMS	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
1498000000-E	610	360	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	4435000000-N	1135	35	EA	CONES	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
1519000000-E	610	345	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4446100000-E	SP	56	LF	BARRICADES (TYPE III)	6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
1560000000-E	620	54	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4455000000-N	1150	10	MD	FLAGGER	6102000000-E	1664	1,800	SY	SODDING
1693000000-E	654	2	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	4465000000-N	1160	2	EA	TEMPORARY CRASH CUSHIONS	6105000000-E	1664	30	M/G	WATER
3030000000-E	862	800	LF	STEEL BM GUARDRAIL	4485000000-E	1170	300	LF	PORTABLE CONCRETE BARRIER	6108000000-E	1665	0.25	TON	FERTILIZER TOPDRESSING
3150000000-N	862	10	EA	ADDITIONAL GUARDRAIL POSTS	4490000000-E	1170	100	LF	PORTABLE CONCRETE BARRIER (ANCHORED)	6114000000-N	SP	2.5	HR	SPECIALIZED HAND MOWING
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	4615000000-E	1205	276	LF	REMOVABLE TAPE PAVEMENT MARKING LINES (4")	6132000000-N	SP	8	EA	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	4810000000-E	1205	16,602	LF	PAINT PAVEMENT MARKING LINES (4")	7060000000-E	1705	1,310	LF	SIGNAL CABLE
					4835000000-E	1205	44	LF	PAINT PAVEMENT MARKING LINES (24")	7120000000-E	1705	6	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
					4850000000-E	1205	1,100	LF	REMOVAL OF PAVEMENT MARKING LINES (4")	7264000000-E	1710	1,140	LF	MESSENGER CABLE (3/8")
					4900000000-N	1252	14	EA	PERMANENT RAISED PAVEMENT MARKERS	7300000000-E	1715	118	LF	TRENCHING (UNPAVED)
										7360000000-N	1720	10	EA	WOOD POLE
										7372000000-N	1721	8	EA	GUY ASSEMBLY
										7408000000-E	1722	1	EA	1" RISER WITH WEATHERHEAD
										7420000000-E	1722	5	EA	2" RISER WITH WEATHERHEAD
										7444000000-E	1725	378	LF	INDUCTIVE LOOP SAWCUT
										7456000000-E	1726	1,300	LF	LEAD-IN CABLE
										7636000000-N	1745	1	EA	SIGN FOR SIGNALS
										7768000000-N	1751	1	EA	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)
										7780000000-N	SP	2	EA	DETECTOR CARD (TYPE 2070L)

5/28/99
12-FEB-2004 13:38
R:\pcc\j\b3349.sum
DWGardner