

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0003	0106000000-E	230	BORROW EXCAVATION	1,600 CY		
0004	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	20 LF		
0005	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	8 LF		
0006	1245000000-E	SP	SHOULDER RECONSTRUCTION	66.4 SMI		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	250,000 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (2-1/2" TO 4-1/2")	72,000 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	500 SY		
0010	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,700 TON		
0011	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	38,000 TON		
0012	1550000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S12.5D	91,000 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	74 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,786 TON		
0015	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	5,005 TON		
0016	1704000000-E	SP	PATCHING EXISTING PAVEMENT	50 TON		
0017	1840000000-E	665	MILLED RUMBLE STRIPS	350,000 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH REPAIR)	750 TON		
0019	2154000000-N	820	METAL FUNNELS	70 EA		
0020	2165000000-E	820	12" FUNNEL DRAIN PIPE	3,150 LF		
0021	2176000000-E	820	12" FUNNEL DRAIN PIPE ELBOWS	62 EA		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0023	2354000000-N	840	FRAME WITH GRATE, STD 840.22	5 EA		
0024	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	34 EA		
0025	2486000000-E	SP	GENERIC DRAINAGE ITEM PATCH DRAINAGE STRUCTURE	280 SF		
0026	2486000000-E	SP	GENERIC DRAINAGE ITEM PATCH RC PIPE CULVERT	14 SF		
0027	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	650 SY		
0028	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	580 SY		
0029	3030000000-E	862	STEEL BM GUARDRAIL	6,975 LF		
0030	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	450 LF		
0031	3075000000-E	862	TRIPLE CORRUGATED STEEL BM GUARDRAIL	660 LF		
0032	3135000000-N	862	W-TR STEEL BM GUARDRAIL TRAN- SITION SECTIONS	7 EA		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
0034	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III MODIFIED)	8 EA		
0035	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	17 EA		
0037	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	1 EA		
0038	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	5,000 LF		
0039	3506000000-E	866	4" TIMBER FENCE POSTS, ***** LONG (8')	350 EA		
0040	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	20 EA		
0041	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	400 SF		
0042	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0043	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	6 EA		
0044	4430000000-N	1130	DRUMS	200 EA		
0045	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0046	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	2 EA		
0047	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	1,600 LF		
0048	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM SKINNY DRUMS	80 EA		
0049	4620000000-E	1205	REMOVABLE TAPE PAVEMENT MARKING LINES (6")	4,000 LF		
0050	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	19,000 LF		
0051	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	360,000 LF		
0052	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	47,000 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,262 LF		
0054	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	8,000 LF		
0055	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	832,990 LF		
0056	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	16,000 LF		
0057	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	1,500 LF		
0058	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	400 EA		
0059	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,500 EA		
0060	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0061	6012000000-E	1610	SEDIMENT CONTROL STONE	20 TON		
0062	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0063	6084000000-E	1660	SEEDING & MULCHING	82.48 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	25 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.13 TON		

0704/Mar21/Q2126095.01/D207192200000/E65

Total Amount Of Bid For Entire Project :

C201594 (I-4711)  
COUNTY: Robeson

2/16/99

Contract No: C201594  
County: Robeson

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General