

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 29.00-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40 LF		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		
0012	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	240 TON		
0014	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	470 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	41 TON		
0016	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	110 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2022000000-E	815	SUBDRAIN EXCAVATION	22 CY		
001E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
002C	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0021	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0022	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	555 LF		
0027	3030000000-E	862	STEEL BM GUARDRAIL	700 LF		
002E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	84 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003C	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0031	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
003E	3649000000-E	876	PLAIN RIP RAP, CLASS B	3 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	330 SY		
003E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6.25 SF		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	13 LF		
0037	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0038	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4 EA		
0039	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	5 EA		
0040	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	464 SF		
0041	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0042	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0043	4446100000-E	SP	BARRICADES (TYPE III)	64 LF		
0044	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,600 LF		
0045	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,600 LF		
0046	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	10 EA		
0047	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	58 TON		
0048	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	58 TON		
0049	5444000000-E	1510	6" PVC WATER PIPE, SDR ***** (SDR 21)	84 LF		
0050	5450000000-E	1510	8" PVC WATER PIPE, SDR ***** (SDR 21)	472 LF		
0051	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	1,205 LB		
0052	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	1 EA		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	5546000000-E	1510	8" GATE VALVE & VALVE BOX, *****WP (200# WP)	2	EA	
0054	6000000000-E	1605	TEMPORARY SILT FENCE	1,700	LF	
0055	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115	TON	
0056	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	160	TON	
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	65	TON	
0058	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
0059	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0060	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
0061	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50	LF	
0062	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0063	6029000000-E	SP	SAFETY FENCE	1,140	LF	
0064	6030000000-E	1630	SILT EXCAVATION	340	CY	
0065	6036000000-E	1631	MATTING FOR EROSION CONTROL	155	SY	
0066	6042000000-E	1632	1/4" HARDWARE CLOTH	80	LF	
0067	6084000000-E	1660	SEEDING & MULCHING	1	ACR	
0068	6087000000-E	1660	MOWING	1	ACR	
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0070	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0073	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0074	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		

STRUCTURE ITEMS

0075	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 29.00 -L-)	Lump Sum	L.S.	
0076	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16 + 29.00 -L-)	Lump Sum	L.S.	
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	41.2 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 29.00 -L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,900 LB		
008C	8364000000-E	450	HP12X53 STEEL PILES	650 LF		
0081	8503000000-E	460	CONCRETE BARRIER RAIL	175.5 LF		
0082	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	283 TON		
0083	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	315 SY		
0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008E	8753100000-E	SP	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,316.25 LF		

C201485 (B-4319)
COUNTY: Wayne

2/16/99

Contract No: C201485
County: Wayne

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General