

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (11+06.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	250 TON		
0008	0106000000-E	230	BORROW EXCAVATION	4,600 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	9 TON		
0012	0706000000-E	310	12" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0013	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0014	0805000000-E	310	12" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0015	0995000000-E	340	PIPE REMOVAL	56 LF		
0016	0996000000-N	350	PIPE CLEAN-OUT	4 EA		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	35 TON		

County: Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	25 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	9 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	12.5 LF		
0032	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0033	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	1 EA		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	4 EA		
0036	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	4 EA		

County: Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3635000000-E	876	PLAIN RIP RAP, CLASS II	120 TON		
0038	3642000000-E	876	PLAIN RIP RAP, CLASS A	500 TON		
0039	3649000000-E	876	PLAIN RIP RAP, CLASS B	2 TON		
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,280 SY		
0041	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0042	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	104 SF		
0043	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	276 SF		
0044	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0045	4430000000-N	1130	DRUMS	30 EA		
0046	4435000000-N	1135	CONES	20 EA		
0047	4446100000-E	SP	BARRICADES (TYPE III)	100 LF		
0048	4460000000-N	1155	WARNING LIGHTS (TYPE B)	4 EA		
0049	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	1 EA		
0050	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	20,000 LF		
0051	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	100 LF		
0052	4915000000-E	1264	7' U-CHANNEL POSTS	3 EA		
0053	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		
0054	6000000000-E	1605	TEMPORARY SILT FENCE	500 LF		
0055	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	65 TON		
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	120 TON		
0058	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0059	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0060	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0061	6024000000-E	1622	TEMPORARY SLOPE DRAINS	20 LF		
0062	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0063	6029000000-E	SP	SAFETY FENCE	100 LF		
0064	6030000000-E	1630	SILT EXCAVATION	145 CY		
0065	6036000000-E	1631	MATTING FOR EROSION CONTROL	200 SY		
0066	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0067	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0068	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0069	6087000000-E	1660	MOWING	0.5 ACR		
0070	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0073	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0075	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	8748000000-E	SP	SELECT BACKFILL MATERIAL, CLASS ** (VI)	325 TON		
STRUCTURE ITEMS						
0077	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (11+06.50 -L-)	Lump Sum	L.S.	
0078	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (11+06.50 -L-)	Lump Sum	L.S.	
0079	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	60.8 LF		
0080	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	39 LF		
0081	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	55 LF		
0082	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	25 LF		
0083	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	16 LF		
0084	8113000000-N	SP	SID INSPECTION	1 EA		
0085	8115000000-N	SP	CROSSHOLE SONIC LOGGING	3 EA		
0086	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,901 SF		
0087	8161000000-E	420	GROOVING BRIDGE FLOORS	4,784 SF		
0088	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	144.1 CY		
0089	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11+06.50 -L-)	Lump Sum	L.S.	
0090	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,623 LB		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,997 LB		
0092	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	602.74 LF		
0093	8364000000-E	450	HP12X53 STEEL PILES	105 LF		
0094	8391000000-N	450	STEEL PILE POINTS	7 EA		
0095	8433000000-E	452	*** STEEL SHEET PILES (18")	675 SF		
0096	8468000000-E	460	ONE BAR METAL RAIL	291 LF		
0097	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" X 1'-6")	306.33 LF		
0098	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	173 TON		
0099	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	193 SY		
0100	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0101	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
			Total Amount Of Bid For Entire Project :			

1554/Apr07/Q84490.22/D473432620000/E101

C201510 (B-3922)
COUNTY: Watauga

2/16/99

Contract No: C201510
County: Watauga

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General