

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (11+06.50)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (23+60-L1-)	Lump Sum	L.S.	
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (32+86-L2-)	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0008	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	250 TON		
0010	0106000000-E	230	BORROW EXCAVATION	4,600 CY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0013	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VI)	450 TON		
0014	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VII)	590 TON		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	89 TON		
0016	0343000000-E	310	15" SIDE DRAIN PIPE	72 LF		
0017	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40 LF		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	48	LF	
0019	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (48", 0.109")	264	LF	
0020	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (72", 0.138")	200	LF	
0021	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	32	LF	
0022	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	80	LF	
0023	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (48", 0.109")	3	EA	
0024	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (72", 0.138")	2	EA	
0025	0706000000-E	310	12" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24	LF	
0026	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56	LF	
0027	0805000000-E	310	12" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4	EA	
0028	0995000000-E	340	PIPE REMOVAL	665	LF	
0029	0996000000-N	350	PIPE CLEAN-OUT	4	EA	
0030	1121000000-E	520	AGGREGATE BASE COURSE	580	TON	
0031	1220000000-E	545	INCIDENTAL STONE BASE	150	TON	
0032	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	235	TON	
0033	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	645	TON	

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	53 TON		
0035	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	15 TON		
0036	2000000000-N	806	RIGHT OF WAY MARKERS	33 EA		
0037	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0038	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0039	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0040	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0041	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0042	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0043	2264000000-E	840	PIPE PLUGS	0.13 CY		
0044	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0045	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0046	2500000000-E	842	CONCRETE RETAINING WALLS	18 CY		
0047	2556000000-E	846	SHOULDER BERM GUTTER	150 LF		
0048	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	590 LF		
0049	3030000000-E	862	STEEL BM GUARDRAIL	262.5 LF		
0050	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0051	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	1 EA		
0052	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III MOD)	3 EA		
0054	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	4 EA		
0055	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	7 EA		
0056	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	5 EA		
0057	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0058	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	137.5 LF		
0059	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0060	3635000000-E	876	PLAIN RIP RAP, CLASS II	120 TON		
0061	3642000000-E	876	PLAIN RIP RAP, CLASS A	500 TON		
0062	3649000000-E	876	PLAIN RIP RAP, CLASS B	15 TON		
0063	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,660 SY		
0064	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0065	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	604 SF		
0066	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	372 SF		
0067	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	90 SF		
0068	4425000000-N	1125	WARNING FLAG SETS	12 EA		
0069	4430000000-N	1130	DRUMS	90 EA		
0070	4435000000-N	1135	CONES	61 EA		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4446100000-E	SP	BARRICADES (TYPE III)	200 LF		
0072	4455000000-N	1150	FLAGGER	80 MD		
0073	4460000000-N	1155	WARNING LIGHTS (TYPE B)	4 EA		
0074	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0075	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (45 MPH)	1 EA		
0076	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	1 EA		
0077	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	285 LF		
0078	4730000000-E	1205	EPOXY PAVEMENT MARKING LINES (4")	5,810 LF		
0079	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,800 LF		
0080	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	140 LF		
0081	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,390 LF		
0082	4915000000-E	1264	7' U-CHANNEL POSTS	3 EA		
0083	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		
0084	5492000000-E	SP	3/4" PE WATER TUBING, SDR 9, *****WP (200# WP)	52 LF		
0085	6000000000-E	1605	TEMPORARY SILT FENCE	1,250 LF		
0086	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0087	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	310 TON		
0088	6012000000-E	1610	SEDIMENT CONTROL STONE	440 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0090	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0091	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0092	6024000000-E	1622	TEMPORARY SLOPE DRAINS	20 LF		
0093	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0094	6029000000-E	SP	SAFETY FENCE	740 LF		
0095	6030000000-E	1630	SILT EXCAVATION	600 CY		
0096	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,370 SY		
0097	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	440 SY		
0098	6042000000-E	1632	1/4" HARDWARE CLOTH	620 LF		
0099	6070000000-N	SP	SPECIAL STILLING BASINS	7 EA		
0100	6084000000-E	1660	SEEDING & MULCHING	4.1 ACR		
0101	6087000000-E	1660	MOWING	1.5 ACR		
0102	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0103	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0104	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0105	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0106	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0107	6123000000-E	1670	REFORESTATION	0.25 ACR		
0108	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	16 EA		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	8748000000-E	SP	SELECT BACKFILL MATERIAL, CLASS ** (VI)	325 TON		
<b>STRUCTURE ITEMS</b>						
0110	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (11+06.50 -L-)	Lump Sum	L.S.	
0111	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (11+06.50 -L-)	Lump Sum	L.S.	
0112	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (23+59.50-L1-)	Lump Sum	L.S.	
0113	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (32+85.50-L2-)	Lump Sum	L.S.	
0114	8096000000-E	SP	PILE EXCAVATION IN SOIL	67 LF		
0115	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	124 LF		
0116	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	60.8 LF		
0117	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	39 LF		
0118	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	55 LF		
0119	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	25 LF		
0120	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	16 LF		
0121	8113000000-N	SP	SID INSPECTION	1 EA		
0122	8115000000-N	SP	CROSSHOLE SONIC LOGGING	3 EA		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (23+59.50-L1-)	Lump Sum	L.S.	
0124	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (32+85.50-L2-)	Lump Sum	L.S.	
0125	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,901 SF		
0126	8161000000-E	420	GROOVING BRIDGE FLOORS	4,784 SF		
0127	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	206.1 CY		
0128	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11+06.50 -L-)	Lump Sum	L.S.	
0129	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (23+59.50-L1-)	Lump Sum	L.S.	
0130	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (32+85.50-L2-)	Lump Sum	L.S.	
0131	8217000000-E	425	REINFORCING STEEL (BRIDGE)	45,219 LB		
0132	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,997 LB		
0133	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	602.74 LF		
0134	8364000000-E	450	HP12X53 STEEL PILES	440 LF		
0135	8391000000-N	450	STEEL PILE POINTS	19 EA		
0136	8433000000-E	452	*** STEEL SHEET PILES (18")	675 SF		
0137	8468000000-E	460	ONE BAR METAL RAIL	291 LF		
0138	8503000000-E	460	CONCRETE BARRIER RAIL	167.26 LF		
0139	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-0" X 1'-6")	306.33 LF		



County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	508 TON		
0141	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	566 SY		
0142	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0143	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0144	8755000000-E	430	3'-0" X 1'-6" PRESTRESSED CONC CORED SLABS	836.26 LF		
<b>1056/Apr12/Q119300.97/D637108720000/E144</b>			<b>Total Amount Of Bid For Entire Project :</b>			

C201612 (B-3926 & B-3922)  
COUNTY: Watauga

2/16/99

Contract No: C201612  
County: Watauga

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General