

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	60 CY		
0003	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	5,410 SY		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	5 TON		
0005	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	48 LF		
0006	1220000000-E	545	INCIDENTAL STONE BASE	1,200 TON		
0007	1245000000-E	SP	SHOULDER RECONSTRUCTION	18.5 SMI		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	107,573 SY		
0009	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.OB	9,436 TON		
0010	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.OB	20,852 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	14,777 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,273 TON		
0013	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0014	1704000000-E	SP	PATCHING EXISTING PAVEMENT	3,590 TON		
0015	1891000000-E	SP	GENERIC PAVING ITEM VARIABLE DEPTH MILLING	27,956 SY		
0016	2209000000-E	838	ENDWALLS	1.5 CY		
0017	2253000000-E	840	PIPE COLLARS	2 CY		

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
001E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2	EA	
002C	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	2,429	LF	
0021	2591000000-E	848	4" CONCRETE SIDEWALK	67	SY	
0022	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	2	EA	
0023	2605000000-N	SP	WHEELCHAIR RAMPS	2	EA	
0024	2612000000-E	848	6" CONCRETE DRIVEWAY	35	SY	
002E	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	2	EA	
002E	2830000000-N	858	ADJUSTMENT OF MANHOLES	7	EA	
0027	3030000000-E	862	STEEL BM GUARDRAIL	1,050	LF	
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	12	EA	
002E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	123,420	LF	
003C	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	75,306	LF	
0031	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	262	LF	
0032	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12	EA	
0033	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	4	EA	
0034	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	198,726	LF	

County : Bertie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	262 LF		
003E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	12 EA		
0037	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4 EA		
003E	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	706 EA		
003E	6000000000-E	1605	TEMPORARY SILT FENCE	300 LF		
004C	6012000000-E	1610	SEDIMENT CONTROL STONE	10 TON		
0041	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0042	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
004E	7300000000-E	1715	TRENCHING (UNPAVED)	10 LF		
0044	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	2 EA		
004E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,541 LF		

1018/May04/Q597460.0/D144046100000/E45

Total Amount Of Bid For Entire Project :

C201382
COUNTY: Bertie

2/16/99

Contract No: C201382
County: Bertie

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General