

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0241000000-E	SP	GENERIC GRADING ITEM INCIDENTAL GRADING FOR GUARD- RAIL	2,333 SY		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	17 TON		
0005	0343000000-E	310	15" SIDE DRAIN PIPE	60 LF		
0006	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	68 LF		
0007	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	84 LF		
0008	0995000000-E	340	PIPE REMOVAL	60 LF		
0009	1121000000-E	520	AGGREGATE BASE COURSE	823 TON		
0010	1220000000-E	545	INCIDENTAL STONE BASE	520 TON		
0011	1245000000-E	SP	SHOULDER RECONSTRUCTION	23.48 SMI		
0012	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	3,817 SY		
0013	1330000000-E	607	INCIDENTAL MILLING	1,144 SY		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	7,682 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	475 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	33,089 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,338 TON		
0018	1704000000-E	SP	PATCHING EXISTING PAVEMENT	60 TON		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	19 EA		
0020	2253000000-E	840	PIPE COLLARS	1 CY		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0022	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	80 LF		
0023	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	5 EA		
0024	2605000000-N	SP	WHEELCHAIR RAMPS	1 EA		
0025	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	194 SY		
0026	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0027	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0028	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0029	3030000000-E	862	STEEL BM GUARDRAIL	475 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0031	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III MOD)	2 EA		
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	28 EA		
0034	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	127,822 LF		
0035	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	113,064 LF		
0036	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,340 LF		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	150 LF		
0038	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	275 LF		
0039	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	30 EA		
0040	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	21 EA		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	118,649 LF		
0042	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	150 LF		
0043	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	275 LF		
0044	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	30 EA		
0045	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	19 EA		
0046	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	395 EA		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	1,160 LF		
0048	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	253 TON		
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	135 TON		
0050	6030000000-E	1630	SILT EXCAVATION	30 CY		
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0052	6084000000-E	1660	SEEDING & MULCHING	25.16 ACR		

C201610
COUNTY: Scotland

2/16/99

Contract No: C201610
County: Scotland

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General