

County : Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	16,700 CY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+22.03)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0206000000-E	SP	TEMPORARY SHORING - BARRIER SUPPORTED	1,200 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	39 TON		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	44 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	48 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	40 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	1,200 TON		

County : Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
002C	1275000000-E	600	PRIME COAT	560 GAL		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	60 TON		
0022	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	400 TON		
002E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	29 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	120 TON		
002E	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
003C	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0031	2209000000-E	838	ENDWALLS	1 CY		
0032	2275000000-E	SP	FLOWABLE FILL	4 CY		
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0034	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
003E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
003E	2556000000-E	846	SHOULDER BERM GUTTER	370 LF		

County : Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
003E	2619000000-E	850	4" CONCRETE PAVED DITCH	195 SY		
003E	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	350 LF		
004C	3030000000-E	862	STEEL BM GUARDRAIL	537.5 LF		
0041	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0042	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0043	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0044	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
004E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
004E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
0047	3649000000-E	876	PLAIN RIP RAP, CLASS B	140 TON		
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,360 SY		
004E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
005C	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	5 SF		
0051	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	13 LF		
0052	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0053	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	3 EA		
0054	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	72 SF		

County : Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	160 SF		
005E	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0057	4430000000-N	1130	DRUMS	40 EA		
005E	4435000000-N	1135	CONES	40 EA		
005E	4446100000-E	SP	BARRICADES (TYPE III)	48 LF		
006C	4455000000-N	1150	FLAGGER	280 MD		
0061	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
006E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	320 LF		
006E	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	90 LF		
0064	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	20 EA		
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	21,600 LF		
006E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,492 LF		
0067	6000000000-E	1605	TEMPORARY SILT FENCE	560 LF		
006E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	285 TON		
006E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	285 TON		
007C	6012000000-E	1610	SEDIMENT CONTROL STONE	780 TON		
0071	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
007E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		

County : Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0074	6029000000-E	SP	SAFETY FENCE	450 LF		
0075	6030000000-E	1630	SILT EXCAVATION	1,545 CY		
0076	6036000000-E	1631	MATTING FOR EROSION CONTROL	910 SY		
0077	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	55 SY		
0078	6042000000-E	1632	1/4" HARDWARE CLOTH	260 LF		
0079	6070000000-N	SP	SPECIAL STILLING BASINS	20 EA		
0080	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0081	6087000000-E	1660	MOWING	2 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0086	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0087	6123000000-E	1670	REFORESTATION	0.1 ACR		
0088	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0089	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	252 LF		
------	--------------	-----	------------------------------------	-----------	--	--

AA1

*** OR ***

County : Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	232	LF	
0091 AA2	0986000000-E	SP	GENERIC PIPE ITEM 15" HDPE PIPE CULVERTS	20	LF	
*** OR ***						
0092 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	232	LF	
0093 AA3	0986000000-E	SP	GENERIC PIPE ITEM 15" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, 0.064" THICK	20	LF	
***** END SCHEDULE AA *****						
WALL ITEMS						
0094	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL	1,350	SF	
009E	8847000000-E	SP	GENERIC RETAINING WALL ITEM SOIL NAIL RETAINING WALL	5,662	SF	
STRUCTURE ITEMS						
009E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18 + 22.03-L-)	Lump Sum	L.S.	
0097	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 22.03-L-)	Lump Sum	L.S.	
009E	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SOIL	234	LF	
009E	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	133	LF	
010C	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	234	LF	

County : Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0101	8113000000-N	SP	SID INSPECTION	2 EA		
0102	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0103	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,023.7 SF		
0104	8161000000-E	420	GROOVING BRIDGE FLOORS	3,020 SF		
0105	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	104.1 CY		
0106	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18 + 22.03-L-)	Lump Sum	L.S.	
0107	8217000000-E	425	REINFORCING STEEL (BRIDGE)	32,112 LB		
0108	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,694 LB		
0109	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	98,600 LS		
0110	8433000000-E	452	*** STEEL SHEET PILES (18'')	2,270 SF		
0111	8503000000-E	460	CONCRETE BARRIER RAIL	193.52 LF		
0112	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0113	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0114	8748000000-E	SP	SELECT BACKFILL MATERIAL, CLASS ** (VI)	210 TON		

1545/May10/Q211980.17/D467973240000/E114

Total Amount Of Bid For Entire Project :

C201426
COUNTY: Swain

2/16/99

Contract No: C201426
County: Swain

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General