



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

July 12, 2006

Addendum No. 1

RE: Contract ID: C201626
WBS# 38132
Pitt County
NC-33 From West City Limits of
Grimesland to 5 Lane Section in Sampson.

July 18, 2006 Letting

To Whom It May Concern:

Reference is made to the sketch maps and proposal form recently furnished to you on this project.

The following revisions have been made to the proposal form:

On Page No. 15, the project special provision entitled "Shoulder Construction" has been replaced with the project special provision entitled "Shoulder Reconstruction." Please void Page No. 15 in your proposal and staple the revised Page No. 15 thereto.

On Page No. 1 of the item sheets, line item "3-124300000-E-SP Shoulder Construction" is hereby changed to "3-124500000-E-SP Shoulder Reconstruction." The quantity remained the same at 10 SMI. The contract will be prepared accordingly.

The following revisions have been made to the sketch maps:

Sheet Nos. 1 and 2 were revised to reflect the change from "Shoulder Construction" to "Shoulder Reconstruction" and to add a note concerning moving of ditches. Please void Sheet Nos. 1 and 2 in your sketch maps and replace with the revised Sheet Nos. 1 and 2.

New Sheet No. 4 is being added to show details of the widening at Avon Road. Please staple new Sheet No. 4 after Sheet No. 3 in your sketch maps.

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
DESIGN SERVICES UNIT
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128
FAX: 919-250-4119


WEBSITE: WWW.DOH.DOT.STATE.NC.US

LOCATION:
CENTURY CENTER COMPLEX
ENTRANCE B2
1020 BIRCH RIDGE DRIVE
RALEIGH NC

Page No. 2 (C201626)
Pitt County

The Expedite file has been updated to reflect these revisions. Please download the Expedite addendum file and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,



R. A. Garris, PE
Contract Officer

RAG/jag/pa
Attachments

cc: Mr. W. S. Varnedoe, PE
Mr. S. D. DeWitt, PE
Mr. E. C. Powell, PE
Mr. C. E. Lassiter, PE
Ms. D. M. Barbour, PE
Mr. Art McMillan, PE
Mr. Victor Barbour, PE
Mr. Mark Staley (2)
Mr. Robert Memory
Mr. R. E. Davenport, Jr., PE
Ms. Norma Smith
Ms. Marsha Byrd
Ms. Taylor Mishoe
Project File (2)

PROJECT SPECIAL PROVISIONS

ROADWAY

SHOULDER RECONSTRUCTION:

(1-18-00) (Rev.7-18-06)

RR 07

Description

The work covered by this provision consists of reconstructing earth shoulders, including median shoulder in accordance with the *Roadway Standard Drawing Nos. 560.01 and 560.02*, from the edge of pavement to the existing shoulder point as directed by the Engineer. Perform this work immediately after the resurfacing operations are completed as directed by the Engineer.

Materials

On any map that contains widening, use all suitable material generated from the widening operation to construct the shoulder. Furnish any other earth material necessary for the construction of the shoulders. Provide earth material meeting the approval of the Engineer. No testing will be necessary.

Perform shoulder reconstruction in the following order: scarify the existing shoulder to provide the proper bond; add the earth material to the shoulder; and compact the reconstructed shoulder to the satisfaction of the Engineer.

The Contractor shall dispose of any excess material generated by the shoulder reconstruction in an approved disposal site.

Measurement and Payment

Shoulder Reconstruction will be measured and paid for as the actual number of shoulder miles that have been constructed. Measurement will be made along the edge of each shoulder. Measurement will be made to the nearest 0.01 of a mile. Such price and payment will be full compensation for furnishing earth material, hauling, placing, compaction, and all incidentals necessary to complete construction of the shoulders.

Incidental Stone Base will be measured and paid for as provided in Article 545-6 of the *Standard Specifications*.

Seeding and Mulching will be measured and paid for as provided elsewhere in this contract.

Payment will be made under:

Pay Item	Pay Unit
Shoulder Reconstruction	Shoulder Mile

PRICE ADJUSTMENT - ASPHALT BINDER FOR PLANT MIX: (11-21-00)

Price adjustments for asphalt binder for plant mix will be made in accordance with Section 620 of the *Standard Specifications* as modified herein.

The base price index for asphalt binder for plant mix is \$369.29 per ton.

This base price index represents an average of F.O.B. selling prices of asphalt binder at supplier's terminals on June 1, 2006.