

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+34.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,000 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	250 TON		
0008	0106000000-E	230	BORROW EXCAVATION	15,300 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	50 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	1,500 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,750 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0014	0995000000-E	340	PIPE REMOVAL	40 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,250 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	400 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	770 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	120 TON		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0026	2253000000-E	840	PIPE COLLARS	1.5 CY		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0028	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2 LF		
0029	2354200000-N	840	FRAME WITH GRATE, STD 840.24	1 EA		
0030	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.***** (840.33)	2 EA		
0031	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	65 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	525 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0037	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	712.5 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0039	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0040	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (3)	400 LF		
0041	3569000000-E	867	BARBED WIRE FENCE RESET	400 LF		
0042	3642000000-E	876	RIP RAP, CLASS A	25 TON		
0043	3649000000-E	876	RIP RAP, CLASS B	280 TON		
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,400 SY		
0045	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	589 SF		
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	128 SF		
0049	4430000000-N	1130	DRUMS	60 EA		
0050	4435000000-N	1135	CONES	20 EA		
0051	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0052	4450000000-N	1150	FLAGGER	352 HR		
0053	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0054	4590000000-E	SP	GENERIC TRAFFIC CONTROL ITEM EPOXY PAVEMENT MARKING LINES (4")	3,840 LF		
0055	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	114 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	16,800 LF		
0057	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	12 EA		
0058	6000000000-E	1605	TEMPORARY SILT FENCE	400 LF		
0059	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0060	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	245 TON		
0061	6012000000-E	1610	SEDIMENT CONTROL STONE	315 TON		
0062	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0063	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0064	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0065	6024000000-E	1622	TEMPORARY SLOPE DRAINS	175 LF		
0066	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5 EA		
0067	6029000000-E	SP	SAFETY FENCE	400 LF		
0068	6030000000-E	1630	SILT EXCAVATION	1,300 CY		
0069	6036000000-E	1631	MATTING FOR EROSION CONTROL	650 SY		
0070	6037000000-E	SP	COIR FIBER MAT	257 SY		
0071	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
0072	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0073	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0074	6087000000-E	1660	MOWING	1.5 ACR		
0075	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0077	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75	LB	
0078	6108000000-E	1665	FERTILIZER TOPDRESSING	3	TON	
0079	6114000000-N	SP	SPECIALIZED HAND MOWING	3.5	HR	
0080	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	
0081	6123000000-E	1670	REFORESTATION	1	ACR	
0082	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FAIRCLOTH SKIMMER	1	EA	
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
0083	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	48	LF	
AA1						
0084	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	116	LF	
AA1						
*** OR ***						
0085	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28	LF	
AA2						
0086	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	96	LF	
AA2						
0087	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	20	LF	
AA2						
0088	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	20	LF	
AA2						
*** OR ***						
0089	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28	LF	
AA3						
0090	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	96	LF	
AA3						
0091	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	20	LF	
AA3						

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	20 LF		
***** END SCHEDULE AA *****						
<b>STRUCTURE ITEMS</b>						
0093	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (18+34.50 -L-)	Lump Sum	L.S.	
0094	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18+34.50 -L-)	Lump Sum	L.S.	
0095	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+34.50 -L-)	Lump Sum	L.S.	
0096	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	75.4 LF		
0097	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	22 LF		
0098	8113000000-N	SP	SID INSPECTION	4 EA		
0099	8114000000-N	SP	SPT TESTING	4 EA		
0100	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0101	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+34.50 -L-)	Lump Sum	L.S.	
0102	8156000000-E	SP	CONCRETE WEARING SURFACE	5,458 SF		
0103	8161000000-E	420	GROOVING BRIDGE FLOORS	6,361 SF		
0104	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	104.4 CY		
0105	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+34.50 -L-)	Lump Sum	L.S.	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	8217000000-E	425	REINFORCING STEEL (BRIDGE)	24,651 LB		
0107	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,669 LB		
0108	8364000000-E	450	HP12X53 STEEL PILES	490 LF		
0109	8475000000-E	460	TWO BAR METAL RAIL	309.68 LF		
0110	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-11 1/2")	325.34 LF		
0111	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	725 TON		
0112	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	805 SY		
0113	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0114	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0115	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,948.94 LF		

0829/Jun13/Q97503.01/D483975080000/E115

Total Amount Of Bid For Entire Project :

**Contract No: C 201474**

**County: Rowan**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General