



BEGIN PROJECT 37301  
-L- POT 10+32

FINAL PAVEMENT MARKING SCHEDULE			
SYMBOL	DESCRIPTION	PAY ITEM QUANTITY BREAKDOWN	TOTAL QUANTITY
FINAL MARKERS SNOWPLOWABLE PAVEMENT MARKERS			
ME	YELLOW & YELLOW	217 EA	
			TOTAL 217 EA
PAVEMENT MARKINGS THERMOPLASTIC ( 4" , 90 MILS )			
TA	WHITE EDGELINE	850 LF	
			TOTAL 850 LF
THERMOPLASTIC ( 4" , 120 MILS )			
TD	2' WHITE MINISKIP	22 LF	
TE	WHITE SOLID LANE LINE	150 LF	
TF	10 FT. YELLOW SKIP	1732 LF	
TH	YELLOW SINGLE CENTER	6885 LF	
TI	YELLOW DOUBLE CENTER	3974 LF	
			TOTAL 12763 LF
THERMOPLASTIC ( 8" , 90 MILS )			
TT	YELLOW DIAGONAL	55 LF	
			TOTAL 55 LF
THERMOPLASTIC ( 24" , 120 MILS )			
T2	WHITE STOPBAR	100 LF	
			TOTAL 100 LF
THERMOPLASTIC PAVEMENT MARKING SYMBOLS ( 90 MILS )			
UA	LEFT TURN ARROW	15 EA	
UB	RIGHT TURN ARROW	2 EA	
UC	STRAIGHT ARROW	4 EA	
			TOTAL 21 EA

NOTE: REFER TO ROADWAY STANDARD DRAWINGS FOR PAVEMENT MARKING DETAILS

APPROVED *[Signature]* DATE: 6-26-06

**FINAL PAVEMENT MARKING PLAN**

SCALE: NONE		REVISIONS
DATE: 12-18-03		
DWG. BY: RCB		
DESIGN BY:		
REVIEWED BY:		

26-JUN-2006 14:03  
 \\dl3cad208484\rdy\moving\_ahed\sr1419\_mai3022r\1419\_pml.dgn  
 PLOT AT D:\3CAD\226332