

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	0.1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,075 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	3,500 CY		
0007	0106000000-E	230	BORROW EXCAVATION	11,750 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	675 CY		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	180 SY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	1,050 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,350 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	710 TON		
0013	0522000000-E	310	*** X *** X *** RC PIPE TEES, CLASS III (15" X 15" X 15")	2 EA		
0014	0902000000-E	310	**** X **** BIT COAT CS PIPE ARCH CULVERTS, TYPE A ***** THICK (87" X 63", 0.109")	152 LF		
0015	0995000000-E	340	PIPE REMOVAL	1,400 LF		
0016	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0017	1220000000-E	545	INCIDENTAL STONE BASE	350 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,550 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	5,100 TON		
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,700 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	675 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	260 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	25 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	8 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	8 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	6 EA		
0031	2220000000-E	838	REINFORCED ENDWALLS	19.4 CY		
0032	2275000000-E	SP	FLOWABLE FILL	30 CY		
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	55 EA		
0034	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.85 LF		
0035	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	13 EA		
0036	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0038	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	15 EA		
0039	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	17 EA		
0040	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0041	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0042	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	8,800 LF		
0043	2591000000-E	848	4" CONCRETE SIDEWALK	2,550 SY		
0044	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	7 EA		
0045	2612000000-E	848	6" CONCRETE DRIVEWAY	360 SY		
0046	2626000000-E	852	3" CONCRETE ISLAND COVERS	4 SY		
0047	2830000000-N	858	ADJUSTMENT OF MANHOLES	7 EA		
0048	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0049	3030000000-E	862	STEEL BM GUARDRAIL	662.5 LF		
0050	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	12.5 LF		
0051	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0052	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0053	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0054	3628000000-E	876	RIP RAP, CLASS I	40 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	3649000000-E	876	RIP RAP, CLASS B	410 TON		
0056	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,100 SY		
0057	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	130 SF		
0058	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	208 SF		
0059	4430000000-N	1130	DRUMS	149 EA		
0060	4435000000-N	1135	CONES	60 EA		
0061	4450000000-N	1150	FLAGGER	1,600 HR		
0062	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	45 EA		
0063	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	850 LF		
0064	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	12,763 LF		
0065	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	55 LF		
0066	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	100 LF		
0067	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	21 EA		
0068	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	29,740 LF		
0069	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	217 EA		
0070	5672000000-N	1515	RELOCATE FIRE HYDRANT	2 EA		
0071	6000000000-E	1605	TEMPORARY SILT FENCE	2,200 LF		
0072	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0073	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	585 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6012000000-E	1610	SEDIMENT CONTROL STONE	465 TON		
0075	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0076	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0077	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0078	6024000000-E	1622	TEMPORARY SLOPE DRAINS	45 LF		
0079	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0080	6029000000-E	SP	SAFETY FENCE	300 LF		
0081	6030000000-E	1630	SILT EXCAVATION	915 CY		
0082	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,000 SY		
0083	6042000000-E	1632	1/4" HARDWARE CLOTH	1,260 LF		
0084	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0085	6087000000-E	1660	MOWING	2.5 ACR		
0086	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0087	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0088	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0089	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0090	6111000000-E	SP	IMPERVIOUS DIKE	65 LF		
0091	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0092	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	4 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6132000000-N	SP	GENERIC EROSION CONTROL ITEM SPECIAL STILLING BASINS	3	EA	
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
0094	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,184	LF	
AA1						
0095	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	644	LF	
AA1						
0096	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,116	LF	
AA1						
0097	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	2,124	LF	
AA1						
*** OR ***						
0098	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	928	LF	
AA2						
0099	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	248	LF	
AA2						
0100	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,100	LF	
AA2						
0101	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,748	LF	
AA2						
0102	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	256	LF	
AA2						
0103	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	396	LF	
AA2						
0104	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	16	LF	
AA2						
0105	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.079")	376	LF	
AA2						

\*\*\* OR \*\*\*

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	928	LF	
0107 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	248	LF	
0108 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,100	LF	
0109 AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,748	LF	
0110 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	256	LF	
0111 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	396	LF	
0112 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	16	LF	
0113 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	376	LF	

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

0656/Aug03/Q125261.6/D314856500000/E113

Total Amount Of Bid For Entire Project :