

County : Columbus

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0003 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 1,000 CY | | |
| 0004 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 105 TON | | |
| 0005 | 0995000000-E | 340 | PIPE REMOVAL | 538 LF | | |
| 0006 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 170 TON | | |
| 0007 | 1330000000-E | 607 | INCIDENTAL MILLING | 2,970 SY | | |
| 0008 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 4,450 TON | | |
| 0009 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 3,390 TON | | |
| 0010 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 4,860 TON | | |
| 0011 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 642 TON | | |
| 0012 | 2253000000-E | 840 | PIPE COLLARS | 1.75 CY | | |
| 0013 | 2535000000-E | 846 | ***X *** CONCRETE CURB (8" X 12") | 344 LF | | |
| 0014 | 2612000000-E | 848 | 6" CONCRETE DRIVEWAY | 65 SY | | |
| 0015 | 2655000000-E | 852 | 5" MONOLITHIC CONCRETE ISLANDS (KEYED IN) | 125 SY | | |
| 0016 | 2830000000-N | 858 | ADJUSTMENT OF MANHOLES | 6 EA | | |
| 0017 | 2845000000-N | 858 | ADJUSTMENT OF METER BOXES OR VALVE BOXES | 3 EA | | |
| 0018 | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 15,900 LF | | |

County : Columbus

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0019 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 19,815 | LF | |
| 0020 | 4695000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS) | 335 | LF | |
| 0021 | 4697000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS) | 275 | LF | |
| 0022 | 4725000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) | 50 | EA | |
| 0023 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 363 | EA | |
| 0024 | 5325600000-E | 1510 | 6" WATER LINE | 15 | LF | |
| 0025 | 5540000000-E | 1515 | 6" VALVE | 1 | EA | |
| 0026 | 5672000000-N | 1515 | RELOCATE FIRE HYDRANT | 1 | EA | |
| 0027 | 5882000000-N | SP | GENERIC UTILITY ITEM BREAKDOWN & REBUILD EXT MAN-HOLE | 2 | EA | |
| 0028 | 5888000000-E | SP | GENERIC UTILITY ITEM 12" DI SEWER PIPE, CLASS 52 | 20 | LF | |
| 0029 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 125 | LF | |
| 0030 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 75 | TON | |
| 0031 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 800 | TON | |
| 0032 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 215 | TON | |
| 0033 | 6015000000-E | 1615 | TEMPORARY MULCHING | 9 | ACR | |
| 0034 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 350 | LB | |
| 0035 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 1.25 | TON | |
| 0036 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 50 | LF | |

County : Columbus

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0037 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 2 EA | | |
| 0038 | 6030000000-E | 1630 | SILT EXCAVATION | 785 CY | | |
| 0039 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 5,600 SY | | |
| 0040 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 20 LF | | |
| 0041 | 6045000000-E | SP | *** TEMPORARY PIPE (18") | 10 LF | | |
| 0042 | 6069000000-E | 1638 | STILLING BASINS | 18 CY | | |
| 0043 | 6084000000-E | 1660 | SEEDING & MULCHING | 8.75 ACR | | |
| 0044 | 6087000000-E | 1660 | MOWING | 5.5 ACR | | |
| 0045 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 110 LB | | |
| 0046 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.3 TON | | |
| 0047 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 225 LB | | |
| 0048 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 6.25 TON | | |
| 0049 | 6111000000-E | SP | IMPERVIOUS DIKE | 10 LF | | |
| 0050 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 1 HR | | |
| 0051 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 8 EA | | |
| 0052 | 7060000000-E | 1705 | SIGNAL CABLE | 550 LF | | |
| 0053 | 7120000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 3 SECTION) | 4 EA | | |
| 0054 | 7144000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 5 SECTION) | 2 EA | | |
| 0055 | 7252000000-E | 1710 | MESSENGER CABLE (1/4") | 1,663 LF | | |
| 0056 | 7264000000-E | 1710 | MESSENGER CABLE (3/8") | 360 LF | | |

County : Columbus

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0057 | 7279000000-E | 1715 | TRACER WIRE | 150 LF | | |
| 0058 | 7288000000-E | 1715 | PAVED TRENCHING (*****) (1, 2") | 90 LF | | |
| 0059 | 7300000000-E | 1715 | UNPAVED TRENCHING (*****) (1, 2") | 825 LF | | |
| 0060 | 7301000000-E | 1715 | DIRECTIONAL DRILL (*****) (1, 2") | 150 LF | | |
| 0061 | 7324000000-N | 1716 | JUNCTION BOX (STANDARD SIZE) | 7 EA | | |
| 0062 | 7348000000-N | 1716 | JUNCTION BOX (OVER-SIZED, HEAVY DUTY) | 2 EA | | |
| 0063 | 7360000000-N | 1720 | WOOD POLE | 4 EA | | |
| 0064 | 7372000000-N | 1721 | GUY ASSEMBLY | 15 EA | | |
| 0065 | 7408000000-E | 1722 | 1" RISER WITH WEATHERHEAD | 2 EA | | |
| 0066 | 7420000000-E | 1722 | 2" RISER WITH WEATHERHEAD | 3 EA | | |
| 0067 | 7432000000-E | 1722 | 2" RISER WITH HEAT SHRINK TUBING | 2 EA | | |
| 0068 | 7444000000-E | 1725 | INDUCTIVE LOOP SAWCUT | 550 LF | | |
| 0069 | 7456000000-E | 1726 | LEAD-IN CABLE (*****) (18-2) | 1,420 LF | | |
| 0070 | 7516000000-E | 1730 | COMMUNICATIONS CABLE (**FIBER) (12) | 2,313 LF | | |
| 0071 | 7552000000-N | 1731 | INTERCONNECT CENTER | 2 EA | | |
| 0072 | 7566000000-N | 1733 | DELINEATOR MARKER | 1 EA | | |
| 0073 | 7686000000-N | SP | CONDUIT ENTRANCE INTO EXISTING FOUNDATION | 1 EA | | |
| 0074 | 7756000000-N | 1751 | CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED) | 1 EA | | |
| 0075 | 7780000000-N | 1751 | DETECTOR CARD (TYPE 2070L) | 7 EA | | |

County : Columbus

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|---|--------------|-------|---|-------------|-----------|--------|
| 0076 | 7901000000-N | 1753 | CABINET BASE EXTENDER | 1 EA | | |
| 0077 | 8126000000-N | 414 | CULVERT EXCAVATION, STA ***** (32+29.90 -L-REV) | Lump Sum | L.S. | |
| 0078 | 8133000000-E | 414 | FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT | 12 TON | | |
| 0079 | 8196000000-E | 420 | CLASS A CONCRETE (CULVERT) | 31.9 CY | | |
| 0080 | 8245000000-E | 425 | REINFORCING STEEL (CULVERT) | 3,262 LB | | |
| 0081 | 8590000000-E | 876 | RIP RAP, CLASS ** (I) | 45 TON | | |
| 0082 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 225 SY | | |
| 0083 | 8897000000-N | SP | GENERIC STRUCTURE ITEM 16" STEEL PIPE SLEEVE | 2 EA | | |
| ***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) ***** | | | | | | |
| 0084 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 108 LF | | |
| AA1 | | | | | | |
| 0085 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 466 LF | | |
| AA1 | | | | | | |
| 0086 | 0378000000-E | 310 | 24" RC PIPE CULVERTS, CLASS III | 248 LF | | |
| AA1 | | | | | | |
| *** OR *** | | | | | | |
| 0087 | 0378000000-E | 310 | 24" RC PIPE CULVERTS, CLASS III | 156 LF | | |
| AA2 | | | | | | |
| 0088 | 0536000000-E | SP | **** HDPE PIPE CULVERTS (15") | 108 LF | | |
| AA2 | | | | | | |
| 0089 | 0536000000-E | SP | **** HDPE PIPE CULVERTS (18") | 466 LF | | |
| AA2 | | | | | | |
| 0090 | 0536000000-E | SP | **** HDPE PIPE CULVERTS (24") | 92 LF | | |
| AA2 | | | | | | |
| *** OR *** | | | | | | |
| 0091 | 0378000000-E | 310 | 24" RC PIPE CULVERTS, CLASS III | 156 LF | | |
| AA3 | | | | | | |

County : Columbus

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|-------------|--------------|-------|---|-----------|-----------|--------|
| 0092 AA3 | 0540000000-E | SP | **** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15") | 108 LF | | |
| 0093 AA3 | 0540000000-E | SP | **** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18") | 466 LF | | |
| 0094 AA3 | 0540000000-E | SP | **** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24") | 92 LF | | |

**** END SCHEDULE AA ****

1107/Aug01/Q78053.7/D470946700000/E94

Total Amount Of Bid For Entire Project :

Contract No: C 201624

County: COLUMBUS

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General