

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+59.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	15 TON		
0010	0345000000-E	310	24" SIDE DRAIN PIPE	40 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	24 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	20 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0015	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	1,200 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	680 TON		
0018	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	700 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	76 TON		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0026	2253000000-E	840	PIPE COLLARS	0.9 CY		
0027	2264000000-E	840	PIPE PLUGS	0.09 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0029	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2 EA		
0030	3030000000-E	862	STEEL BM GUARDRAIL	487.5 LF		
0031	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0033	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0036	3649000000-E	876	PLAIN RIP RAP, CLASS B	3 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	245 SY		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	31.25 SF		
0039	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	7.188 SF		
0040	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	71 LF		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0042	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
0043	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	10 EA		
0044	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	431 SF		
0045	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0046	4425000000-N	1125	WARNING FLAG SETS	6 EA		
0047	4430000000-N	1130	DRUMS	20 EA		
0048	4446100000-E	SP	BARRICADES (TYPE III)	48 LF		
0049	4455000000-N	1150	FLAGGER	50 MD		
0050	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,623 LF		
0051	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	32 LF		
0052	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	20 EA		
0053	5300000000-E	1505	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (VI)	22 TON		
0054	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	22 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	5378000000-E	1510	12" DI WATER PIPE, PC 350	204 LF		
0056	5423000000-E	1510	**** PE WATER PIPE, SDR ****, *****#WP (3/4", SDR 7, 200#)	38 LF		
0057	5480000000-E	1510	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP	1,510 LB		
0058	5648000000-N	1510	RELOCATE EXISTING WATER METER	2 EA		
0059	5804000000-E	1530	FILL OR REMOVE ABANDONED 12" PIPE, ***** (PVC WATER)	204 LF		
0060	6000000000-E	1605	TEMPORARY SILT FENCE	1,100 LF		
0061	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	115 TON		
0063	6012000000-E	1610	SEDIMENT CONTROL STONE	45 TON		
0064	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0065	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0066	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0067	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0068	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0069	6029000000-E	SP	SAFETY FENCE	200 LF		
0070	6030000000-E	1630	SILT EXCAVATION	100 CY		
0071	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,100 SY		
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0074	6087000000-E	1660	MOWING	1 ACR		
0075	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0076	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0077	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0078	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0079	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0080	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		
STRUCTURE ITEMS						
0081	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+59.50 -L-)	Lump Sum	L.S.	
0082	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+59.50 -L-)	Lump Sum	L.S.	
0083	8161000000-E	420	GROOVING BRIDGE FLOORS	4,599 SF		
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	45.4 CY		
0085	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+59.50 -L-)	Lump Sum	L.S.	
0086	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,568 LB		
0087	8364000000-E	450	HP12X53 STEEL PILES	735 LF		
0088	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (15+59.50 -L-)	Lump Sum	L.S.	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8503000000-E	460	CONCRETE BARRIER RAIL	245.5 LF		
0090	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	185 TON		
0091	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	206 SY		
0092	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0093	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,347.5 LF		
0094	8860000000-N	SP	GENERIC STRUCTURE ITEM DEBRIS REMOVAL	Lump Sum	L.S.	
0095	8892000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	3,670 SF		
0096	8990000000-N	SP	CONTRACT TIME	1,000 DOL		
0833/Jul06/Q41408.828/D424888800000/E96			Total Amount Of Bid For Entire Project :			

C201257
COUNTY: Cumberland

2/16/99

Contract No: C201257
County: Cumberland

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General