

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+00.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	8 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	31 TON		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	60 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	329 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	191 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	27 TON		
0015	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0016	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0017	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
001E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002C	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0021	2253000000-E	840	PIPE COLLARS	0.4 CY		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0023	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	82 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	450 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003C	3649000000-E	876	RIP RAP, CLASS B	6 TON		
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	221 SY		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	192 SF		
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0034	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
003E	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6000000000-E	1605	TEMPORARY SILT FENCE	800 LF		
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0038	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	45 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	60 LF		
0044	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0045	6029000000-E	SP	SAFETY FENCE	350 LF		
0046	6030000000-E	1630	SILT EXCAVATION	150 CY		
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	600 SY		
0048	6042000000-E	1632	1/4" HARDWARE CLOTH	75 LF		
0049	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0050	6087000000-E	1660	MOWING	0.5 ACR		
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
005E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0057 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	224 LF		
*** OR ***						
005E AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	224 LF		
*** OR ***						
005E AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	224 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
006C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+00.00 -L-)	Lump Sum	L.S.	
0061	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (18+00.00 -L-)	Lump Sum	L.S.	
0062	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	38.2 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+00.00 -L-)	Lump Sum	L.S.	
0064	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,632 LB		
006E	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	80,925 LS		
006E	8364000000-E	450	HP12X53 STEEL PILES	910 LF		
0067	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	176.1 LF		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	97 TON		
006E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	108 SY		
007C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0071	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0072	8860000000-N	SP	GENERIC STRUCTURE ITEM GROUTING AND POST-TENSIONING	Lump Sum	L.S.	
0073	8892000000-E	SP	GENERIC STRUCTURE ITEM BRIDGE DECK GRINDING	2,951 SF		
0074	8897000000-N	SP	GENERIC STRUCTURE ITEM FULL-WIDTH PRECAST CONCRETE DECK PANELS	11 EA		

1419/Jul11/Q96201.65/D32577210000/E74

Total Amount Of Bid For Entire Project :

Contract No: C 201501

County: MARTIN

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General