



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY  
GOVERNOR

LYNDO TIPPETT  
SECRETARY

January 4, 2007

**Addendum No. 1**

RE: Contract ID: C201712  
WBS# 5CR.20321.5  
Durham County  
21 Sections of Secondary Roads

**January 16, 2007 Letting**

To Whom It May Concern:

Reference is made to the Sketch Maps and Proposal form recently furnished to you on this project.

The following revisions have been made to the proposal form:

On Page No. 14 the Project Special Provision entitled "Removal of Existing Asphalt Pavement" has been added. Please void Page No. 14 in your proposal and staple the revised Page No.14 thereto.

On Page No. 1 of the Item Sheets, the quantity for line item "4-1245000000-E-SP Shoulder Reconstruction" has been revised. By copy of this addendum, the pay item quantity is hereby increased from 24.58 SMI to 25.4 SMI. Also, on Page No. 1 of the Item Sheets, the quantity for line item "11-1525100000-E-SP Asphalt Concrete Surface Course, Type SF9.5A (Leveling Course)" has been revised. By copy of this addendum, the pay item quantity is hereby reduced from 146 Ton to 71 Ton. The Contractor's bid price must be based on these revised pay item quantities. The Contract will be prepared accordingly.

On Page No. 2 of the Item Sheets the following new line item is hereby added: "30-1520000000-E-SP Asphalt Concrete Surface Course, Type S9.5B (Leveling Course)" Quantity = 75 Ton. The Contractor's bid price shall include this new pay item. The Contract will be prepared accordingly.

The Table of Contents has been revised to reflect the above noted change. Please void the Table of Contents in your proposal and staple the revised Table of Contents thereto.

**MAILING ADDRESS:**  
NC DEPARTMENT OF TRANSPORTATION  
DESIGN SERVICES UNIT  
1591 MAIL SERVICE CENTER  
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128  
FAX: 919-250-4119

WEBSITE: [WWW.DOH.DOT.STATE.NC.US](http://WWW.DOH.DOT.STATE.NC.US)

**LOCATION:**  
CENTURY CENTER COMPLEX  
ENTRANCE B2  
1020 BIRCH RIDGE DRIVE  
RALEIGH NC

Page 2

January 4, 2007

Addendum No. 1

RE: Contract ID: C201712

WBS# 5CR.20321.5

Durham County

The following revisions have been made to the Sketch Maps:

On Sheet No. 8 the Summary of Quantities has been revised to reflect the above noted changes. Please void Sheet No. 8 in your Sketch Maps and staple the revised Sheet No. 8 thereto.

On Sheet No. 10 the Pavement Schedule was revised for Symbol "V2". Please void Sheet No. 10 in your Sketch Maps and staple the revised Sheet No. 10 thereto.

The Expedite File has been updated to reflect these revisions. Please download the Expedite Addendum File and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,



R. A. Garris, PE  
Contract Officer

RAG/jag/blr  
Attachment

cc: Mr. W. S. Varnedoe, PE  
Mr. E. C. Powell, PE  
Mr. J. Wally Bowman, PE  
Ms. D. M. Barbour, PE  
Mr. Art McMillan, PE  
Mr. Victor Barbour, PE  
Mr. Robert Memory  
Mr. Mark Staley (2)  
Mr. R. E. Davenport, Jr., PE  
Ms. Norma Smith  
Ms. Marsha Byrd  
Mr. Ronnie Higgins  
Ms. Taylor Mishoe  
Project Files (2)

**TABLE OF CONTENTS**

**COVER SHEET  
PROPOSAL SHEETS**

<b><u>PROJECT SPECIAL PROVISIONS</u></b>	(WHITE SHEETS)	<i>PAGE No.</i>
Contract Time and Liquidated Damages.....		1
Intermediate Contract Time.....		1-2
Prosecution of Work.....		2-3
Railroad Grade Crossing.....		3
Major Contract Items.....		3
Specialty Items.....		3
Posted Weight Limits.....		3
Schedule of Estimated Completion Progress.....		4
Minority and Women Business .....		4-12
Fuel Price Adjustment.....		13
Outsourcing Outside U.S.A.....		14
Act of God.....		14
Removal of Existing Asphalt Pavement .....		14
Roadway.....		15-23
Traffic Control.....		24-31
Erosion Control.....		32
Sketch Maps		

**STANDARD SPECIAL PROVISIONS** (YELLOW SHEETS)

Availability of Funds – Termination of Contracts.....	1
General Seed Specification for Seed Quality.....	2-4
Errata.....	5-7
Plant and Pest Quarantines.....	8
Minimum Wage .....	9

Item Sheet

Signature Sheet (Bid Acceptance by Department)

**OUTSOURCING OUTSIDE THE USA:**

(9-21-04)

RG 95

All work on consultant contracts, services contracts, and construction contracts shall be performed in the United States of America. No work shall be outsourced outside of the United States of America.

*Outsourcing* for the purpose of this provision is defined as the practice of subcontracting labor, work, services, staffing, or personnel to entities located outside of the United States.

The North Carolina Secretary of Transportation shall approve exceptions to this provision in writing.

**ACT OF GOD**

(12-19-06)

RG 151

Revise the 2006 Standard Specifications as follows:

Page 1-69, 107-18 Contractor's Responsibility for Work, in the first paragraph, last sentence, replace the word *legally* with the word *contractually*.

**REMOVAL OF EXISTING ASPHALT PAVEMENT:**

The Contractor shall perform the removal of existing asphalt pavement in accordance with Section 250 of the specifications and the following:

Where the depth of existing pavement to be removed is less than the total depth of proposed pavement, the Contractor shall remove additional material from beneath the existing pavement to a depth sufficient that the resulting top surface elevation of the proposed pavement will match the final surface elevation of the other typical sections being constructed on Map 15. This additional material removed shall be disposed of in waste areas furnished by the Contractor.

No measurement will be made of the additional material removed from under the existing pavement in order that the surface elevation will match as required above, as the cost of this work will be considered incidental to the work being paid for at the contract unit price per square yard for "Removal of Existing Asphalt Pavement".

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	5,292 SY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	701 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	25.4 SMI		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1" TO 3")	40,978 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	8,070 SY		
0007	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,225 TON		
0008	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	762 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	28,290 TON		
0010	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	1,035 TON		
0011	1525100000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)	71 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,858 TON		
0013	1704000000-E	SP	PATCHING EXISTING PAVEMENT	2,370 TON		
0014	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0015	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0016	2830000000-N	858	ADJUSTMENT OF MANHOLES	143 EA		
0017	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	53 EA		
0018	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	155,221 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	203,241 LF		
0020	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	2,620 LF		
0021	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	500 LF		
0022	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,775 LF		
0023	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	107 EA		
0024	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	282 EA		
0025	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,000 LF		
0026	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,991 EA		
0027	6084000000-E	1660	SEEDING & MULCHING	19 ACR		
0028	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	9,400 LF		
0029	7456000000-E	1726	LEAD-IN CABLE (***** (18-4)	2,000 LF		
0030	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	75 TON		

1053/Jan04/Q471107.4/D9255220000/E30

Total Amount Of Bid For Entire Project :