

PROJECT SPECIAL PROVISION

(10-18-95)

1

PERMITS

The Contractor's attention is directed to the following permits which have been issued to the Department of Transportation by the authority granting the permit.

<u>PERMIT</u>	<u>AUTHORITY GRANTING THE PERMIT</u>
Dredge and Fill and/or Work in Navigable Waters (404)	U. S. Army Corps of Engineers
Water Quality (401)	Division of Environmental Management, DENR State of North Carolina

The Contractor shall comply with all applicable permit conditions during construction of this project. Those conditions marked by * are the responsibility of the department and the Contractor has no responsibility in accomplishing those conditions.

Agents of the permitting authority will periodically inspect the project for adherence to the permits.

The Contractor's attention is also directed to Articles 107-10 and 107-14 of the *Standard Specifications* and the following:

Should the Contractor propose to utilize construction methods (such as temporary structures or fill in waters and/or wetlands for haul roads, work platforms, cofferdams, etc.) not specifically identified in the permit (individual, general, or nationwide) authorizing the project it shall be the Contractor's responsibility to coordinate with the Engineer to determine what, if any, additional permit action is required. The Contractor shall also be responsible for initiating the request for the authorization of such construction method by the permitting agency. The request shall be submitted through the Engineer. The Contractor shall not utilize the construction method until it is approved by the permitting agency. The request normally takes approximately 60 days to process; however, no extensions of time or additional compensation will be granted for delays resulting from the Contractor's request for approval of construction methods not specifically identified in the permit.

Where construction moratoriums are contained in a permit condition which restricts the Contractor's activities to certain times of the year, those moratoriums will apply only to the portions of the work taking place in the waters or wetlands provided that activities outside those areas is done in such a manner as to not affect the waters or wetlands.

U.S. ARMY CORPS OF ENGINEERS
WILMINGTON DISTRICT

RECEIVED

JUL 31 2006

Action ID. 200531495-1496

County: Buncombe


177

USGS Quad: Black Mountain

DIVISION OF HIGHWAYS
OFFICE OF NATURAL ENVIRONMENT

GENERAL PERMIT (REGIONAL AND NATIONWIDE) VERIFICATION

Property Owner / Authorized Agent: NC Department of Transportation, Project Development and Environmental Analysis Branch, Attn: Gregory J. Thorpe, Director
Address: 1548 Mail Service Center
Raleigh, North Carolina
27699-1548



Telephone No.: 919-733-3141

Size and location of property (water body, road name/number, town, etc.): Bridge No. 653 on SR 2804 and Bridge No. 654 over Sand Branch Creek on SR 2786, south of Black Mountain, TIP B-3119.

Description of projects area and activity: Replace Bridge No. 653 with a single span, 130-foot long steel girder bridge on new alignment to the west of the existing structure. Construct a 0.05-acre, temporary rock work pad on the north bank of the river to set drill piers for the new bridge. Replace Bridge No. 654 with a single span, prefabricated bottomless arch culvert on the existing alignment. Construct a 0.001-acre, temporary impervious dike on the west bank to facilitate culvert construction. Traffic will be detoured off site using existing routes. A moratorium on in-water construction activities will be observed from 1 November to 15 April of any year. **SPECIAL CONDITION: All conditions of the attached NC Wildlife Resources Commission letter of July 3, 2006 are hereby incorporated as special conditions of this permit. Herbaceous riparian vegetation will be reestablished within 15 working days of ground disturbing activities.**

Applicable Law: Section 404 (Clean Water Act, 33 USC 1344)
 Section 10 (Rivers and Harbors Act, 33 USC 403)
Authorization: Regional General Permit Number:
Nationwide Permit Number: 33

Your work is authorized by the above referenced permit provided it is accomplished in strict accordance with the attached conditions and your submitted plans. Any violation of the attached conditions or deviation from your submitted plans may subject the permittee to a stop work order, a restoration order and/or appropriate legal action.

This verification will remain valid until the Nationwide Permit (NWP) is modified, reissued or revoked prior to March 18, 2007. It is incumbent upon you to remain informed of changes to the NWPs. We will issue a public notice when the NWP's are reissued. Furthermore, if you commence or are under contract to commence this activity before the date that the relevant NWP is modified or revoked, you will have twelve (12) months from the date of the modification or revocation of the NWP to complete the activity under the present terms and conditions of this NWP. If, prior to the expiration date identified below, the authorized NWP is reissued and/or modified, this verification will remain valid until the expiration date identified below, provided it complies with all new and/or modified terms and conditions. The District Engineer may, at any time, exercise his discretionary authority to modify, suspend or revoke a case specific activity's authorization under any NWP.

Activities subject to Section 404 (as indicated above) may also require an individual Section 401 Water Quality Certification. You should contact the NC Division of Water Quality (telephone (919) 733-1786) to determine Section 401 requirements.

For activities occurring within the twenty coastal counties subject to regulation under the Coastal Area Management Act (CAMA), prior to beginning work you must contact the N.C. Division of Coastal Management.

This Department of the Army verification does not relieve the permittee of the responsibility to obtain any other required Federal, State or local approvals/permits.

If there are any questions regarding this verification, any of the conditions of the Permit, or the Corps of Engineers regulatory program, please contact Mr. Steven Lund at telephone (828) 271-7980 x 223.

Corps Regulatory Official: Steven Lund *SWL*

Date: 7/24/2006

Expiration Date of Verification: 3/18/2007

Determination of Jurisdiction:

Based on preliminary information, there appear to be waters of the US within the above described project area. This preliminary determination is not an appealable action under the Regulatory Program Administrative Appeal Process (Reference 33 CFR Part 331).

- There are Navigable Waters of the United States within the above described project area subject to the permit requirements of Section 10 of the Rivers and Harbors Act and Section 404 of the Clean Water Act. Unless there is a change in the law or our published regulations, this determination may be relied upon for a period not to exceed five years from the date of this notification.
- There are waters of the US and/or wetlands within the above described project area subject to the permit requirements of Section 404 of the Clean Water Act (CWA)(33 USC § 1344). Unless there is a change in the law or our published regulations, this determination may be relied upon for a period not to exceed five years from the date of this notification.
- The jurisdictional areas within the above described project area have been identified under a previous action. Please reference jurisdictional determination issued _____. Action ID _____

Basis of Jurisdictional Determination: _____

Corps Regulatory Official:

Date:

SURVEY PLATS, FIELD SKETCH, WETLAND DELINEATION FORMS, PROJECT PLANS, ETC., MUST BE ATTACHED TO THE FILE COPY OF THIS FORM, IF REQUIRED OR AVAILABLE.

Action ID Number: 200531495-1496, TIP B-3119 179

County: Buncombe

Permittee: NCDOT, PD&EA, Attn: Gregory J. Thorpe, Director

Date Permit Issued: 7/24/2006, NW 33

Project Manager: Lund

✗ Upon completion of the activity authorized by this permit and any mitigation required by the permit, sign this certification and return it to the following address:


US ARMY CORPS OF ENGINEERS
WILMINGTON DISTRICT
ASHEVILLE REGULATORY FIELD OFFICE
151 PATTON AVENUE, ROOM 208
ASHEVILLE, NORTH CAROLINA 28801-5006

Please note that your permitted activity is subject to a compliance inspection by a U. S. Army Corps of Engineers representative. If you fail to comply with this permit you are subject to permit suspension, modification, or revocation.

I hereby certify that the work authorized by the above referenced permit has been completed in accordance with the terms and condition of the said permit, and required mitigation was completed in accordance with the permit conditions.

Signature of Permittee

Date



☒ North Carolina Wildlife Resources Commission ☒

Richard B. Hamilton, Executive Director

TO: Steve Lund, NCDOT Coordinator
Asheville Regulatory Field Office, USACE

FROM: Marla Chambers, Western NCDOT Permit Coordinator *Marla Chambers*
Habitat Conservation Program, NCWRC

DATE: July 3, 2006

SUBJECT: Review of the Categorical Exclusion document and Section 404 and 401 Permit application by NCDOT to replace Bridge No. 653 on SR 2804 over the Broad River and Bridge No. 654 on SR 2786 over Sand Branch, Buncombe County, North Carolina. TIP No. B-3119.

North Carolina Department of Transportation (NCDOT) has requested a Section 404 Permit from the U.S. Army Corps of Engineers (USACE) and a 401 Water Quality Certification from the Division of Water Quality (NCDWQ). Staff biologists with the North Carolina Wildlife Resources Commission (NCWRC) have reviewed the information provided. These comments are provided in accordance with the provisions of the National Environmental Policy Act (42 U.S.C. 4332(2)(c)) and the Fish and Wildlife Coordination Act (48 Stat. 401, as amended; 16 U.S.C. 661-667d).

The NCDOT proposes to replace Bridge No. 653 on SR 2804 over the Broad River and Bridge No. 654 on SR 2786 over Sand Branch. Bridge No. 653 will be replaced with a bridge, with the south end of the bridge in the same location and the north end shifted approximately 130 feet to the west. Bridge No. 654 will be replaced on existing alignment with a single span prefabricated arch structure (bottomless culvert). Traffic will be detoured offsite. NCDOT proposes to temporarily impact 118 linear feet (0.05 acres) of the Broad River for a work pad at Bridge No. 653 and 46 linear feet (0.001 acres) of Sand Branch due to the installation of an impervious dike at Bridge No. 654. An unnamed tributary to the Broad River is in the project study area; however, it appears there will be no impacts to it.

Broad River and Sand Branch, both Class C Trout waters, may support wild trout populations in the area. NCDOT indicates they will adhere to a moratorium prohibiting in-stream work and land disturbance within the 25-foot trout buffer from November 1 through April 15 and use Design Standards for Sensitive Watersheds. Although the current standard trout moratorium dates differ slightly, we will concur with the above mentioned dates that we recommended previously. We appreciate these minimization efforts and others including spanning the river with no bents in the water and the use of a bottomless culvert.

NCWRC can concur with the issuance of Section 404 and 401 permits provided that the following conditions are implemented:

1. Sediment and erosion control measures should adhere to the Design Standards for Sensitive Watersheds and be strictly maintained until project completion.
2. Temporary or permanent herbaceous vegetation should be planted on all bare soil as soon as possible and within 15 calendar days of ground disturbing activities to provide long-term erosion control.
3. Tall fescue should not be used in riparian areas. We encourage NCDOT to utilize onsite native vegetation and materials for streambank stabilization when practicable. Erosion control matting should be used in riparian areas, instead of straw mulch.
4. Stormwater, including deck drainage, should be directed to buffer areas or retention basins and should not be routed directly into the stream.
5. Only clean, sediment-free rock should be used as temporary fill, and should be removed without excessive disturbance of the natural stream bottom when construction is completed.
6. Discharge of materials into the stream from demolition of the old bridge should be avoided as much as practicable. Any materials that inadvertently reach the stream should be removed.
7. The natural dimension, pattern, and profile of the stream above and below the crossing should not be modified by widening the stream channel or changing the depth of the stream.
8. Removal of vegetation in riparian areas should be minimized. Native trees and shrubs should be planted along the streambanks to reestablish the riparian zone and to provide long-term erosion control.
9. Grading and backfilling should be minimized, and tree and shrub growth should be retained if possible to ensure long term availability of shoreline cover for fish and wildlife. Backfill materials should be obtained from upland sites.


10. Riprap placed for bank stabilization should be limited to the streambank below the high water mark, and vegetation should be used for stabilization above the high water elevation.
11. If concrete will be used during construction, work must be accomplished so that wet (uncured) concrete does not contact surface waters. This will lessen the chance of altering the water chemistry and causing a fish kill.
12. Discharging hydroseeding mixtures and washing out hydroseeders and other equipment in or adjacent to surface waters is strictly prohibited.
13. Heavy equipment should be operated from the bank rather than in the stream channel whenever possible in order to minimize sedimentation and reduce the likelihood of introducing other pollutants into the stream. All mechanized equipment operated near surface waters should be inspected and maintained regularly to prevent contamination of surface waters from fuels, lubricants, hydraulic fluids or other toxic materials.
14. The existing roadway that is to be eliminated should be removed back to original ground elevations and the natural floodplain elevations and functions should be restored. Disturbed areas should be seeded or mulched to stabilize the soil and native tree species should be planted with a spacing of not more than 10'x10'.

Thank you for the opportunity to review and comment on this project. If you have any questions regarding these comments, please contact me at (704) 545-3841.

cc: Marella Buncick, USFWS
Brian Wrenn, NCDWQ
Elizabeth Lusk, NCDOT
Carla Dagnino, NCDOT

NATIONWIDE PERMIT 33
DEPARTMENT OF THE ARMY
CORPS OF ENGINEERS
FINAL NOTICE OF ISSUANCE AND MODIFICATION OF NATIONWIDE PERMITS
FEDERAL REGISTER
AUTHORIZED MARCH 18, 2002

Temporary Construction, Access and Dewatering: Temporary structures, work and discharges, including cofferdams, necessary for construction activities or access fills or dewatering of construction sites; provided that the associated primary activity is authorized by the Corps of Engineers or the U.S. Coast Guard (USCG), or for other construction activities not subject to the Corps or USCG regulations. Appropriate measures must be taken to maintain near normal downstream flows and to minimize flooding. Fill must be of materials, and placed in a manner, that will not be eroded by expected high flows. The use of dredged material may be allowed if it is determined by the District Engineer that it will not cause more than minimal adverse effects on aquatic resources. Temporary fill must be entirely removed to upland areas, or dredged material returned to its original location, following completion of the construction activity, and the affected areas must be restored to the pre-project conditions. Cofferdams cannot be used to dewater wetlands or other aquatic areas so as to change their use. Structures left in place after cofferdams are removed require a section 10 permit if located in navigable waters of the United States. (See 33 CFR part 322). The permittee must notify the District Engineer in accordance with the "Notification" general condition. The notification must also include a restoration plan of reasonable measures to avoid and minimize adverse effects to aquatic resources. The District Engineer will add special conditions, where necessary, to ensure environmental adverse effects is minimal. Such conditions may include: Limiting the temporary work to the minimum necessary; requiring seasonal restrictions; modifying the restoration plan; and requiring alternative construction methods (e.g., construction mats in wetlands where practicable.). (Sections 10 and 404)



NATIONWIDE PERMIT GENERAL CONDITIONS

The following General Conditions must be followed in order for any authorization by a NWP to be valid:

1. Navigation. No activity may cause more than a minimal adverse effect on navigation.
2. Proper Maintenance. Any structure or fill authorized shall be properly maintained, including maintenance to ensure public safety.
3. Soil Erosion and Sediment Controls. Appropriate soil erosion and sediment controls must be used and maintained in effective operating condition during construction, and all exposed soil and other fills, as well as any work below the ordinary high water mark or high tide line, must be permanently stabilized at the earliest practicable date. Permittees are encouraged to perform work within waters of the United States during periods of low-flow or no-flow.
4. Aquatic Life Movements. No activity may substantially disrupt the necessary life-cycle movements of those species of aquatic life indigenous to the waterbody, including those species that normally migrate through the area, unless the activity's primary purpose is to impound water. Culverts placed in streams must be installed to maintain low flow conditions.
5. Equipment. Heavy equipment working in wetlands must be placed on mats, or other measures must be taken to minimize soil disturbance.
6. Regional and Case-By-Case Conditions. The activity must comply with any regional conditions that may have been added by the Division Engineer (see 33 CFR 330.4(e)) and with any case specific conditions added by the Corps or by the state or tribe in its Section 401 Water Quality Certification and Coastal Zone Management Act consistency determination.
7. Wild and Scenic Rivers. No activity may occur in a component of the National Wild and Scenic River System; or in a river officially designated by Congress as a 'study river" for possible inclusion in the system, while the river is in an official study status; unless the appropriate Federal agency, with direct management responsibility for such river, has determined in writing that the proposed activity will not adversely affect the Wild and Scenic River designation, or study status. Information on Wild and Scenic Rivers may be obtained from the appropriate Federal land management agency in the area (e.g., National Park Service, U.S. Forest Service, Bureau of Land Management, U.S. Fish and Wildlife Service).
8. Tribal Rights. No activity or its operation may impair reserved tribal rights, including, but not limited to, reserved water rights and treaty fishing and hunting rights.
9. Water Quality.

a. In certain states and tribal lands an individual 401 Water Quality Certification must be obtained or waived (See 33 CFR 330.4(c)).

b. For NWP's 12, 14, 17, 18, 32, 39, 40, 42, 43, and 44, where the state or tribal 401 certification (either generically or individually) does not require or approve water quality management measures, the permittee must provide water quality management measures that will ensure that the authorized work does not result in more than minimal degradation of water quality (or the Corps determines that compliance with state or local standards, where applicable, will ensure no more than minimal adverse effect on water quality). An important component of water quality management includes stormwater management that minimizes degradation of the downstream aquatic system, including water quality (refer to General Condition 21 for stormwater management requirements). Another important component of water quality management is the establishment and maintenance of vegetated buffers next to open waters, including streams (refer to General Condition 19 for vegetated buffer requirements for the NWP's).

This condition is only applicable to projects that have the potential to affect water quality. While appropriate measures must be taken, in most cases it is not necessary to conduct detailed studies to identify such measures or to require monitoring.

10. Coastal Zone Management. In certain states, an individual state coastal zone management consistency concurrence must be obtained or waived (see 33 CFR 330.4(d)).

11. Endangered Species.

a. No activity is authorized under any NWP which is likely to jeopardize the continued existence of a threatened or endangered species or a species proposed for such designation, as identified under the Federal Endangered Species Act (ESA), or which will destroy or adversely modify the critical habitat of such species. Non-federal permittees shall notify the District Engineer if any listed species or designated critical habitat might be affected or is in the vicinity of the project, or is located in the designated critical habitat and shall not begin work on the activity until notified by the District Engineer that the requirements of the ESA have been satisfied and that the activity is authorized. For activities that may affect Federally-listed endangered or threatened species or designated critical habitat, the notification must include the name(s) of the endangered or threatened species that may be affected by the proposed work or that utilize the designated critical habitat that may be affected by the proposed work. As a result of formal or informal consultation with the FWS or NMFS the District Engineer may add species-specific regional endangered species conditions to the NWP's.

b. Authorization of an activity by a NWP does not authorize the "take" of a threatened or endangered species as defined under the ESA. In the absence of separate authorization (e.g., an ESA Section 10 Permit, a Biological Opinion with "incidental take" provisions, etc.) from the USFWS or the NMFS, both lethal and non-lethal "takes" of protected species are in violation of the ESA. Information on the location of threatened and endangered species and their critical habitat can be obtained directly from the offices of the USFWS and NMFS or their World Wide

Web pages at <http://www.fws.gov/r9endspp/endspp.html> and <http://www.nfms.noaa.gov/protres/overview/es.html> respectively.

12. Historic Properties. No activity that may affect historic properties listed, or eligible for listing, in the National Register of Historic Places is authorized, until the District Engineer has complied with the provisions of 33 CFR part 325, Appendix C. The prospective permittee must notify the District Engineer if the authorized activity may affect any historic properties listed, determined to be eligible, or which the prospective permittee has reason to believe may be eligible for listing on the National Register of Historic Places, and shall not begin the activity until notified by the District Engineer that the requirements of the National Historic Preservation Act have been satisfied and that the activity is authorized. Information on the location and existence of historic resources can be obtained from the State Historic Preservation Office and the National Register of Historic Places (see 33 CFR 330.4(g)). For activities that may affect historic properties listed in, or eligible for listing in, the National Register of Historic Places, the notification must state which historic property may be affected by the proposed work or include a vicinity map indicating the location of the historic property.

✕ 13. Notification.

a. Timing; where required by the terms of the NWP, the prospective permittee must notify the District Engineer with a preconstruction notification (PCN) as early as possible. The District Engineer must determine if the notification is complete within 30 days of the date of receipt and can request additional information necessary to make the PCN complete only once. However, if the prospective permittee does not provide all of the requested information, then the District Engineer will notify the prospective permittee that the notification is still incomplete and the PCN review process will not commence until all of the requested information has been received by the District Engineer. The prospective permittee shall not begin the activity:

1. Until notified in writing by the District Engineer that the activity may proceed under the NWP with any special conditions imposed by the District or Division Engineer; or

2. If notified in writing by the District or Division Engineer that an Individual Permit is required; or

3. Unless 45 days have passed from the District Engineer's receipt of the complete notification and the prospective permittee has not received written notice from the District or Division Engineer. Subsequently, the permittee's right to proceed under the NWP may be modified, suspended, or revoked only in accordance with the procedure set forth in 33 CFR 330.5(d)(2).

b. Contents of Notification: The notification must be in writing and include the following information:

1. Name, address and telephone numbers of the prospective permittee;

2. Location of the proposed project;

3. Brief description of the proposed project; the project's purpose; direct and indirect adverse environmental effects the project would cause; any other NWP(s), Regional General Permit(s), or Individual Permit(s) used or intended to be used to authorize any part of the proposed project or any related activity. Sketches should be provided when necessary to show that the activity complies with the terms of the NWP (Sketches usually clarify the project and when provided result in a quicker decision.);

4. For NWPs 7, 12, 14, 18, 21, 34, 38, 39, 40, 41, 42, and 43, the PCN must also include a delineation of affected special aquatic sites, including wetlands, vegetated shallows (e.g., submerged aquatic vegetation, seagrass beds), and riffle and pool complexes (see paragraph 13(f));

5. For NWP 7 (Cutfall Structures and Maintenance), the PCN must include information regarding the original design capacities and configurations of those areas of the facility where maintenance dredging or excavation is proposed;

6. For NWP 14 (Linear Transportation Projects), the PCN must include a compensatory mitigation proposal to offset permanent losses of waters of the US and a statement describing how temporary losses of waters of the US will be minimized to the maximum extent practicable;

7. For NWP 21 (Surface Coal Mining Activities), the PCN must include an Office of Surface Mining (OSM) or state-approved mitigation plan, if applicable. To be authorized by this NWP, the District Engineer must determine that the activity complies with the terms and conditions of the NWP and that the adverse environmental effects are minimal both individually and cumulatively and must notify the project sponsor of this determination in writing;

8. For NWP 27 (Stream and Wetland Restoration Activities), the PCN must include documentation of the prior condition of the site that will be reverted by the permittee;

9. For NWP 29 (Single-Family Housing), the PCN must also include:

i. Any past use of this NWP by the Individual Permittee and/or the permittee's spouse;

ii. A statement that the single-family housing activity is for a personal residence of the permittee;

iii. A description of the entire parcel, including its size, and a delineation of wetlands. For the purpose of this NWP, parcels of land measuring $\frac{1}{4}$ -acre or less will not require a formal on-site delineation. However, the applicant shall provide an indication of where the wetlands are and the amount of wetlands that exists on the property. For parcels greater than $\frac{1}{4}$ -acre in size, formal wetland delineation must be prepared in accordance with the current

method required by the Corps. (See paragraph 13(f));

iv. A written description of all land (including, if available, legal descriptions) owned by the prospective permittee and/or the prospective permittee's spouse, within a one mile radius of the parcel, in any form of ownership (including any land owned as a partner, corporation, joint tenant, co-tenant, or as a tenant-by-the-entirety) and any land on which a purchase and sale agreement or other contract for sale or purchase has been executed;

10. For NWP 31 (Maintenance of Existing Flood Control Facilities), the prospective permittee must either notify the District Engineer with a PCN prior to each maintenance activity or submit a five-year (or less) maintenance plan. In addition, the PCN must include all of the following:

i. Sufficient baseline information identifying the approved channel depths and configurations and existing facilities. Minor deviations are authorized, provided the approved flood control protection or drainage is not increased;

ii. A delineation of any affected special aquatic sites, including wetlands; and,

iii. Location of the dredged material disposal site;

11. For NWP 33 (Temporary Construction, Access, and Dewatering), the PCN must also include a restoration plan of reasonable measures to avoid and minimize adverse effects to aquatic resources;

12. For NWPs 39, 43 and 44, the PCN must also include a written statement to the District Engineer explaining how avoidance and minimization for losses of waters of the US were achieved on the project site;

13. For NWP 39 and NWP 42, the PCN must include a compensatory mitigation proposal to offset losses of waters of the US or justification explaining why compensatory mitigation should not be required. For discharges that cause the loss of greater than 300 linear feet of an intermittent stream bed, to be authorized, the District Engineer must determine that the activity complies with the other terms and conditions of the NWP, determine adverse environmental effects are minimal both individually and cumulatively, and waive the limitation on stream impacts in writing before the permittee may proceed;

14. For NWP 40 (Agricultural Activities), the PCN must include a compensatory mitigation proposal to offset losses of waters of the US. This NWP does not authorize the relocation of greater than 300 linear feet of existing serviceable drainage ditches constructed in non-tidal streams unless, for drainage ditches constructed in intermittent nontidal streams, the District Engineer waives this criterion in writing, and the District Engineer has determined that the project complies with all terms and conditions of this NWP, and that any adverse impacts of the project on the aquatic environment are minimal, both individually and cumulatively;

15. For NWP 43 (Stormwater Management Facilities), the PCN must include, for the construction of new stormwater management facilities, a maintenance plan (in accordance with state and local requirements, if applicable) and a compensatory mitigation proposal to offset losses of waters of the US. For discharges that cause the loss of greater than 300 linear feet of an intermittent stream bed, to be authorized, the District Engineer must determine that the activity complies with the other terms and conditions of the NWP, determine adverse environmental effects are minimal both individually and cumulatively, and waive the limitation on stream impacts in writing before the permittee may proceed;

16. For NWP 44 (Mining Activities), the PCN must include a description of all waters of the US adversely affected by the project, a description of measures taken to minimize adverse effects to waters of the US, a description of measures taken to comply with the criteria of the NWP, and a reclamation plan (for all aggregate mining activities in isolated waters and non-tidal wetlands adjacent to headwaters and any hard rock/mineral mining activities);

17. For activities that may adversely affect Federally-listed endangered or threatened species, the PCN must include the name(s) of those endangered or threatened species that may be affected by the proposed work or utilize the designated critical habitat that may be affected by the proposed work; and

18. For activities that may affect historic properties listed in, or eligible for listing in, the National Register of Historic Places, the PCN must state which historic property may be affected by the proposed work or include a vicinity map indicating the location of the historic property.

c. Form of Notification: The standard Individual Permit application form (Form ENG 4345) may be used as the notification but must clearly indicate that it is a PCN and must include all of the information required in (b) (1)-(18) of General Condition 13. A letter containing the requisite information may also be used.

d. District Engineer's Decision: In reviewing the PCN for the proposed activity, the District Engineer will determine whether the activity authorized by the NWP will result in more than minimal individual or cumulative adverse environmental effects or may be contrary to the public interest. The prospective permittee may submit a proposed mitigation plan with the PCN to expedite the process. The District Engineer will consider any proposed compensatory mitigation the applicant has included in the proposal in determining whether the net adverse environmental effects to the aquatic environment of the proposed work are minimal. If the District Engineer determines that the activity complies with the terms and conditions of the NWP and that the adverse effects on the aquatic environment are minimal, after considering mitigation, the District Engineer will notify the permittee and include any conditions the District Engineer deems necessary. The District Engineer must approve any compensatory mitigation proposal before the permittee commences work. If the prospective permittee is required to submit a compensatory mitigation proposal with the PCN, the proposal may be either conceptual or detailed. If the prospective permittee elects to submit a compensatory mitigation plan with the PCN, the District Engineer will expeditiously review the proposed compensatory mitigation

plan. The District Engineer must review the plan within 45 days of receiving a complete PCN and determine whether the conceptual or specific proposed mitigation would ensure no more than minimal adverse effects on the aquatic environment. If the net adverse effects of the project on the aquatic environment (after consideration of the compensatory mitigation proposal) are determined by the District Engineer to be minimal, the District Engineer will provide a timely written response to the applicant. The response will state that the project can proceed under the terms and conditions of the NWP.

If the District Engineer determines that the adverse effects of the proposed work are more than minimal, then the District Engineer will notify the applicant either:

1. That the project does not qualify for authorization under the NWP and instruct the applicant on the procedures to seek authorization under an Individual Permit;

2. that the project is authorized under the NWP subject to the applicant's submission of a mitigation proposal that would reduce the adverse effects on the aquatic environment to the minimal level; or

3. that the project is authorized under the NWP with specific modifications or conditions. Where the District Engineer determines that mitigation is required to ensure no more than minimal adverse effects occur to the aquatic environment, the activity will be authorized within the 45-day PCN period. The authorization will include the necessary conceptual or specific mitigation or a requirement that the applicant submit a mitigation proposal that would reduce the adverse effects on the aquatic environment to the minimal level. When conceptual mitigation is included, or a mitigation plan is required under item (2) above, no work in waters of the US will occur until the District Engineer has approved a specific mitigation plan.

e. Agency Coordination: The District Engineer will consider any comments from Federal and state agencies concerning the proposed activity's compliance with the terms and conditions of the NWPs and the need for mitigation to reduce the project's adverse environmental effects to a minimal level.

For activities requiring notification to the District Engineer that result in the loss of greater than $\frac{1}{2}$ -acre of waters of the US, the District Engineer will provide immediately (e.g., via facsimile transmission, overnight mail, or other expeditious manner) a copy to the appropriate Federal or state offices (USFWS, state natural resource or water quality agency, EPA, State Historic Preservation Officer (SHPO), and, if appropriate, the NMFS). With the exception of NWP 37, these agencies will then have 10 calendar days from the date the material is transmitted to telephone or fax the District Engineer notice that they intend to provide substantive, site-specific comments. If so contacted by an agency, the District Engineer will wait an additional 15 calendar days before making a decision on the notification. The District Engineer will fully consider agency comments received within the specified time frame, but will provide no response to the resource agency, except as provided below. The District Engineer will indicate in the administrative record associated with each notification that the resource agencies' concerns were considered. As required by section 305(b)(4)(B) of the Magnuson-Stevens

Fishery Conservation and Management Act, the District Engineer will provide a response to NMFS within 30 days of receipt of any Essential Fish Habitat conservation recommendations. Applicants are encouraged to provide the Corps multiple copies of notifications to expedite agency notification.

f. Wetland Delineations: Wetland delineations must be prepared in accordance with the current method required by the Corps (For NWP 29 see paragraph (b)(9)(iii) for parcels less than $\frac{1}{4}$ -acre in size). The permittee may ask the Corps to delineate the special aquatic site. There may be some delay if the Corps does the delineation. Furthermore, the 45-day period will not start until the wetland delineation has been completed and submitted to the Corps, where appropriate.

*14. Compliance Certification. Every permittee who has received NWP verification from the Corps will submit a signed certification regarding the completed work and any required mitigation. The certification will be forwarded by the Corps with the authorization letter and will include:

- a. A statement that the authorized work was done in accordance with the Corps authorization, including any general or specific conditions;
- b. A statement that any required mitigation was completed in accordance with the permit conditions; and
- c. The signature of the permittee certifying the completion of the work and mitigation.

15. Use of Multiple Nationwide Permits. The use of more than one NWP for a single and complete project is prohibited, except when the acreage loss of waters of the US authorized by the NWPs does not exceed the acreage limit of the NWP with the highest specified acreage limit (e.g. if a road crossing over tidal waters is constructed under NWP 14, with associated bank stabilization authorized by NWP 13, the maximum acreage loss of waters of the US for the total project cannot exceed $\frac{1}{3}$ -acre).

16. Water Supply Intakes. No activity, including structures and work in navigable waters of the US or discharges of dredged or fill material, may occur in the proximity of a public water supply intake except where the activity is for repair of the public water supply intake structures or adjacent bank stabilization.

17. Shellfish Beds. No activity, including structures and work in navigable waters of the US or discharges of dredged or fill material, may occur in areas of concentrated shellfish populations, unless the activity is directly related to a shellfish harvesting activity authorized by NWP 4.

18. Suitable Material. No activity, including structures and work in navigable waters of the US or discharges of dredged or fill material, may consist of unsuitable material (e.g., trash, debris, car bodies, asphalt, etc.) and material used for construction or discharged must be free

from toxic pollutants in toxic amounts (see section 307 of the CWA).

19. Mitigation. The District Engineer will consider the factors discussed below when determining the acceptability of appropriate and practicable mitigation necessary to offset adverse effects on the aquatic environment that are more than minimal.

a. The project must be designed and constructed to avoid and minimize adverse effects to waters of the US to the maximum extent practicable at the project site (i.e., on site).

b. Mitigation in all its forms (avoiding, minimizing, rectifying, reducing or compensating) will be required to the extent necessary to ensure that the adverse effects to the aquatic environment are minimal.

c. Compensatory mitigation at a minimum one-for-one ratio will be required for all wetland impacts requiring a PCN, unless the District Engineer determines in writing that some other form of mitigation would be more environmentally appropriate and provides a project-specific waiver of this requirement. Consistent with National policy, the District Engineer will establish a preference for restoration of wetlands as compensatory mitigation, with preservation used only in exceptional circumstances.

d. Compensatory mitigation (i.e., replacement or substitution of aquatic resources for those impacted) will not be used to increase the acreage losses allowed by the acreage limits of some of the NWPs. For example, $\frac{1}{4}$ -acre of wetlands cannot be created to change a $\frac{3}{4}$ -acre loss of wetlands to a $\frac{1}{2}$ -acre loss associated with NWP 39 verification. However, $\frac{1}{2}$ -acre of created wetlands can be used to reduce the impacts of a $\frac{1}{2}$ -acre loss of wetlands to the minimum impact level in order to meet the minimal impact requirement associated with NWPs.

e. To be practicable, the mitigation must be available and capable of being done considering costs, existing technology, and logistics in light of the overall project purposes. Examples of mitigation that may be appropriate and practicable include, but are not limited to: reducing the size of the project; establishing and maintaining wetland or upland vegetated buffers to protect open waters such as streams; and replacing losses of aquatic resource functions and values by creating, restoring, enhancing, or preserving similar functions and values, preferably in the same watershed.

f. Compensatory mitigation plans for projects in or near streams or other open waters will normally include a requirement for the establishment, maintenance, and legal protection (e.g., easements, deed restrictions) of vegetated buffers to open waters. In many cases, vegetated buffers will be the only compensatory mitigation required. Vegetated buffers should consist of native species. The width of the vegetated buffers required will address documented water quality or aquatic habitat loss concerns. Normally, the vegetated buffer will be 25 to 50 feet wide on each side of the stream, but the District Engineers may require slightly wider vegetated buffers to address documented water quality or habitat loss concerns. Where both wetlands and open waters exist on the project site, the Corps will determine the appropriate compensatory mitigation (e.g., stream buffers or wetlands compensation) based on what is best for the aquatic

environment or, a watershed basis. In cases where vegetated buffers are determined to be the most appropriate form of compensatory mitigation, the District Engineer may waive or reduce the requirement to provide wetland compensatory mitigation for wetland impacts.

g. Compensatory mitigation proposals submitted with the " notification" may be either conceptual or detailed. If conceptual plans are approved under the verification, then the Corps will condition the verification to require detailed plans be submitted and approved by the Corps prior to construction of the authorized activity in waters of the US.

h. Permittees may propose the use of mitigation banks, in-lieu fee arrangements or separate activity-specific compensatory mitigation. In all cases that require compensatory mitigation, the mitigation provisions will specify the party responsible for accomplishing and/or complying with the mitigation plan.

20. Spawning Areas. Activities, including structures and work in navigable waters of the US or discharges of dredged or fill material, in spawning areas during spawning seasons must be avoided to the maximum extent practicable. Activities that result in the physical destruction (e.g., excavate, fill, or smother downstream by substantial turbidity) of an important spawning area are not authorized.

21. Management of Water Flows. To the maximum extent practicable, the activity must be designed to maintain preconstruction downstream flow conditions (e.g., location, capacity, and flow rates). Furthermore, the activity must not permanently restrict or impede the passage of normal or expected high flows (unless the primary purpose of the fill is to impound waters) and the structure or discharge of dredged or fill material must withstand expected high flows. The activity must, to the maximum extent practicable, provide for retaining excess flows from the site, provide for maintaining surface flow rates from the site similar to preconstruction conditions, and provide for not increasing water flows from the project site, relocating water, or redirecting water flow beyond preconstruction conditions. Stream channelizing will be reduced to the minimal amount necessary, and the activity must, to the maximum extent practicable, reduce adverse effects such as flooding or erosion downstream and upstream of the project site, unless the activity is part of a larger system designed to manage water flows. In most cases, it will not be a requirement to conduct detailed studies and monitoring of water flow.

This condition is only applicable to projects that have the potential to affect waterflows. While appropriate measures must be taken, it is not necessary to conduct detailed studies to identify such measures or require monitoring to ensure their effectiveness. Normally, the Corps will defer to state and local authorities regarding management of water flow.

22. Adverse Effects From Impoundments. If the activity creates an impoundment of water, adverse effects to the aquatic system due to the acceleration of the passage of water, and/or the restricting its flow shall be minimized to the maximum extent practicable. This includes structures and work in navigable waters of the US, or discharges of dredged or fill material.

23. Waterfowl Breeding Areas. Activities, including structures and work in navigable

waters of the US or discharges of dredged or fill material, into breeding areas for migratory waterfowl must be avoided to the maximum extent practicable.

24. Removal of Temporary Fills. Any temporary fills must be removed in their entirety and the affected areas returned to their preexisting elevation.

25. Designated Critical Resource Waters. Critical resource waters include, NOAA-designated marine sanctuaries, National Estuarine Research Reserves, National Wild and Scenic Rivers, critical habitat for Federally listed threatened and endangered species, coral reefs, state natural heritage sites, and outstanding national resource waters or other waters officially designated by a state as having particular environmental or ecological significance and identified by the District Engineer after notice and opportunity for public comment. The District Engineer may also designate additional critical resource waters after notice and opportunity for comment.

a. Except as noted below, discharges of dredged or fill material into waters of the US are not authorized by NWP 7, 12, 14, 16, 17, 21, 29, 31, 35, 39, 40, 42, 43, and 44 for any activity within, or directly affecting, critical resource waters, including wetlands adjacent to such waters. Discharges of dredged or fill materials into waters of the US may be authorized by the above NWPs in National Wild and Scenic Rivers if the activity complies with General Condition 7. Further, such discharges may be authorized in designated critical habitat for Federally listed threatened or endangered species if the activity complies with General Condition 11 and the USFWS or the NMFS has concurred in a determination of compliance with this condition.

b. For NWPs 3, 8, 10, 13, 15, 18, 19, 22, 23, 25, 27, 28, 30, 33, 34, 36, 37, and 38, notification is required in accordance with General Condition 13, for any activity proposed in the designated critical resource waters including wetlands adjacent to those waters. The District Engineer may authorize activities under these NWPs only after it is determined that the impacts to the critical resource waters will be no more than minimal.

26. Fills Within 100-Year Floodplains. For purposes of this General Condition, 100-year floodplains will be identified through the existing Federal Emergency Management Agency's (FEMA) Flood Insurance Rate Maps or FEMA-approved local floodplain maps.

a. Discharges in Floodplain; Below Headwaters. Discharges of dredged or fill material into waters of the US within the mapped 100-year floodplain, below headwaters (i.e. five cfs), resulting in permanent above-grade fills, are not authorized by NWPs 39, 40, 42, 43, and 44.

b. Discharges in Floodway; Above Headwaters. Discharges of dredged or fill material into waters of the US within the FEMA or locally mapped floodway, resulting in permanent above-grade fills, are not authorized by NWPs 39, 40, 42, and 44.

c. The permittee must comply with any applicable FEMA-approved state or local floodplain management requirements.

27. Construction Period. For activities that have not been verified by the Corps and the

project was commenced or under contract to commence by the expiration date of the NWP (or modification or revocation date), the work must be completed within 12-months after such date (including any modification that affects the project).

For activities that have been verified and the project was commenced or under contract to commence within the verification period, the work must be completed by the date determined by the Corps.

For projects that have been verified by the Corps, an extension of a Corps approved completion date may be requested. This request must be submitted at least one month before the previously approved completion date.

FURTHER INFORMATION

1. District Engineers have authority to determine if an activity complies with the terms and conditions of a NWP.
2. NWPs do not obviate the need to obtain other Federal, State, or local permits, approvals, or authorizations required by law.
3. NWPs do not grant any property rights or exclusive privileges.
4. NWPs do not authorize any injury to the property or rights of others.
5. NWPs do not authorize interference with any existing or proposed Federal project.

DEFINITIONS

Best Management Practices (BMPs): BMPs are policies, practices, procedures, or structures implemented to mitigate the adverse environmental effects on surface water quality resulting from development. BMPs are categorized as structural or nonstructural. A BMP policy may affect the limits on a development.

Compensatory Mitigation: For purposes of Section 10/404, compensatory mitigation is the restoration, creation, enhancement, or in exceptional circumstances, preservation of wetlands and/or other aquatic resources for the purpose of compensating for unavoidable adverse impacts, which remain, after all appropriate and practicable avoidance and minimization has been achieved.

Creation: The establishment of a wetland or other aquatic resource where one did not formerly exist.

Enhancement: Activities conducted in existing wetlands or other aquatic resources that increase

one or more aquatic functions.

Ephemeral Stream: An ephemeral stream has *flowing* water only during and for a short duration after, precipitation events in a typical year. Ephemeral stream beds are located above the water table year-round. Groundwater is not a source of water for the stream. Runoff from rainfall is the primary source of water for stream flow.

Farm Tract: A unit of contiguous land under one ownership that is operated as a farm or part of a farm.

Flood Fringe: That portion of the 100-year floodplain outside of the floodway (often referred to as “floodway fringe”).

Floodway: The area regulated by Federal, state, or local requirements to provide for the discharge of the base flood so the cumulative increase in water surface elevation is no more than a designated amount (not to exceed one foot as set by the National Flood Insurance Program) within the 100-year floodplain.

Independent Utility: A test to determine what constitutes a single and complete project in the Corps regulatory program. A project is considered to have independent utility if it would be constructed absent the construction of other projects in the project area. Portions of a multi-phase project that depend upon other phases of the project do not have independent utility. Phases of a project that would be constructed even if the other phases were not built can be considered as separate single and complete projects with independent utility.

Intermittent Stream: An intermittent stream has flowing water during certain times of the year, when groundwater provides water for stream flow. During dry periods, intermittent streams may not have flowing water. Runoff from rainfall is a supplemental source of water for stream flow.

Loss of waters of the US: Waters of the US that include the filled area and other waters that are permanently adversely affected by flooding, excavation, or drainage because of the regulated activity. Permanent adverse effects include permanent above-grade, at-grade, or below-grade fills that change an aquatic area to dry land, increase the bottom elevation of a waterbody, or change the use of a waterbody. The acreage of loss of waters of the US is the threshold measurement of the impact to existing waters for determining whether a project may qualify for a NWP; it is not a net threshold that is calculated after considering compensatory mitigation that may be used to offset losses of aquatic functions and values. The loss of stream bed includes the linear feet of stream bed that is filled or excavated. Waters of the US temporarily filled, flooded, excavated, or drained, but restored to preconstruction contours and elevations after construction, are not included in the measurement of loss of waters of the US. Impacts to ephemeral waters are only not included in the acreage or linear foot measurements of loss of waters of the US or loss of stream bed, for the purpose of determining compliance with the threshold limits of the NWPs.

Non-tidal Wetland: An area that, during a year with normal patterns of precipitation has

standing or flowing water for sufficient duration to establish an ordinary high water mark. Aquatic vegetation within the area of standing or flowing water is either non-emergent, sparse, or absent. Vegetated shallows are considered to be open waters. The term “open water” includes rivers, streams, lakes, and ponds. For the purposes of the NWP, this term does not include ephemeral waters.

Perennial Stream: A perennial stream has flowing water year-round during a typical year. The water table is located above the stream bed for the most of the year. Groundwater is the primary source of water for stream flow. Runoff from rainfall is a supplemental source of water for stream flow.

Permanent Above-grade Fill: A discharge of dredged or fill material into waters of the US, including wetlands, that results in a substantial increase in ground elevation and permanently converts part or all of the waterbody to dry land. Structural fills authorized by NWPs 3, 25, 36, etc. are not included.

Preservation: The protection of ecologically important wetlands or other aquatic resources in perpetuity through the implementation of appropriate legal and physical mechanisms. Preservation may include protection of upland areas adjacent to wetlands as necessary to ensure protection and/or enhancement of the overall aquatic ecosystem.

Restoration: Re-establishment of wetland and/or other aquatic resource characteristics and function(s) at a site where they have ceased to exist, or exist in a substantially degraded state.

Riffle and Pool Complex: Riffle and pool complexes are special aquatic sites under the 404(b)(1) Guidelines. Riffle and pool complexes sometimes characterize steep gradient sections of streams. Such stream sections are recognizable by their hydraulic characteristics. The rapid movement of water over a coarse substrate in riffles results in a rough flow, a turbulent surface and high dissolved oxygen levels in the water. Pools are deeper areas associated with riffles. A slower stream velocity, a streaming flow, a smooth surface, and a finer substrate characterize pools.

Single and Complete Project: The term “single and complete project” is defined at 33 CFR 330.2(i) as the total project proposed or accomplished by one owner/developer or partnership or other association of owners/developers (see definition of independent utility). For linear projects, the “single and complete project” (i.e., a single and complete crossing) will apply to each crossing of a separate water of the US (i.e., a single waterbody) at that location. An exception is for linear projects crossing a single waterbody several times at separate and distant locations; each crossing is considered a single and complete project. However, individual channels in a braided stream or river, or individual arms of a large, irregularly shaped wetland or lake, etc., are not separate waterbodies.

Stormwater Management: Stormwater management is the mechanism for controlling stormwater runoff for the purposes of reducing downstream erosion, water quality degradation, and flooding and mitigating the adverse effects of changes in land use on the aquatic environment.

Stormwater Management Facilities: Stormwater management facilities are those facilities, including but not limited to, stormwater retention and detention ponds and BMPs, which retain water for a period of time to control runoff and/or improve the quality (i.e., by reducing the concentration of nutrients, sediments, hazardous substances and other pollutants) of stormwater runoff.

Stream Channelization: The manipulation of a stream channel to increase the rate of water flow through the stream channel. Manipulation may include deepening, widening, straightening, armoring, or other activities that change the stream cross-section or other aspects of stream channel geometry to increase the rate of water flow through the stream channel. A channelized stream remains a water of the US, despite the modifications to increase the rate of water flow.

Tidal Wetland: A tidal wetland is a wetland (i.e., water of the US) that is inundated by tidal waters. The definitions of a wetland and tidal waters can be found at 33 CFR 328.3(b) and 33 CFR 328.3(f), respectively. Tidal waters rise and fall in a predictable and measurable rhythm or cycle due to the gravitational pulls of the moon and sun. Tidal waters end where the rise and fall of the water surface can no longer be practically measured in a predictable rhythm due to masking by other waters, wind, or other effects. Tidal wetlands are located channelward of the high tide line (i.e., spring high tide line) and are inundated by tidal waters two times per lunar month, during spring high tides.

Vegetated Buffer: A vegetated upland or wetland area next to rivers, streams, lakes, or other open waters, which separates the open water from developed areas, including agricultural land. Vegetated buffers provide a variety of aquatic habitat functions and values (e.g., aquatic habitat for fish and other aquatic organisms, moderation of water temperature changes, and detritus for aquatic food webs) and help improve or maintain local water quality. A vegetated buffer can be established by maintaining an existing vegetated area or planting native trees, shrubs, and herbaceous plants on land next to openwaters. Mowed lawns are not considered vegetated buffers because they provide little or no aquatic habitat functions and values. The establishment and maintenance of vegetated buffers is a method of compensatory mitigation that can be used in conjunction with the restoration, creation, enhancement or preservation of aquatic habitats to ensure that activities authorized by NWP's result in minimal adverse effects to the aquatic environment. (See General Condition 19.)

Vegetated Shallows: Vegetated shallows are special aquatic sites under the 404(b)(1) Guidelines. They are areas that are permanently inundated and under normal circumstances have rooted aquatic vegetation, such as seagrasses in marine and estuarine systems and a variety of vascular rooted plants in freshwater systems.

Waterbody: A waterbody is any area that in a normal year has water flowing or standing above ground to the extent that evidence of an ordinary high water mark is established. Wetlands contiguous to the waterbody are considered part of the waterbody.

**FINAL REGIONAL CONDITIONS FOR NATIONWIDE PERMITS IN THE
WILMINGTON DISTRICT**

1. Waters Excluded from NWP or Subject to Additional Notification Requirements:

a. The Corps identified waters that will be excluded from use of this NWP. These waters are:

1. Discharges into Waters of the United States designated by either the North Carolina Division of Marine Fisheries (NCDMF) or the North Carolina Wildlife Resources Commission (NCWRC) as anadromous fish spawning area are prohibited during the period between February 15 and June 30, without prior written approval from NCDMF or NCWRC and the Corps.

2. Discharges into Waters of the United States designated as sturgeon spawning areas are prohibited during the period between February 1 and June 30, without prior written approval from the National Marine Fisheries Service (NMFS).

b. The Corps identified waters that will be subject to additional notification requirements for activities authorized by this NWP. These waters are:

1. Prior to the use of any NWP in any of the following North Carolina *designated waters*, applicants must comply with Nationwide Permit General Condition 13. In addition, the applicant must furnish a written statement of compliance with all of the conditions of the applicable Nationwide Permit. The North Carolina *designated waters* that require additional notification requirements are “Outstanding Resource Waters” (ORW) and “High Quality Waters” (HQW) (as defined by the North Carolina Division of Water Quality), or “Inland Primary Nursery Areas” (IPNA) (as defined by the North Carolina Wildlife Resources Commission), or contiguous wetlands (as defined by the North Carolina Division of Water Quality), or “Primary Nursery Areas” (PNA) (as defined by the North Carolina Division of Marine Fisheries).

2. Applicants for any NWP in a designated “Area of Environmental Concern” (AEC) in the twenty (20) coastal counties of Eastern North Carolina covered by the North Carolina Coastal Area Management Act (CAMA), must also obtain the required CAMA permit. Construction activities may not commence until a copy of the approved CAMA permit is furnished to the appropriate Wilmington District Regulatory Field Office (Wilmington Field Office – P.O. Box 1890, Wilmington, NC 28402 or Washington Field Office – P.O. Box 1000, Washington, NC 27889) for authorization to begin work.

3. Prior to the use of any NWP on a Barrier Island of North Carolina, applicants must comply with Nationwide Permit General Condition 13. In addition, the applicant shall furnish a written statement of compliance with all of the conditions listed of the applicable Nationwide Permit.

4. Prior to the use of any NWP in a "Mountain or Piedmont Bog" of North Carolina, applicants shall comply with Nationwide Permit General Condition 13. In addition, the applicant shall furnish a written statement of compliance with all of the conditions listed of the applicable NWP.

Note: The following wetland community types identified in the N.C. Natural Heritage Program document, "Classification of Natural communities of North Carolina (Michael P. Schafale and Alan S. Weakley, 1990), are subject to this regional condition.

Mountain Bogs

Swamp Forest-Bog Complex
 Swamp Forest-Bog Complex (Spruce Subtype)
 Southern Appalachian Bog (Northern Subtype)
 Southern Appalachian Bog (Southern Subtype)
 Southern Appalachian Fen

Piedmont Bogs

Upland Depression Swamp Forest

5. Prior to the use of any NWP in Mountain Trout Waters within twenty-five (25) designated counties of North Carolina, applicants shall comply with Nationwide General Condition 13. In addition, the applicant shall furnish a written statement of compliance with all of the conditions listed of the applicable NWP. Notification will include a letter of comments and recommendations from the North Carolina Wildlife Resources Commission (NCWRC), the location of work, a delineation of wetlands, a discussion of alternatives to working in the Mountain Trout Waters, why other alternatives were not selected, and a plan to provide compensatory mitigation for all unavoidable adverse impacts to the Mountain Trout Waters. To facilitate coordination with the NCWRC, the proponent may provide a copy of the notification to the NCWRC concurrent with the notification to the District Engineer. The NCWRC will respond both to the proponent and directly to the Corps of Engineers.

The twenty-five (25) designated counties are:

Alleghany	Ashe	Avery	Yancey
Buncombe	Burke	Caldwell	Wilkes
Cherokee	Clay	Graham	Swain
Haywood	Henderson	Jackson	Surry
Macon	Madison	McDowell	Stokes
Mitchell	Polk	Rutherford	
Transylvania	Watauga		

6. Applicants shall notify the NCDENR Shellfish Sanitation Section prior to dredging in or removing sediment from an area closed to shell fishing where the effluent may be released to an area open for shell fishing or swimming in order to avoid contamination of the disposal area and allow a temporary shellfish closure to be made. Any disposal of sand to the beach should occur between November 1 and April 30 when recreational usage is low. Only clean sand should be used and no dredged sand from closed shell fishing areas. If beach disposal was to occur at times other than stated above or if sand from a closed shell fishing area is to be used, a

swim advisory shall be posted and a press release shall be made. NCDENR Shellfish Sanitation Section must be notified before commencing this activity.

2. List of Final Corps Regional Modifications and Conditions for All Nationwide Permits


a. Individual or multiple NWPs may not be used for activities that result in the cumulative loss or degradation of greater than 300 total linear feet of perennial streambed or intermittent streambed that exhibits important aquatic function(s).

b. Prior to the use of any NWP (except 13, 27, and 39) for any activity that has more than a total of 150 total linear feet of perennial streambed impacts or intermittent streambed impacts (if the intermittent stream has important aquatic function), the applicant must comply with Nationwide Permit General Condition 13. In addition, the applicant shall furnish a written statement of compliance with all of the conditions listed of the applicable NWP. Compensatory mitigation is typically required for any impact that requires such notification. [Note: The Corps uses the Intermittent Channel Evaluation Form, located with Permit Information on the Regulatory Program Web Site, to aid in the determination of the intermittent channel stream status. Also, NWPs 13, 27 and 39 have specific reporting requirements.]

c. For all Nationwide Permits which allow the use of concrete as a building material, measures will be taken to prevent live or fresh concrete, including bags of uncured concrete, from coming into contact with waters of the state until the concrete has hardened.

d. For all Nationwide Permits that allow for the use of riprap material for bank stabilization, filter cloth must be placed underneath the riprap as an additional requirement of its use in North Carolina waters.

e. For all NWPs that involve the construction of culverts, measures will be included in the construction that will promote the safe passage of fish and other aquatic organisms. All culverts in the 20 CAMA coastal counties must be buried to a depth of one foot below the



bed of the stream or wetland. For all culvert construction activities, the dimension, pattern, and profile of the stream, (above and below a pipe or culvert), should not be modified by widening the stream channel or by reducing the depth of the stream. Culvert inverts will be buried at least one foot below the bed of the stream for culverts greater than 48 inches in diameter. For culverts 48 inches in diameter or smaller, culverts must be buried below the bed of the stream to a depth equal to or greater than 20 percent of the diameter of the culvert. Bottomless arch culverts will satisfy this condition. A waiver from the depth specifications in this Regional Condition may be requested in writing. The waiver will only be issued if it can be demonstrated that the impacts of complying with this Regional Condition would result in more adverse impacts to the aquatic

environment.

3. Additional Regional Conditions Applicable to this Specific Nationwide Permit.

The required restoration plan must include a timetable for restoration activities.

NORTH CAROLINA DIVISION OF WATER QUALITY
GENERAL CERTIFICATION CONDITIONS

For the most recent General Certification conditions, call the NC Division of Water Quality, Wetlands/401 Certification Unit at (919) 733- 1786 or access the following website:

<http://h2o.enr.state.nc.us/ncwetlands/certs.html>

NORTH CAROLINA DIVISION OF COASTAL MANAGEMENT
STATE CONSISTENCY

Consistent.

Citations:

2002 Nationwide Permits - Federal Register Notice 15 Jan 2002

2002 Nationwide Permits Corrections - Federal Register Notice 13 Feb 2002

2002 Regional Conditions – Authorized 17 May 2002

WQC #3366

**GENERAL CERTIFICATION FOR PROJECTS ELIGIBLE
FOR CORPS OF ENGINEERS NATIONWIDE PERMIT NUMBER 33
(TEMPORARY CONSTRUCTION, ACCESS AND DEWATERING)
AND RIPARIAN AREA PROTECTION RULES (BUFFER RULES)**

This General Certification is issued in conformity with the requirements of Section 401, Public Laws 92-500 and 95-217 of the United States and subject to the North Carolina Division of Water Quality Regulations in 15A NCAC 2H, Section .0500 and 15A NCAC 2B .0200 for the discharge of fill material to waters and wetland areas as described in 33 CFR 330 Appendix A (B) (33) of the Corps of Engineers regulations (i.e., Nationwide Permit No. 33) and for the Riparian Area Protection Rules (Buffer Rules) in 15A NCAC 2B .0200. The category of activities shall include any fill activity for temporary construction, access and de-watering. This Certification replaces Water Quality Certification Number 2727 issued on May 1, 1992 and Certification Number 3114 issued on February 11, 1997. This WQC is rescinded when the Corps of Engineers reauthorize Nationwide Permit 33 or when deemed appropriate by the Director of the DWQ.

The State of North Carolina certifies that the specified category of activity will not violate appropriate portions of Sections 301, 302, 303, 306 and 307 of the Public Laws 92-500 and 95-217 if conducted in accordance with the conditions hereinafter set forth.

Conditions of Certification:

1. These activities do not require written concurrence from the Division of Water Quality as long as they comply with all conditions of this General Certification. If any condition in this Certification cannot be met, application to and written concurrence from DWQ are required. Also, Condition No. 2 is applicable to all streams in basins with riparian area protection rules;
2. Impacts to any stream length in the Neuse, Tar-Pamlico and Randleman River Basins (or any other major river basins with Riparian Area Protection Rules [Buffer Rules] in effect at the time of application) requires written concurrence from DWQ in accordance with 15A NCAC 2B.0200. Activities listed as "exempt" from these rules do not need to apply for written concurrence under this Certification. New development activities located in the protected 50-foot wide riparian areas (whether jurisdictional wetlands or not) within the Neuse, Tar-Pamlico, Randleman and Catawba River Basins shall be limited to "uses" identified within and constructed in accordance with 15A NCAC 2B .0200. All new development shall be located, designed, constructed, and maintained to have minimal disturbance to protect water quality to the maximum extent practicable through the use of best management practices;
3. Appropriate sediment and erosion control practices which equal or exceed those outlined in the most recent version of the "North Carolina Sediment and Erosion Control Planning and Design Manual" or the "North Carolina Surface Mining Manual" whichever is more appropriate (available from the Division of Land Resources (DLR) in the DENR Regional or Central Offices) shall be in full compliance with all specifications governing the proper design, installation and operation and maintenance of such Best Management Practices in order to assure compliance with the appropriate turbidity water quality standard;

WQC #3366

4. All sediment and erosion control measures placed in wetlands or waters shall be removed and the original grade restored within two months after the Division of Land Resources has released the project;
5. If an environmental document is required, this Certification is not valid until a Finding of No Significant Impact (FONSI) or Record of Decision (ROD) is issued by the State Clearinghouse;
6. Placement of culverts and other structures in waters, streams, and wetlands must be placed below the elevation of the streambed to allow low flow passage of water and aquatic life unless it can be shown to DWQ that providing passage would be impractical. Design and placement of culverts including open bottom or bottomless arch culverts and other structures including temporary erosion control measures shall not be conducted in a manner that may result in aggradation, degradation or significant changes in hydrology of wetlands or stream beds or banks, adjacent to or upstream and down stream of the above structures. The applicant is required to provide evidence that the equilibrium shall be maintained if requested in writing by DWQ. Additionally, when roadways, causeways or other fill projects are constructed across FEMA-designated floodways or wetlands, openings such as culverts or bridges must be provided to maintain the natural hydrology of the system as well as prevent constriction of the floodway that may result in aggradation, degradation or significant changes in hydrology of streams or wetlands;
7. Measures shall be taken to prevent live or fresh concrete from coming into contact with waters of the state until the concrete has hardened;
8. All temporary fill shall be removed to the original grade after construction is complete and the site shall be stabilized to prevent erosion;
9. Pipes shall be installed under the road or causeway in all streams to carry at least the 25 year storm event as outlined in the most recent edition of the "North Carolina Sediment and Erosion Control Planning and Design Manual" or the "North Carolina Surface Mining Manual" so as not to restrict stream flow during use of this Certification;
10. In accordance with North Carolina General Statute Section 143-215.3D(e), any request for written concurrence for a 401 Water Quality Certification must include the appropriate fee. If a project also requires a CAMA Permit, one payment to both agencies shall be submitted and will be the higher of the two fees;
11. Additional site-specific conditions may be added to projects for which written concurrence is required or requested under this Certification in order to ensure compliance with all applicable water quality and effluent standards;
12. Concurrence from DWQ that this Certification applies to an individual project shall expire three years from the date of the cover letter from DWQ or on the same day as the expiration date of these corresponding Nationwide and Regional General Permits, whichever is sooner;

205
WQC #3366

13. When written concurrence is required, the applicant is required to use the most recent version of the Certification of Completion form to notify DWQ when all work included in the 401 Certification has been completed.

Non-compliance with or violation of the conditions herein set forth by a specific fill project shall result in revocation of this Certification for the project and may result in criminal and/or civil penalties.

The Director of the North Carolina Division of Water Quality may require submission of a formal application for individual certification for any project in this category of activity that requires written concurrence under this certification, if it is determined that the project is likely to have a significant adverse effect upon water quality or degrade the waters so that existing uses of the wetland, stream or downstream waters are precluded.

Public hearings may be held for specific applications or group of applications prior to a Certification decision if deemed in the public's best interest by the Director of the North Carolina Division of Water Quality.

Effective date: 18 March 2002

DIVISION OF WATER QUALITY

By


Gregory J. Thorpe, Ph.D.

Acting Director


WQC # 3366

206

NORTH CAROLINA



PROJECT



NOTE:
 BRIDGE NO. 653 MUST BE REPLACED
 AND CARRYING TRAFFIC BEFORE
 BRIDGE NO. 654 IS REPLACED.


VICINITY MAPS

NCDOT
 DIVISION OF HIGHWAYS
 BUNCOMBE COUNTY
 PROJECT: 32877.1.1 (B-3119)

**BRIDGE NO. 653 OVER BROAD
 RIVER ON SR 2804 AND BRIDGE
 NO. 654 OVER SAND BRANCH
 ON SR 2786**


SHEET 1 OF 12

1/26/05



SITE MAP

NCDOT
DIVISION OF HIGHWAYS
BUNCOMBE COUNTY
PROJECT: 32877.1.1 (B-3119)
BRIDGE NO. 653 OVER BROAD
RIVER ON SR 2804 AND BRIDGE
NO. 654 OVER SAND BRANCH
ON SR 2786
SHEET 2 OF 12 **1 / 26 / 05**



VOLUME OF TEMPORARY FILL
 IN SURFACE WATER (BELOW
 NORMAL WS): @ 120 cu m
 TOP OF WORK PAD TO BE
 SET 0.6m ABOVE NWS

**TYPICAL SECTION
 (NOT TO SCALE)**

NCDOT
 DIVISION OF HIGHWAYS
 BUNCOMBE COUNTY
 PROJECT: 32877.1.1 (B-3119)
 BRIDGE NO. 653 OVER BROAD
 RIVER ON SR 2804 AND BRIDGE
 NO. 654 OVER SAND BRANCH
 ON SR 2786
 SHEET 3 OF 12 1/26/05

PROPERTY OWNERS

NAMES AND ADDRESSES

PARCEL NO.	NAMES	ADDRESSES
1	MARY E. PEEK, HEIRS CO MICHAEL LEDBETTER	P.O. BOX 248 OLD FORT, NC 28762
4	MARY E. PEEK, HEIRS CO MICHAEL LEDBETTER	P.O. BOX 248 OLD FORT, NC 28762
5	JAMES E. AND BETTY F. GILLIAM	11171 BENT BRANCH RD. PIKEVILLE, KY 41501
6	LINDA AND ERNEST RUSSELL	21 MARLEY DR. FLATROCK, NC 28731

NCDOT

DIVISION OF HIGHWAYS

BUNCOMBE COUNTY

PROJECT: 32877.1.1 (B-3119)

BRIDGE NO. 653 OVER BROAD

RIVER ON SR 2804 AND BRIDGE

NO. 654 OVER SAND BRANCH

ON SR 2786

SHEET 4 OF 12

1 / 26 / 05

PROJECT REFERENCE NO. B-3192
 & A.V. SHEET NO. 10
 ROADWAY DESIGN & CONSTRUCTION ENGINEER
 PRELIMINARY PLANS
 METRICS
 COUNTY: R/W REV.

Design Exception required for the design speed from 100 km/h to 30 km/h.

DETAIL A
 SPECIAL CUT DITCH
 (NOT TO SCALE)

MIN. D = 0.5 m
 -YI- STA. 11+30 TO 11+47 LT
 -YI- STA. 11+47 TO 11+60 UT

PI STA. 11+27.04
 $\Delta = 17.21$
 $L = 32.42$
 $R = 152.000$
 $SE = 03$

PI STA. 11+84.480
 $\Delta = 19.47$
 $L = 38.94$
 $R = 211.000$
 $SE = 02$

PI STA. 12+47.533
 $\Delta = 23.08$
 $L = 46.16$
 $R = 160.000$
 $SE = 04$

PI STA. 13+04.715
 $\Delta = 25.16$
 $L = 50.32$
 $R = 160.000$
 $SE = 04$

PI STA. 12+22.147
 $\Delta = 5.10$
 $L = 10.20$
 $R = 66.000$
 $SE = 04$

PI STA. 11+07.550
 $\Delta = 12.92$
 $L = 25.84$
 $R = 127.000$
 $SE = 04$

PI STA. 11+47.539
 $\Delta = 14.83$
 $L = 29.66$
 $R = 148.000$
 $SE = 04$

PI STA. 12+06.54
 $\Delta = 17.00$
 $L = 34.00$
 $R = 170.000$
 $SE = 04$

PI STA. 12+20.000
 $\Delta = 19.00$
 $L = 38.00$
 $R = 190.000$
 $SE = 04$

PI STA. 12+72.04
 $\Delta = 21.00$
 $L = 42.00$
 $R = 210.000$
 $SE = 04$

PI STA. 13+46.003
 $\Delta = 23.00$
 $L = 46.00$
 $R = 230.000$
 $SE = 04$

PI STA. 14+05.005
 $\Delta = 25.00$
 $L = 50.00$
 $R = 250.000$
 $SE = 04$

PI STA. 14+64.007
 $\Delta = 27.00$
 $L = 54.00$
 $R = 270.000$
 $SE = 04$

PI STA. 15+23.009
 $\Delta = 29.00$
 $L = 58.00$
 $R = 290.000$
 $SE = 04$

PI STA. 15+82.011
 $\Delta = 31.00$
 $L = 62.00$
 $R = 310.000$
 $SE = 04$

PI STA. 16+41.013
 $\Delta = 33.00$
 $L = 66.00$
 $R = 330.000$
 $SE = 04$

PI STA. 17+00.015
 $\Delta = 35.00$
 $L = 70.00$
 $R = 350.000$
 $SE = 04$

PI STA. 17+59.017
 $\Delta = 37.00$
 $L = 74.00$
 $R = 370.000$
 $SE = 04$

PI STA. 18+18.019
 $\Delta = 39.00$
 $L = 78.00$
 $R = 390.000$
 $SE = 04$

PI STA. 18+77.021
 $\Delta = 41.00$
 $L = 82.00$
 $R = 410.000$
 $SE = 04$

PI STA. 19+36.023
 $\Delta = 43.00$
 $L = 86.00$
 $R = 430.000$
 $SE = 04$

PI STA. 20+00.025
 $\Delta = 45.00$
 $L = 90.00$
 $R = 450.000$
 $SE = 04$

PI STA. 20+60.027
 $\Delta = 47.00$
 $L = 94.00$
 $R = 470.000$
 $SE = 04$

PI STA. 21+20.029
 $\Delta = 49.00$
 $L = 98.00$
 $R = 490.000$
 $SE = 04$

PI STA. 21+80.031
 $\Delta = 51.00$
 $L = 102.00$
 $R = 510.000$
 $SE = 04$

PI STA. 22+40.033
 $\Delta = 53.00$
 $L = 106.00$
 $R = 530.000$
 $SE = 04$

PI STA. 23+00.035
 $\Delta = 55.00$
 $L = 110.00$
 $R = 550.000$
 $SE = 04$

PI STA. 23+60.037
 $\Delta = 57.00$
 $L = 114.00$
 $R = 570.000$
 $SE = 04$

PI STA. 24+20.039
 $\Delta = 59.00$
 $L = 118.00$
 $R = 590.000$
 $SE = 04$

PI STA. 24+80.041
 $\Delta = 61.00$
 $L = 122.00$
 $R = 610.000$
 $SE = 04$

PI STA. 25+40.043
 $\Delta = 63.00$
 $L = 126.00$
 $R = 630.000$
 $SE = 04$

PI STA. 26+00.045
 $\Delta = 65.00$
 $L = 130.00$
 $R = 650.000$
 $SE = 04$

PI STA. 26+60.047
 $\Delta = 67.00$
 $L = 134.00$
 $R = 670.000$
 $SE = 04$

PI STA. 27+20.049
 $\Delta = 69.00$
 $L = 138.00$
 $R = 690.000$
 $SE = 04$

PI STA. 27+80.051
 $\Delta = 71.00$
 $L = 142.00$
 $R = 710.000$
 $SE = 04$

PI STA. 28+40.053
 $\Delta = 73.00$
 $L = 146.00$
 $R = 730.000$
 $SE = 04$

PI STA. 29+00.055
 $\Delta = 75.00$
 $L = 150.00$
 $R = 750.000$
 $SE = 04$

PI STA. 29+60.057
 $\Delta = 77.00$
 $L = 154.00$
 $R = 770.000$
 $SE = 04$

PI STA. 30+20.059
 $\Delta = 79.00$
 $L = 158.00$
 $R = 790.000$
 $SE = 04$

PI STA. 30+80.061
 $\Delta = 81.00$
 $L = 162.00$
 $R = 810.000$
 $SE = 04$

PI STA. 31+40.063
 $\Delta = 83.00$
 $L = 166.00$
 $R = 830.000$
 $SE = 04$

PI STA. 32+00.065
 $\Delta = 85.00$
 $L = 170.00$
 $R = 850.000$
 $SE = 04$

PI STA. 32+60.067
 $\Delta = 87.00$
 $L = 174.00$
 $R = 870.000$
 $SE = 04$

PI STA. 33+20.069
 $\Delta = 89.00$
 $L = 178.00$
 $R = 890.000$
 $SE = 04$

PI STA. 33+80.071
 $\Delta = 91.00$
 $L = 182.00$
 $R = 910.000$
 $SE = 04$

PI STA. 34+40.073
 $\Delta = 93.00$
 $L = 186.00$
 $R = 930.000$
 $SE = 04$

PI STA. 35+00.075
 $\Delta = 95.00$
 $L = 190.00$
 $R = 950.000$
 $SE = 04$

PI STA. 35+60.077
 $\Delta = 97.00$
 $L = 194.00$
 $R = 970.000$
 $SE = 04$

PI STA. 36+20.079
 $\Delta = 99.00$
 $L = 198.00$
 $R = 990.000$
 $SE = 04$

PI STA. 36+80.081
 $\Delta = 101.00$
 $L = 202.00$
 $R = 1010.000$
 $SE = 04$

PI STA. 37+40.083
 $\Delta = 103.00$
 $L = 206.00$
 $R = 1030.000$
 $SE = 04$

PI STA. 38+00.085
 $\Delta = 105.00$
 $L = 210.00$
 $R = 1050.000$
 $SE = 04$

PI STA. 38+60.087
 $\Delta = 107.00$
 $L = 214.00$
 $R = 1070.000$
 $SE = 04$

PI STA. 39+20.089
 $\Delta = 109.00$
 $L = 218.00$
 $R = 1090.000$
 $SE = 04$

PI STA. 39+80.091
 $\Delta = 111.00$
 $L = 222.00$
 $R = 1110.000$
 $SE = 04$

PI STA. 40+40.093
 $\Delta = 113.00$
 $L = 226.00$
 $R = 1130.000$
 $SE = 04$

PI STA. 41+00.095
 $\Delta = 115.00$
 $L = 230.00$
 $R = 1150.000$
 $SE = 04$

PI STA. 41+60.097
 $\Delta = 117.00$
 $L = 234.00$
 $R = 1170.000$
 $SE = 04$

PI STA. 42+20.099
 $\Delta = 119.00$
 $L = 238.00$
 $R = 1190.000$
 $SE = 04$

PI STA. 42+80.101
 $\Delta = 121.00$
 $L = 242.00$
 $R = 1210.000$
 $SE = 04$

PI STA. 43+40.103
 $\Delta = 123.00$
 $L = 246.00$
 $R = 1230.000$
 $SE = 04$

PI STA. 44+00.105
 $\Delta = 125.00$
 $L = 250.00$
 $R = 1250.000$
 $SE = 04$

PI STA. 44+60.107
 $\Delta = 127.00$
 $L = 254.00$
 $R = 1270.000$
 $SE = 04$

PI STA. 45+20.109
 $\Delta = 129.00$
 $L = 258.00$
 $R = 1290.000$
 $SE = 04$

PI STA. 45+80.111
 $\Delta = 131.00$
 $L = 262.00$
 $R = 1310.000$
 $SE = 04$

PI STA. 46+40.113
 $\Delta = 133.00$
 $L = 266.00$
 $R = 1330.000$
 $SE = 04$

PI STA. 47+00.115
 $\Delta = 135.00$
 $L = 270.00$
 $R = 1350.000$
 $SE = 04$

PI STA. 47+60.117
 $\Delta = 137.00$
 $L = 274.00$
 $R = 1370.000$
 $SE = 04$

PI STA. 48+20.119
 $\Delta = 139.00$
 $L = 278.00$
 $R = 1390.000$
 $SE = 04$

PI STA. 48+80.121
 $\Delta = 141.00$
 $L = 282.00$
 $R = 1410.000$
 $SE = 04$

PI STA. 49+40.123
 $\Delta = 143.00$
 $L = 286.00$
 $R = 1430.000$
 $SE = 04$

PI STA. 50+00.125
 $\Delta = 145.00$
 $L = 290.00$
 $R = 1450.000$
 $SE = 04$

PI STA. 50+60.127
 $\Delta = 147.00$
 $L = 294.00$
 $R = 1470.000$
 $SE = 04$

PI STA. 51+20.129
 $\Delta = 149.00$
 $L = 298.00$
 $R = 1490.000$
 $SE = 04$

PI STA. 51+80.131
 $\Delta = 151.00$
 $L = 302.00$
 $R = 1510.000$
 $SE = 04$

PI STA. 52+40.133
 $\Delta = 153.00$
 $L = 306.00$
 $R = 1530.000$
 $SE = 04$

PI STA. 53+00.135
 $\Delta = 155.00$
 $L = 310.00$
 $R = 1550.000$
 $SE = 04$

PI STA. 53+60.137
 $\Delta = 157.00$
 $L = 314.00$
 $R = 1570.000$
 $SE = 04$

PI STA. 54+20.139
 $\Delta = 159.00$
 $L = 318.00$
 $R = 1590.000$
 $SE = 04$

PI STA. 54+80.141
 $\Delta = 161.00$
 $L = 322.00$
 $R = 1610.000$
 $SE = 04$

PI STA. 55+40.143
 $\Delta = 163.00$
 $L = 326.00$
 $R = 1630.000$
 $SE = 04$

PI STA. 56+00.145
 $\Delta = 165.00$
 $L = 330.00$
 $R = 1650.000$
 $SE = 04$

PI STA. 56+60.147
 $\Delta = 167.00$
 $L = 334.00$
 $R = 1670.000$
 $SE = 04$

PI STA. 57+20.149
 $\Delta = 169.00$
 $L = 338.00$
 $R = 1690.000$
 $SE = 04$

PI STA. 57+80.151
 $\Delta = 171.00$
 $L = 342.00$
 $R = 1710.000$
 $SE = 04$

PI STA. 58+40.153
 $\Delta = 173.00$
 $L = 346.00$
 $R = 1730.000$
 $SE = 04$

PI STA. 59+00.155
 $\Delta = 175.00$
 $L = 350.00$
 $R = 1750.000$
 $SE = 04$

PI STA. 59+60.157
 $\Delta = 177.00$
 $L = 354.00$
 $R = 1770.000$
 $SE = 04$

PI STA. 60+20.159
 $\Delta = 179.00$
 $L = 358.00$
 $R = 1790.000$
 $SE = 04$

PI STA. 60+80.161
 $\Delta = 181.00$
 $L = 362.00$
 $R = 1810.000$
 $SE = 04$

PI STA. 61+40.163
 $\Delta = 183.00$
 $L = 366.00$
 $R = 1830.000$
 $SE = 04$

PI STA. 62+00.165
 $\Delta = 185.00$
 $L = 370.00$
 $R = 1850.000$
 $SE = 04$

PI STA. 62+60.167
 $\Delta = 187.00$
 $L = 374.00$
 $R = 1870.000$
 $SE = 04$

PI STA. 63+20.169
 $\Delta = 189.00$
 $L = 378.00$
 $R = 1890.000$
 $SE = 04$

PI STA. 63+80.171
 $\Delta = 191.00$
 $L = 382.00$
 $R = 1910.000$
 $SE = 04$

PI STA. 64+40.173
 $\Delta = 193.00$
 $L = 386.00$
 $R = 1930.000$
 $SE = 04$

PI STA. 65+00.175
 $\Delta = 195.00$
 $L = 390.00$
 $R = 1950.000$
 $SE = 04$

PI STA. 65+60.177
 $\Delta = 197.00$
 $L = 394.00$
 $R = 1970.000$
 $SE = 04$

PI STA. 66+20.179
 $\Delta = 199.00$
 $L = 398.00$
 $R = 1990.000$
 $SE = 04$

PI STA. 66+80.181
 $\Delta = 201.00$
 $L = 402.00$
 $R = 2010.000$
 $SE = 04$

PI STA. 67+40.183
 $\Delta = 203.00$
 $L = 406.00$
 $R = 2030.000$
 $SE = 04$

PI STA. 68+00.185
 $\Delta = 205.00$
 $L = 410.00$
 $R = 2050.000$
 $SE = 04$

PI STA. 68+60.187
 $\Delta = 207.00$
 $L = 414.00$
 $R = 2070.000$
 $SE = 04$

PI STA. 69+20.189
 $\Delta = 209.00$
 $L = 418.00$
 $R = 2090.000$
 $SE = 04$

PI STA. 69+80.191
 $\Delta = 211.00$
 $L = 422.00$
 $R = 2110.000$
 $SE = 04$

PI STA. 70+40.193
 $\Delta = 213.00$
 $L = 426.00$
 $R = 2130.000$
 $SE = 04$

PI STA. 71+00.195
 $\Delta = 215.00$
 $L = 430.00$
 $R = 2150.000$
 $SE = 04$

PI STA. 71+60.197
 $\Delta = 217.00$
 $L = 434.00$
 $R = 2170.000$
 $SE = 04$

PI STA. 72+20.199
 $\Delta = 219.00$
 $L = 438.00$
 $R = 2190.000$
 $SE = 04$

PI STA. 72+80.201
 $\Delta = 221.00$
 $L = 442.00$
 $R = 2210.000$
 $SE = 04$

PI STA. 73+40.203
 $\Delta = 223.00$
 $L = 446.00$
 $R = 2230.000$
 $SE = 04$

PI STA. 74+00.205
 $\Delta = 225.00$
 $L = 450.00$
 $R = 2250.000$
 $SE = 04$

PI STA. 74+60.207
 $\Delta = 227.00$
 $L = 454.00$
 $R = 2270.000$
 $SE = 04$

PI STA. 75+20.209
 $\Delta = 229.00$
 $L = 458.00$
 $R = 2290.000$
 $SE = 04$

PI STA. 75+80.211
 $\Delta = 231.00$
 $L = 462.00$
 $R = 2310.000$
 $SE = 04$

PI STA. 76+40.213
 $\Delta = 233.00$
 $L = 466.00$
 $R = 2330.000$
 $SE = 04$

PI STA. 77+00.215
 $\Delta = 235.00$
 $L = 470.00$
 $R = 2350.000$
 $SE = 04$

PI STA. 77+60.217
 $\Delta = 237.00$
 $L = 474.00$
 $R = 2370.000$
 $SE = 04$

PI STA. 78+20.219
 $\Delta = 239.00$
 $L = 478.00$
 $R = 2390.000$
 $SE = 04$

PI STA. 78+80.221
 $\Delta = 241.00$
 $L = 482.00$
 $R = 2410.000$
 $SE = 04$

PI STA. 79+40.223
 $\Delta = 243.00$
 $L = 486.00$
 $R = 2430.000$
 $SE = 04$

PI STA. 80+00.225
 $\Delta = 245.00$
 $L = 490.00$
 $R = 2450.000$
 $SE = 04$

PI STA. 80+60.227
 $\Delta = 247.00$
 $L = 494.00$
 $R = 2470.000$
 $SE = 04$

PI STA. 81+20.229
 $\Delta = 249.00$
 $L = 498.00$
 $R = 2490.000$
 $SE = 04$

PI STA. 81+80.231
 $\Delta = 251.00$
 $L = 502.00$
 $R = 2510.000$
 $SE = 04$

PI STA. 82+40.233
 $\Delta = 253.00$
 $L = 506.00$
 $R = 2530.000$
 $SE = 04$

PI STA. 83+00.235
 $\Delta = 255.00$
 $L = 510.00$
 $R = 2550.000$
 $SE = 04$

PI STA. 83+60.237
 $\Delta = 257.00$
 $L = 514.00$
 $R = 2570.000$
 $SE = 04$

PI STA. 84+20.239
 $\Delta = 259.00$
 $L = 518.00$
 $R = 2590.000$
 $SE = 04$

PI STA. 84+80.241
 $\Delta = 261.00$
 $L = 522.00$
 $R = 2610.000$
 $SE = 04$

PI STA. 85+40.243
 $\Delta = 263.00$
 $L = 526.00$
 $R = 2630.000$
 $SE = 04$

PI STA. 86+00.245
 $\Delta = 265.00$
 $L = 530.00$
 $R = 2650.000$
 $SE = 04$

PI STA. 86+60.247
 $\Delta = 267.00$
 $L = 534.00$
 $R = 2670.000$
 $SE = 04$

PI STA. 87+20.249
 $\Delta = 269.00$
 $L = 538.00$

PROJECT REFERENCE NO. P-312
 SHEET NO. 212
 ROADWAY DESIGN ENGINEER
 METRIC ENGINEERING
 PRELIMINARY PLANS
 CONVENTION: 1/1
 R/W REV.

















Design Exception required for the design speed from 100 km/h to 30 km/h.

$PI\ Stn\ 11+27.704$
 $\Delta = 17.27122$ (LT)
 $L = 39.979$
 $R = 247.1400$
 $SE = 0.3$

$PI\ Stn\ 11+84.460$
 $\Delta = 19.40137$ (RT)
 $L = 50.949$
 $R = 26.078$
 $SE = 0.4$

$PI\ Stn\ 12+42.533$
 $\Delta = 44.19008$ (LT)
 $L = 510.96$
 $R = 160.000$

$PI\ Stn\ 13+04.715$
 $\Delta = 23.18544$ (LT)
 $L = 69.108$
 $R = 160.000$




SEE SHEET 6 FOR -L-, -Y-, & -YI- PROFILE
 MICHAEL CLAYCOMB and wife,
 JACQUELINE CLAYCOMB
 PI Stn 10+787.87
 $\Delta = 146.044$
 $L = 78.787$
 $R = 157.000$

REVISIONS
 R/W REVISION 02/18/04 SM -1- REMOVED R/W MONUMENT & YI -11+597.87 AND ADDED ADDITIONAL TEMPORARY CONSTRUCTION EASEMENT TO PARCEL 4
 R/W REVISION 07/14/03 DS -2- REVISED R/W MONUMENTS, STATIONS, OFFSETS & EASEMENTS DUE TO UPDATED SURVEYS ON PARCELS 12, 13 & 4 ADDED R/OE PARCEL 3


NAD 83


214



SITE 1

PLAN VIEW

 DENOTES TEMPORARY SURFACE WATER IMPACT



NCDOT
 DIVISION OF HIGHWAYS
 BUNCOMBE COUNTY
 PROJECT: 32877.11 (B-3119)
 BRIDGE NO. 653 OVER BROAD
 RIVER ON SR 2804 AND BRIDGE
 NO. 654 OVER SAND BRANCH
 ON SR 2786
 SHEET 9 OF 12 1/26/05


PROJECT REFERENCE NO. B-319
 SHEET NO. 10
 ROADWAY DESIGN
 PROPOSED
 PRELIMINARY PLANS
 CONTRACTOR
 R/W REV.

FOR -L2- PROFILE SEE SHEET 6

215

Design Exception required for the design speed from 100 km/h to 30 km/h.

-L2-
 PI Sta. 10+34.883 Δ = 28.50 RT Δ = 18.57 RT
 PI Sta. 10+67.508 Δ = 36.14 RT Δ = 24.70 RT
 PI Sta. 10+76.666 Δ = 30.53 RT Δ = 19.70 RT
 R = 30.000
 SE = 02
 V = 30 KM/H
 HIGH WATER MARK: 10+30.000
 ON ST. 21.750
 WOODS



REVISIONS
 R/W REVISION 01/14/05 - ADDED R/W MONUMENT STA 10+76.666 FT AND REVISED R/W LINE, ADDED 2 TEMPORARY DRAINAGE EASEMENTS ON PARCEL 5

SEE SHEET 6 FOR -L2- PROFILE


PROJECT REFERENCE NO.	B-319	SHEET NO.	
ROADWAY DESIGNER	ENGINEER	HYDRAULICS NUMBER	
PRELIMINARY PLANS			
CONSTRY.		R/W REV.	

FOR -L2- PROFILE SEE SHEET 6

216

Design Exception required for the design speed from 100 km/h to 30 km/h.

-L2-
 $PI Sta. 10+34.883$
 $\Delta = 28.50'$
 $R = 70.00'$
 $SE = 0.2$
 $V = 30$ KM/H
 $PI Sta. 10+47.508$
 $\Delta = 36.14'$
 $R = 100.00'$
 $SE = 0.2$
 $V = 30$ KM/H
 $PI Sta. 10+56.300$
 $\Delta = 30.53'$
 $R = 115.000'$
 $SE = 0.2$
 $V = 30$ KM/H
 $PI Sta. 10+76.666$
 $\Delta = 18.973'$
 $R = 115.000'$
 $SE = 0.2$
 $V = 30$ KM/H
 $PI Sta. 10+81.872$
 $\Delta = 62.010'$
 $R = 115.000'$
 $SE = 0.2$
 $V = 30$ KM/H



DENOTES TEMPORARY SURFACE IMPACTS



SEE SHEET 6 FOR -L2- PROFILE

REVISIONS
 R/W REVISION 01/14/05 DS - ADDED R/W MONUMENT STA 10+76.666 RT AND REVISED R/W LINE; ADDED 2 TEMPORARY DRAINAGE ESSENTS ON PARCEL 5

217

6

LINDA and husband,
ERNEST RUSSELL



JACK E. FERREIRA

JAMES E. and wife,
BETTY F. GILLIAM

 DENOTES TEMPORARY
SURFACE WATER
IMPACTS

SITE 2




PLAN VIEW

NCDOT
 DIVISION OF HIGHWAYS
 BUNCOMBE COUNTY
 PROJECT: 32877.L1 (B-3119)
 BRIDGE NO. 653 OVER BROAD
 RIVER ON SR 2804 AND BRIDGE
 NO. 654 OVER SAND BRANCH
 ON SR 2786
 SHEET 12 OF 12 1/26/05

CONTRACT: C20122 TIP PROJECT: B-319

See Sheet 1A For Index of Sheets.
See Sheet 1B For Conventional Symbols



VICINITY MAP

This project is not within any municipal boundaries.

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

BUNCOMBE COUNTY

LOCATION: BRIDGE NO. 653 OVER THE BROAD RIVER ON SR 2804
AND BRIDGE NO. 654 OVER SAND BRANCH CREEK ON SR 2786




TYPE OF WORK: GRADING, DRAINAGE, PAVING,
CULVERT, AND STRUCTURE



ALL DIMENSIONS IN
THESE PLANS ARE IN METERS

STATE	N.C.	PROJECT NUMBER	B-3119
COUNTY	BUNCOMBE	PROJECT NAME	SR 2804/2786
DISTRICT	14	DESIGNER	PE, UTL
DATE		DATE	

PRELIMINARY PLANS
NO. 1000-1000-1000-1000-1000



THERE IS NO CONTROL OF ACCESS ON THIS PROJECT.
DESIGN EXCEPTION REQUIRED FOR THE DESIGN SPEED FROM 100 KMH TO 30 KMH.
CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

GRAPHIC SCALES

PLANS: 1" = 100'

PROFILE (HORIZONTAL): 1" = 100'

PROFILE (VERTICAL): 1" = 10'

DESIGN DATA

ADT 2006	=	183
ADT 2025	=	342
DHV	=	10 %
D	=	60 %
T	=	3 %
V	=	30 km/h**
* TST 1 % DUAL 2 %		
FUNC CLASS = LOCAL		

PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT B-3119	=	0.098 km
LENGTH STRUCTURE TIP PROJECT B-3119	=	0.053 km
TOTAL LENGTH TIP PROJECT B-3119	=	0.151 km

Prepared in the Office of:

DIVISION OF HIGHWAYS
1000 Birch Ridge Dr., Raleigh, NC 27610

RIGHT OF WAY DATE: MAY 28, 2004

LETTING DATE: MAY 16, 2006

PROJECT ENGINEER: TONY HOUSER, PE

PROJECT MANAGER: LEE ANN MOORE

HYDRAULICS ENGINEER: _____

ROADWAY DESIGN ENGINEER: _____

STATE ENGINEER: _____

DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION

PROJECT REFERENCE NO. **B-319** SHEET NO. **3**

TOWNSHIP DESIGN NUMBER

HYDRAULICS ENGINEER

CONTRACT NO.

R/W REV.

METRIC

1 0 10

FOR -L2- PROFILE SEE SHEET 6


DATUM DESCRIPTION

THIS LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATE ESTABLISHED BY THE STATE PLANNING BOARD. THE STATE PLANNING BOARD HAS ADOPTED THE NAD 83 DATUM FOR ALL PROJECTS. THE AVERAGE HORIZONTAL DISTANCE FROM THE STATE PLANNING BOARD DATUM TO THIS PROJECT DATUM IS 10.000 METERS. THE AVERAGE VERTICAL DISTANCE FROM THE STATE PLANNING BOARD DATUM TO THIS PROJECT DATUM IS 0.000 METERS. ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES. VERTICAL DATUM USED IS NAVD 83.

**** Design Exception for the design speed from 100 km/h to 30 km/h.**

-L2-

PI STA 10+34.883 P/Sig 10+47.508 P/Sig 11+13.652
 $\Delta = 12.615$ $\Delta = 14.824$ $\Delta = 30.537$ $\Delta = 76.47$ (RT)
 $L = 70.14$ $L = 98.16$ $L = 317.80$ $L = 1150.00$
 $R = 30.000$ $R = 30.000$ $R = 30.000$ $R = 1150.000$
 $SE = 0.02$ $SE = 0.02$ $SE = 0.02$ $SE = 0.02$
 $V = 30$ $V = 30$ $V = 30$ $V = 30$ KM/H



220

SEE SHEET 6 FOR -L2- PROFILE

REVISIONS

R/W REVISION 01/14/05 DS - ADDED R/W MONUMENT STA 10+76.666 RT AND REVISED R/W LINE; ADDED 2 TEMPORARY DRAINAGE EASEMENTS ON PARCEL 5

PROJECT REFERENCE NO. SHEET NO. 1
 P-319
 HYDRAULICS
 ROAD DESIGN
 DRAWING



COUNTRY
 1/4" = 1'

PRELIMINARY PLANS
 100% DESIGN

STRUCTURE HYDRAULIC DATA
 DESIGN DISCHARGE - 25 CMS
 DESIGN FREQUENCY - 25 YRS
 DESIGN HW ELEVATION - 62.09 M
 BASE DISCHARGE - 40 CMS
 BASE FREQUENCY - 40 YRS
 BASE HW ELEVATION - 62.80 M
 OVERTOPPING DISCHARGE - 60 CMS
 OVERTOPPING FREQUENCY - 500 YRS
 OVERTOPPING ELEVATION - 62.20 M

TIME 7 RAILROAD BRIDGE IN DOUBLE TRACK
 WATER GATE ELEVATION 62.81 M (RT.)
 (C.C. STA. 10+42.000 TO 10+42.000)

END GRADE - L.S. STA. 10+42.000
 ELEV. 62.81 M

PI = 10+18.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

PI = 10+42.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

TIME 4 RAILROAD BRIDGE IN DOUBLE TRACK
 WATER GATE ELEVATION 62.81 M (RT.)
 (C.C. STA. 10+42.000 TO 10+42.000)

STRUCTURE HYDRAULIC DATA
 DESIGN DISCHARGE - 38 CMS
 DESIGN FREQUENCY - 25 YRS
 DESIGN HW ELEVATION - 65.15 M
 BASE DISCHARGE - 45 CMS
 BASE FREQUENCY - 40 YRS
 BASE HW ELEVATION - 65.73 M
 OVERTOPPING DISCHARGE - 500 YRS
 OVERTOPPING FREQUENCY - 500 YRS
 OVERTOPPING ELEVATION - 65.04 M

END GRADE - L.S. STA. 10+42.000
 ELEV. 62.81 M

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

TIME 4 RAILROAD BRIDGE IN DOUBLE TRACK
 WATER GATE ELEVATION 62.81 M (RT.)
 (C.C. STA. 10+42.000 TO 10+42.000)

STRUCTURE HYDRAULIC DATA
 DESIGN DISCHARGE - 38 CMS
 DESIGN FREQUENCY - 25 YRS
 DESIGN HW ELEVATION - 65.15 M
 BASE DISCHARGE - 45 CMS
 BASE FREQUENCY - 40 YRS
 BASE HW ELEVATION - 65.73 M
 OVERTOPPING DISCHARGE - 500 YRS
 OVERTOPPING FREQUENCY - 500 YRS
 OVERTOPPING ELEVATION - 65.04 M

END GRADE - L.S. STA. 10+42.000
 ELEV. 62.81 M

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

221

TIME 3 RAILROAD BRIDGE IN DOUBLE TRACK
 WATER GATE ELEVATION 62.81 M (RT.)
 (C.C. STA. 10+42.000 TO 10+42.000)

STRUCTURE HYDRAULIC DATA
 DESIGN DISCHARGE - 25 CMS
 DESIGN FREQUENCY - 25 YRS
 DESIGN HW ELEVATION - 62.09 M
 BASE DISCHARGE - 40 CMS
 BASE FREQUENCY - 40 YRS
 BASE HW ELEVATION - 62.80 M
 OVERTOPPING DISCHARGE - 60 CMS
 OVERTOPPING FREQUENCY - 500 YRS
 OVERTOPPING ELEVATION - 62.20 M

END GRADE - L.S. STA. 10+42.000
 ELEV. 62.81 M

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

TIME 3 RAILROAD BRIDGE IN DOUBLE TRACK
 WATER GATE ELEVATION 62.81 M (RT.)
 (C.C. STA. 10+42.000 TO 10+42.000)

STRUCTURE HYDRAULIC DATA
 DESIGN DISCHARGE - 25 CMS
 DESIGN FREQUENCY - 25 YRS
 DESIGN HW ELEVATION - 62.09 M
 BASE DISCHARGE - 40 CMS
 BASE FREQUENCY - 40 YRS
 BASE HW ELEVATION - 62.80 M
 OVERTOPPING DISCHARGE - 60 CMS
 OVERTOPPING FREQUENCY - 500 YRS
 OVERTOPPING ELEVATION - 62.20 M

END GRADE - L.S. STA. 10+42.000
 ELEV. 62.81 M

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

TIME 3 RAILROAD BRIDGE IN DOUBLE TRACK
 WATER GATE ELEVATION 62.81 M (RT.)
 (C.C. STA. 10+42.000 TO 10+42.000)

STRUCTURE HYDRAULIC DATA
 DESIGN DISCHARGE - 25 CMS
 DESIGN FREQUENCY - 25 YRS
 DESIGN HW ELEVATION - 62.09 M
 BASE DISCHARGE - 40 CMS
 BASE FREQUENCY - 40 YRS
 BASE HW ELEVATION - 62.80 M
 OVERTOPPING DISCHARGE - 60 CMS
 OVERTOPPING FREQUENCY - 500 YRS
 OVERTOPPING ELEVATION - 62.20 M

END GRADE - L.S. STA. 10+42.000
 ELEV. 62.81 M

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

TIME 3 RAILROAD BRIDGE IN DOUBLE TRACK
 WATER GATE ELEVATION 62.81 M (RT.)
 (C.C. STA. 10+42.000 TO 10+42.000)

STRUCTURE HYDRAULIC DATA
 DESIGN DISCHARGE - 25 CMS
 DESIGN FREQUENCY - 25 YRS
 DESIGN HW ELEVATION - 62.09 M
 BASE DISCHARGE - 40 CMS
 BASE FREQUENCY - 40 YRS
 BASE HW ELEVATION - 62.80 M
 OVERTOPPING DISCHARGE - 60 CMS
 OVERTOPPING FREQUENCY - 500 YRS
 OVERTOPPING ELEVATION - 62.20 M

END GRADE - L.S. STA. 10+42.000
 ELEV. 62.81 M

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

PI = 10+47.000
 EL. = 62.418 M
 VC = 24 M
 V = 36 M/A

15-05-2005
 JUN-2005

SEE SHEET 4 FOR L.S. & V.L.
 SEE SHEET 5 FOR L.S.