

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	215 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	25.4 SMI		
0004	1330000000-E	607	INCIDENTAL MILLING	765 SY		
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,820 TON		
0006	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	6,855 TON		
0007	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	649 TON		
0008	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	411 TON		
0009	1704000000-E	SP	PATCHING EXISTING PAVEMENT	440 TON		
0010	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0011	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	106,524 LF		
0012	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	65,340 LF		
0013	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	200 LF		
0014	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	200 LF		
0015	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	20 EA		
0016	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	12 EA		
0017	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	48,608 LF		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	838	EA	
0019	6084000000-E	1660	SEEDING & MULCHING	20.42	ACR	
0933/Dec08/Q241946.82/D58537100000/E19			Total Amount Of Bid For Entire Project :			

Contract No: C 201702

County: Chatham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General