

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (24 + 65.00-LREV-)	Lump Sum	L.S.	
0004	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB- BING	0.4 HA		
000E	0057000000-M	226	UNDERCUT EXCAVATION	200 M3		
000E	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-M	230	BORROW EXCAVATION	1,100 M3		
000E	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	4,640 M2		
000E	0318000000-M	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	35 MTN		
001C	0582000000-M	310	400MM CS PIPE CULVERTS, 1.63MM THICK	84 M		
0011	0706000000-M	310	300MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	20 M		
0012	0995000000-M	340	PIPE REMOVAL	96 M		
0013	1245000000-M	SP	SHOULDER RECONSTRUCTION	1.7 SKM		
0014	1330000000-M	607	INCIDENTAL MILLING	720 M2		
0015	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,400 MTN		
001E	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	70 MTN		
0017	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,350 MTN		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1539000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S12.5C	495 MTN		
001E	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	205 MTN		
002C	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	28 MTN		
0021	2022000000-M	815	SUBDRAIN EXCAVATION	80 M3		
0022	2033000000-M	815	SUBDRAIN FINE AGGREGATE	60 M3		
002E	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	120 M		
0024	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	12 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
002E	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	4 M		
0027	2264000000-M	840	PIPE PLUGS	0.1 M3		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
003C	2556000000-M	846	SHOULDER BERM GUTTER	60 M		
0031	2995000000-N	SP	GENERIC DRAINAGE ITEM TEMPORARY STEEL COVER FOR DRAINAGE STRUCTURE	1 EA		
0032	3345000000-M	864	REMOVE & RESET EXISTING GUARD- RAIL	207 M		
003E	3649000000-M	876	PLAIN RIP RAP, CLASS B	4 MTN		
0034	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	155 M2		
003E	4412000000-M	SP	WORK ZONE SIGNS (STATIONARY)	35 M2		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4412100000-M	SP	WORK ZONE SIGNS (PORTABLE)	9 M2		
0037	4412200000-M	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	2 M2		
003E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
003E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	3 EA		
004C	4430000000-N	1130	DRUMS	200 EA		
0041	4446100000-M	SP	BARRICADES (TYPE III)	18 M		
0042	4455000000-N	1150	FLAGGER	20 MD		
0043	4460000000-N	1155	WARNING LIGHTS (TYPE B)	3 EA		
0044	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	1 EA		
004E	4495000000-M	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	718 M		
004E	4500000000-M	1170	RESET PORTABLE CONCRETE BARRIER	694 M		
0047	4520000000-N	1266	TUBULAR MARKERS (FIXED)	50 EA		
004E	4620000000-M	1205	REMOVABLE TAPE PAVEMENT MARKING LINES (150MM)	175 M		
004E	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	4,796 M		
005C	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	933 M		
0051	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	50 M		
0052	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	25 M		
0053	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	17 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	9,381	M	
005E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	6	EA	
005E	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	12,733	M	
0057	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	6	EA	
005E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	150	EA	
005E	6000000000-M	1605	TEMPORARY SILT FENCE	230	M	
006C	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	75	MTN	
0061	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	65	MTN	
0062	6012000000-M	1610	SEDIMENT CONTROL STONE	45	MTN	
006E	6015000000-M	1615	TEMPORARY MULCHING	1	HA	
0064	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	50	KG	
006E	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5	MTN	
006E	6030000000-M	1630	SILT EXCAVATION	75	M3	
0067	6036000000-M	1631	MATTING FOR EROSION CONTROL	600	M2	
006E	6084000000-M	1660	SEEDING & MULCHING	1	HA	
006E	6087000000-M	1660	MOWING	0.5	HA	
007C	6090000000-M	1661	SEED FOR REPAIR SEEDING	25	KG	
0071	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.25	MTN	
0072	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	25	KG	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6108000000-M	1665	FERTILIZER TOPDRESSING	1.5 MTN		
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0075	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		
STRUCTURE ITEMS						
0076	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (25 + 36.132 -LREV- NBL)	Lump Sum	L.S.	
0077	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (25 + 36.132 -LREV- SBL)	Lump Sum	L.S.	
0078	8119000000-M	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	2,315 M3		
0079	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	431 M2		
0080	8161000000-M	420	GROOVING BRIDGE FLOORS	480.8 M2		
0081	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	157 M3		
0082	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (25 + 36.132 -LREV- NBL)	Lump Sum	L.S.	
0083	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (25 + 36.132 -LREV- SBL)	Lump Sum	L.S.	
0084	8217000000-M	425	REINFORCING STEEL (BRIDGE)	12,164 KG		
0085	8259000000-M	430	914MM PRESTRESSED CONCRETE GIRDERS	172.824 M		
0086	8364000000-M	450	HP310X79 STEEL PILES	420 M		
0087	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (25 + 36.132 -LREV- NBL)	Lump Sum	L.S.	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (25 + 36.132 -LREV- SBL)	Lump Sum	L.S.	
008F	8503000000-M	460	CONCRETE BARRIER RAIL	61 M		
009C	8608000000-M	876	PLAIN RIP RAP CLASS II (600MM THICK)	143 MTN		
0091	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	145 M2		
0092	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0093	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0094	8860000000-N	SP	GENERIC STRUCTURE ITEM CLEANING AND PAINTING EXISTING STEEL PILES AT STA 25 + 36.132 - LREV- NBL	Lump Sum	L.S.	
009E	8860000000-N	SP	GENERIC STRUCTURE ITEM CLEANING AND PAINTING EXISTING STEEL PILES AT STA 25 + 36.132 - LREV- SBL	Lump Sum	L.S.	
1605/Dec07/Q59889.574/D430996900000/E95			Total Amount Of Bid For Entire Project :			

C201512
COUNTY: CUMBERLAND

2/16/99

Contract No: C201512
County: Cumberland

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General