

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	5,292 SY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	701 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	25.4 SMI		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1" TO 3")	40,978 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	8,070 SY		
0007	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,225 TON		
0008	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	762 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	28,290 TON		
0010	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	1,035 TON		
0011	1525100000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)	71 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,858 TON		
0013	1704000000-E	SP	PATCHING EXISTING PAVEMENT	2,370 TON		
0014	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0015	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0016	2830000000-N	858	ADJUSTMENT OF MANHOLES	143 EA		
0017	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	53 EA		
0018	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	155,221 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	203,241	LF	
0020	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	2,620	LF	
0021	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	500	LF	
0022	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,775	LF	
0023	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	107	EA	
0024	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	282	EA	
0025	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,000	LF	
0026	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,991	EA	
0027	6084000000-E	1660	SEEDING & MULCHING	19	ACR	
0028	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	9,400	LF	
0029	7456000000-E	1726	LEAD-IN CABLE (***** (18-4)	2,000	LF	
0030	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	75	TON	

1053/Jan04/Q471107.4/D92552200000/E30

Total Amount Of Bid For Entire Project :

**Contract No: C 201712**

**County: Durham**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General