

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	3,350 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	210 TON		
0007	0106000000-E	230	BORROW EXCAVATION	17,800 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	183 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	600 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,100 SY		
0011	0206000000-E	SP	TEMPORARY SHORING - BARRIER SUPPORTED	500 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	720 TON		
0013	0342000000-E	310	*** SIDE DRAIN PIPE (12")	28 LF		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	32 LF		
0015	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	208 LF		
0016	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (84", 0.168")	60 LF		
0017	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK (18", 0.064" W/ TEE)	44 LF		
0018	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	44 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	1 EA		
0020	0995000000-E	340	PIPE REMOVAL	1,116 LF		
0021	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	700 LB		
0022	1121000000-E	520	AGGREGATE BASE COURSE	1,740 TON		
0023	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0024	1275000000-E	600	PRIME COAT	1,040 GAL		
0025	1330000000-E	607	INCIDENTAL MILLING	500 SY		
0026	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,900 TON		
0027	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,705 TON		
0028	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,790 TON		
0029	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	720 TON		
0030	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	225 TON		
0031	2022000000-E	815	SUBDRAIN EXCAVATION	530 CY		
0032	2033000000-E	815	SUBDRAIN FINE AGGREGATE	400 CY		
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,327 LF		
0034	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	72 EA		
0035	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	5 EA		
0036	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	30 LF		
0037	2253000000-E	840	PIPE COLLARS	1.5 CY		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2264000000-E	840	PIPE PLUGS	0.5 CY		
0039	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	44 EA		
0040	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	7 LF		
0041	2354200000-N	840	FRAME WITH GRATE, STD 840.24	1 EA		
0042	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	6 EA		
0043	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	5 EA		
0044	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0045	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	14 EA		
0046	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	16 EA		
0047	2472000000-N	840	GENERIC DRAINAGE ITEM MODIFIED DRAINAGE OUTLET	1 EA		
0048	2529000000-E	SP	GENERIC GRADING ITEM (SF) TEMPORARY FABRIC WALL	760 SF		
0049	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	5,770 LF		
0050	2591000000-E	848	4" CONCRETE SIDEWALK	3,125 SY		
0051	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	16 EA		
0052	2612000000-E	848	6" CONCRETE DRIVEWAY	525 SY		
0053	3030000000-E	862	STEEL BM GUARDRAIL	412.5 LF		
0054	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0055	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0057	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	175 LF		
0058	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0059	3628000000-E	876	RIP RAP, CLASS I	52 TON		
0060	3649000000-E	876	RIP RAP, CLASS B	18 TON		
0061	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	722 SY		
0062	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	125 LF		
0063	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0064	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0065	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	9 EA		
0066	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	226 SF		
0067	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	234 SF		
0068	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0069	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0070	4430000000-N	1130	DRUMS	120 EA		
0071	4435000000-N	1135	CONES	25 EA		
0072	4445000000-E	1145	BARRICADES (TYPE III)	50 LF		
0073	4450000000-N	1150	FLAGGER	1,440 HR		
0074	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0075	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	4480000000-N	1165	TMIA	2	EA	
0077	4485000000-E	1170	PORTABLE CONCRETE BARRIER	170	LF	
0078	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	220	LF	
0079	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	270	EA	
0080	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	600	LF	
0081	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	10,230	LF	
0082	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	100	LF	
0083	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	48	EA	
0084	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	40,150	LF	
0085	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	200	LF	
0086	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	20	EA	
0087	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	350	LF	
0088	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	50	LF	
0089	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	20	EA	
0090	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	340	EA	
0091	5325800000-E	1510	8" WATER LINE	130	LF	
0092	5326200000-E	1510	12" WATER LINE	2,542	LF	
0093	5546000000-E	1515	8" VALVE	1	EA	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	5558000000-E	1515	12" VALVE	2 EA		
0095	5643100000-E	1515	3/4" WATER METER	16 EA		
0096	5666000000-E	1515	FIRE HYDRANT	7 EA		
0097	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0098	5691300000-E	1520	8" SANITARY GRAVITY SEWER	1,729 LF		
0099	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	18 EA		
0100	5775000000-E	1525	4' DIA UTILITY MANHOLE	10 EA		
0101	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	49 LF		
0102	5882000000-N	SP	GENERIC UTILITY ITEM BREAK DOWN & FILL ABANDONED SEPTIC TANK	6 EA		
0103	5882000000-N	SP	GENERIC UTILITY ITEM BREAK DOWN & REBUILD EXISTING MANHOLE	2 EA		
0104	6000000000-E	1605	TEMPORARY SILT FENCE	5,620 LF		
0105	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	585 TON		
0106	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,515 TON		
0107	6012000000-E	1610	SEDIMENT CONTROL STONE	910 TON		
0108	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0109	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0110	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0111	6024000000-E	1622	TEMPORARY SLOPE DRAINS	75 LF		
0112	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0113	6029000000-E	SP	SAFETY FENCE	250 LF		
0114	6030000000-E	1630	SILT EXCAVATION	3,320 CY		
0115	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,850 SY		
0116	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	551 SY		
0117	6042000000-E	1632	1/4" HARDWARE CLOTH	980 LF		
0118	6045000000-E	SP	*** TEMPORARY PIPE (18")	260 LF		
0119	6069000000-E	1638	STILLING BASINS	100 CY		
0120	6070000000-N	SP	SPECIAL STILLING BASINS	3 EA		
0121	6084000000-E	1660	SEEDING & MULCHING	5.5 ACR		
0122	6087000000-E	1660	MOWING	2.5 ACR		
0123	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0124	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0125	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0126	6108000000-E	1665	FERTILIZER TOPDRESSING	4 TON		
0127	6111000000-E	SP	IMPERVIOUS DIKE	75 LF		
0128	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0129	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	30 EA		
0130	7060000000-E	1705	SIGNAL CABLE	1,060 LF		
0131	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	9 EA		
0132	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	4 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0133	7264000000-E	1710	MESSENGER CABLE (3/8")	655	LF	
0134	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	170	LF	
0135	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	2	EA	
0136	7360000000-N	1720	WOOD POLE	1	EA	
0137	7372000000-N	1721	GUY ASSEMBLY	2	EA	
0138	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	275	LF	
0139	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	580	LF	
0140	7576000000-N	SP	METAL STRAIN SIGNAL POLE	4	EA	
0141	7613000000-N	SP	SOIL TEST	4	EA	
0142	7614100000-E	SP	DRILLED PIER FOUNDATION	24	CY	
0143	7636000000-N	1745	SIGN FOR SIGNALS	3	EA	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0144	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	480	LF	
AA1						
0145	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,232	LF	
AA1						
0146	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	716	LF	
AA1						
0147	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	576	LF	
AA1						
*** OR ***						
0148	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	316	LF	
AA2						
0149	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,868	LF	
AA2						

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0150 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	308 LF		
0151 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	240 LF		
0152 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (12")	164 LF		
0153 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	364 LF		
0154 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	408 LF		
0155 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	336 LF		
*** OR ***						
0156 AA3	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	316 LF		
0157 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,868 LF		
0158 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	308 LF		
0159 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	240 LF		
0160 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (12", 0.064")	164 LF		
0161 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	364 LF		
0162 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	408 LF		
0163 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")	336 LF		

***** END SCHEDULE AA *****

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0164	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (23+12.30 -L-)	Lump Sum	L.S.	
0165	8126000000-N	414	CULVERT EXCAVATION, STA ***** (23+12.30 -L-)	Lump Sum	L.S.	
0166	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	84 TON		
0167	8196000000-E	420	CLASS A CONCRETE (CULVERT)	123.5 CY		
0168	8245000000-E	425	REINFORCING STEEL (CULVERT)	15,072 LB		
1338/Dec05/Q167966.5/D616584900000/E168			Total Amount Of Bid For Entire Project :			

Contract No: C 201328 (U-3612)

County: Guilford

**ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION**

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General