

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (13+67.50-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	350 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	15 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	100 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	124 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	60 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	390 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	280 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35 TON		
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
002C	2000000000-N	806	RIGHT OF WAY MARKERS	17 EA		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.***** (840.33)	1 EA		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
003C	2556000000-E	846	SHOULDER BERM GUTTER	70 LF		
0031	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0032	3030000000-E	862	STEEL BM GUARDRAIL	150 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3614000000-E	876	RIP RAP, CLASS I	2 SY		
0037	3649000000-E	876	RIP RAP, CLASS B	4 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	178 SY		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,890 SF		
004C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	160 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	32 SF		
0042	4430000000-N	1130	DRUMS	43 EA		
0043	4435000000-N	1135	CONES	43 EA		
0044	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
004E	4450000000-N	1150	FLAGGER	1,376 HR		
004E	4507000000-E	SP	WATER FILLED BARRIER	380 LF		
0047	4508000000-E	SP	RESET WATER FILLED BARRIER	240 LF		
004E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (1)	1,175 LF		
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,090 LF		
005C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	72 LF		
0051	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	18 LF		
0052	6000000000-E	1605	TEMPORARY SILT FENCE	900 LF		
0053	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	145 TON		
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	75 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
005E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
006C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0061	6029000000-E	SP	SAFETY FENCE	1,000 LF		
0062	6030000000-E	1630	SILT EXCAVATION	385 CY		
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,700 SY		
0064	6037000000-E	SP	COIR FIBER MAT	20 SY		
006E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	100 SY		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0067	6071030000-E	SP	COIR FIBER BAFFLES	80 LF		
006E	6071050000-E	SP	*** SKIMMER (2")	3 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
007C	6087000000-E	1660	MOWING	1.5 ACR		
0071	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0072	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0074	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
007E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0077	6123000000-E	1670	REFORESTATION	0.2 ACR		
007E	7060000000-E	1705	SIGNAL CABLE	3,140 LF		
007E	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	16 EA		
008C	7264000000-E	1710	MESSENGER CABLE (3/8")	1,430 LF		
0081	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	290 LF		
0082	7360000000-N	1720	WOOD POLE	13 EA		
0083	7372000000-N	1721	GUY ASSEMBLY	22 EA		
0084	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
008E	7420000000-E	1722	2" RISER WITH WEATHERHEAD	6 EA		
008E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	575 LF		
0087	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	2,940 LF		
008E	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	4 EA		
008E	7636000000-N	1745	SIGN FOR SIGNALS	8 EA		
009C	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0091	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	3 EA		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0092	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+67.50 -L-)	Lump Sum	L.S.	
0093	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	2,250.6 SF		
0094	8161000000-E	420	GROOVING BRIDGE FLOORS	2,540 SF		
0095	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	98.8 CY		
0096	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+67.50 -L-)	Lump Sum	L.S.	
0097	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	66,400 LS		
0098	8468000000-E	460	ONE BAR METAL RAIL	139.2 LF		
0099	8517000000-E	460	1'***X ***** CONCRETE PARAPET (1'-0" X 1'-6")	154.2 LF		
0100	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	48 TON		
0101	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	64 SY		
0102	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0103	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0104	8860000000-N	SP	GENERIC STRUCTURE ITEM METALLIZATION AT STA 13+67.50 -L-	Lump Sum	L.S.	
***** BEGIN SCHEDULE IA ***** ***** (2 ALTERNATES) *****						
0105	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,857 LB		
IA1						
0106	8867000000-E	SP	GENERIC STRUCTURE ITEM 10.75" DIA. MICROPILES	296 LF		
IA1						
0107	8867000000-E	SP	GENERIC STRUCTURE ITEM PERMANENT STEEL CASING FOR 10.75" DIA. MICROPILES	201 LF		
IA1						

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E IA1	8897000000-N	SP	GENERIC STRUCTURE ITEM 10.75" DIA. MICROPILE PROOF LOAD TEST	2	EA	
*** OR ***						
010E IA2	8096000000-E	SP	PILE EXCAVATION IN SOIL	95	LF	
011C IA2	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	153	LF	
0111 IA2	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,739	LB	
0112 IA2	8385000000-E	450	PP ** X **** STEEL PILES (12 X 0.50)	296	LF	

***** END SCHEDULE IA *****

0834/Jan11/Q133205.0/D557707580000/E112

Total Amount Of Bid For Entire Project :

Contract No: C 201635

County: Ashe

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General