

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	6,050 CY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+94.30)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	131 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	550 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	157 CY		
0010	0141000000-E	240	BERM DITCH CONSTRUCTION	200 LF		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	654 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	598 SY		
0013	0199000000-E	SP	TEMPORARY SHORING	290 SF		
0014	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	48 TON		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	96 LF		
0016	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	28 LF		
0017	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0018	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	216 LF		
0019	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0021	0986000000-E	SP	GENERIC PIPE ITEM 16" PVC DRAIN PIPE	355 LF		
0022	0995000000-E	340	PIPE REMOVAL	50 LF		
0023	1121000000-E	520	AGGREGATE BASE COURSE	92 TON		
0024	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0025	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	338 TON		
0026	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	61 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	171 TON		
0028	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	170 TON		
0029	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
0030	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0031	2000000000-N	806	RIGHT OF WAY MARKERS	27 EA		
0032	2022000000-E	815	SUBDRAIN EXCAVATION	215 CY		
0033	2033000000-E	815	SUBDRAIN FINE AGGREGATE	162 CY		
0034	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	985 LF		
0035	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0036	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0037	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2253000000-E	840	PIPE COLLARS	0.5 CY		
0039	2264000000-E	840	PIPE PLUGS	0.13 CY		
0040	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0041	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.85 LF		
0042	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0043	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0044	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0045	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0047	2556000000-E	846	SHOULDER BERM GUTTER	126.5 LF		
0048	3030000000-E	862	STEEL BM GUARDRAIL	400 LF		
0049	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0050	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	2 EA		
0051	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0052	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0053	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	6 EA		
0054	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0055	3360000000-E	863	REMOVE EXISTING GUARDRAIL	150 LF		
0056	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	62.5 LF		

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	1 EA		
0058	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1 EA		
0059	3628000000-E	876	RIP RAP, CLASS I	24 TON		
0060	3635000000-E	876	RIP RAP, CLASS II	22 TON		
0061	3649000000-E	876	RIP RAP, CLASS B	33 TON		
0062	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,035.8 SY		
0063	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0064	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		
0065	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0066	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	11 EA		
0067	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,299 SF		
0068	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	320 SF		
0069	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	230 SF		
0070	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0071	4430000000-N	1130	DRUMS	105 EA		
0072	4435000000-N	1135	CONES	80 EA		
0073	4445000000-E	1145	BARRICADES (TYPE III)	278 LF		
0074	4450000000-N	1150	FLAGGER	470 HR		
0075	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	4480000000-N	1165	TMIA	2	EA	
0077	4485000000-E	1170	PORTABLE CONCRETE BARRIER	240	LF	
0078	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	20	EA	
0079	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,772	LF	
0080	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,772	LF	
0081	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	82	LF	
0082	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	69	LF	
0083	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	4	EA	
0084	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	20,248	LF	
0085	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	46	LF	
0086	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	158	LF	
0087	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4	EA	
0088	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	400	LF	
0089	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	43	LF	
0090	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	40	LF	
0091	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	2	EA	
0092	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	32	EA	

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6000000000-E	1605	TEMPORARY SILT FENCE	1,055 LF		
0094	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	230 TON		
0095	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	320 TON		
0096	6012000000-E	1610	SEDIMENT CONTROL STONE	540 TON		
0097	6015000000-E	1615	TEMPORARY MULCHING	3.5 ACR		
0098	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	165 LB		
0099	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.85 TON		
0100	6029000000-E	SP	SAFETY FENCE	1,465 LF		
0101	6030000000-E	1630	SILT EXCAVATION	1,600 CY		
0102	6036000000-E	1631	MATTING FOR EROSION CONTROL	800 SY		
0103	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	350 SY		
0104	6042000000-E	1632	1/4" HARDWARE CLOTH	125 LF		
0105	6070000000-N	SP	SPECIAL STILLING BASINS	18 EA		
0106	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0107	6087000000-E	1660	MOWING	1.75 ACR		
0108	6090000000-E	1661	SEED FOR REPAIR SEEDING	110 LB		
0109	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.55 TON		
0110	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	110 LB		
0111	6108000000-E	1665	FERTILIZER TOPDRESSING	2.45 TON		
0112	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0113	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	16 EA		
0114	6123000000-E	1670	REFORESTATION	0.45 ACR		
0115	7060000000-E	1705	SIGNAL CABLE	640 LF		
0116	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	4 EA		
0117	7264000000-E	1710	MESSENGER CABLE (3/8")	450 LF		
0118	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	14 LF		
0119	7360000000-N	1720	WOOD POLE	4 EA		
0120	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0121	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0122	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0123	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	361 LF		
0124	7456000000-E	1726	LEAD-IN CABLE (***** (18-2)	590 LF		
0125	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0126	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	1 EA		
0160	2529000000-E	SP	GENERIC GRADING ITEM (SF) TEMPORARY SHORING, CONTRACTOR DESIGNED	1,550 SF		

STRUCTURE ITEMS

0127	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (11+97.50 -L-)	Lump Sum	L.S.	
------	--------------	----	--	----------	------	--

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0128	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (12+94.300 -L-)	Lump Sum	L.S.	
0129	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (11+97.50 -L-)	Lump Sum	L.S.	
0130	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+94.300 -L-)	Lump Sum	L.S.	
0131	8084000000-N	410	FOUNDATION EXCAVATION FOR END BENT ** AT STATION ***** (1, 11+97.50-L-)	Lump Sum	L.S.	
0132	8105500000-E	SP	***-*** DIA DRILLED PIERS IN SOIL (4'-6")	31.7 LF		
0133	8105500000-E	SP	***-*** DIA DRILLED PIERS IN SOIL (6'-0")	14.44 LF		
0134	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	10.17 LF		
0135	8105600000-E	SP	***-*** DIA DRILLED PIERS NOT IN SOIL (4'-6")	32 LF		
0136	8105600000-E	SP	***-*** DIA DRILLED PIERS NOT IN SOIL (6'-0")	26.24 LF		
0137	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	19.68 LF		
0138	8111000000-E	SP	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (4'-6")	31.6 LF		
0139	8111000000-E	SP	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (6'-0")	14.44 LF		
0140	8113000000-N	SP	SID INSPECTION	3 EA		
0141	8115000000-N	SP	CROSSHOLE SONIC LOGGING	4 EA		

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0142	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,477 CY		
0143	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	24,769 SF		
0144	8161000000-E	420	GROOVING BRIDGE FLOORS	21,269 SF		
0145	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	406.1 CY		
0146	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11+97.50-L-)	Lump Sum	L.S.	
0147	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+94.300 -L-)	Lump Sum	L.S.	
0148	8217000000-E	425	REINFORCING STEEL (BRIDGE)	81,278 LB		
0149	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,687 LB		
0150	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	1,124,300 LS		
0151	8364000000-E	450	HP12X53 STEEL PILES	395 LF		
0152	8391000000-N	450	STEEL PILE POINTS	19 EA		
0153	8503000000-E	460	CONCRETE BARRIER RAIL	1,473.58 LF		
0154	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	853 TON		
0155	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	947 SY		
0156	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0157	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0158	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

County : Mitchell, Yancey

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0159	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (11+97.50 -L-)	Lump Sum	L.S.	

0809/Feb13/Q1317213.78/D738072540000/E158

Total Amount Of Bid For Entire Project :

Contract No: C 201180

County: Mitchell & Yancey

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General