

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+98.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	3,770 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	250 CY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	56 LF		
0010	0344000000-E	310	18" SIDE DRAIN PIPE	40 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0014	0995000000-E	340	PIPE REMOVAL	68 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	405 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	310 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40	TON	
001E	2000000000-N	806	RIGHT OF WAY MARKERS	14	EA	
002C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
0022	2556000000-E	846	SHOULDER BERM GUTTER	188	LF	
0023	3030000000-E	862	STEEL BM GUARDRAIL	600	LF	
0024	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50	LF	
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
002E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3	EA	
002E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
002E	3649000000-E	876	RIP RAP, CLASS B	55	TON	
003C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	445	SY	
0031	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	4	EA	
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	459	SF	
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119	SF	
0034	4430000000-N	1130	DRUMS	15	EA	
003E	4435000000-N	1135	CONES	15	EA	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,680	LF	
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	19	EA	
003E	6000000000-E	1605	TEMPORARY SILT FENCE	550	LF	
004C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150	TON	
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180	TON	
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	60	TON	
0043	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	60	LF	
0047	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
004E	6029000000-E	SP	SAFETY FENCE	175	LF	
004E	6030000000-E	1630	SILT EXCAVATION	560	CY	
005C	6036000000-E	1631	MATTING FOR EROSION CONTROL	675	SY	
0051	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	400	SY	
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	40	LF	
005E	6071030000-E	SP	COIR FIBER BAFFLES	150	LF	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
005E	6087000000-E	1660	MOWING	0.5 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0057	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
006C	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0061	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0062	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
006E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17 + 98.00 -L-)	Lump Sum	L.S.	
0064	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17 + 98.00 -L-)	Lump Sum	L.S.	
006E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	38 LF		
006E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	38 LF		
0067	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	40 LF		
006E	8113000000-N	SP	SID INSPECTION	2 EA		
006E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+98.00 -L-)	Lump Sum	L.S.	
0071	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	78.4 CY		
0072	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+98.00 -L-)	Lump Sum	L.S.	
0073	8217000000-E	425	REINFORCING STEEL (BRIDGE)	23,517 LB		
0074	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,445 LB		
0075	8364000000-E	450	HP12X53 STEEL PILES	175 LF		
0076	8503000000-E	460	CONCRETE BARRIER RAIL	234.92 LF		
0077	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	910 TON		
0078	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,012 SY		
0079	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008C	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,292.04 LF		

1516/Feb02/Q46881.96/D375499710000/E80

Total Amount Of Bid For Entire Project :

Contract No: C201636

County: Johnston

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General