

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 12.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	5 TON		
0009	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	40 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0011	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	310 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	360 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	37 TON		
0015	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
0016	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0017	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0018	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0020	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0022	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.16 LF		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	300 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	575 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0028	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0029	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0030	3856000000-E	876	FILTER FABRIC FOR DRAINAGE	165 SY		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	410 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0033	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0034	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,000 LF		
0035	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10 EA		
0036	6000000000-E	1605	TEMPORARY SILT FENCE	725 LF		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6008000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	55 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	115 TON		
004C	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0044	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
004E	6029000000-E	SP	SAFETY FENCE	300 LF		
0046	6030000000-E	1630	SILT EXCAVATION	50 CY		
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	175 SY		
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	500 LF		
004E	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
005C	6087000000-E	1660	MOWING	1 ACR		
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
005E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	
0057	6123000000-E	1670	REFORESTATION	0.1	ACR	
STRUCTURE ITEMS						
0058	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 12.50-L-)	Lump Sum	L.S.	
0059	8112730000-N	SP	PDA TESTING	1	EA	
0060	8112740000-N	SP	PDA ASSISTANCE	1	EA	
0061	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16 + 12.50-L-)	Lump Sum	L.S.	
0062	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	36.6	CY	
0063	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 12.50-L-)	Lump Sum	L.S.	
0064	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,230	LB	
0065	8364000000-E	450	HP12X53 STEEL PILES	600	LF	
0066	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	455	LF	
0067	8393000000-N	450	PILE REDRIVES	7	EA	
0068	8503000000-E	460	CONCRETE BARRIER RAIL	165.5	LF	
0069	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	229	TON	
0070	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	255	SY	
0071	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	991.5 LF		

0753/Feb08/Q22979.11/D332016570000/E72

Total Amount Of Bid For Entire Project :

C201600 (B-4174)

Lenoir County

2/16/99
Z-13

Contract No: C201600

County: Lenoir

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General