

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	53 TON		
001S	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
002C	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	2 EA		
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0022	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
002S	3030000000-E	862	STEEL BM GUARDRAIL	450 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0027	3649000000-E	876	RIP RAP, CLASS B	310 TON		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	990 SY		
002S	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	22.5 SF		
003C	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	53 LF		
0031	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0032	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	7 EA		
003S	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	381 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114 SF		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4445000000-E	1145	BARRICADES (TYPE III)	100 LF		
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,200 LF		
003E	5326200000-E	1510	12" WATER LINE	352 LF		
003E	5558000000-E	1515	12" VALVE	1 EA		
004C	5648000000-N	1515	RELOCATE WATER METER	2 EA		
0041	5672000000-N	1515	RELOCATE FIRE HYDRANT	2 EA		
0042	5804000000-E	1530	ABANDON 12" UTILITY PIPE	355 LF		
004E	6000000000-E	1605	TEMPORARY SILT FENCE	350 LF		
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	135 TON		
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
0047	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
005C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	120 LF		
0051	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
0052	6029000000-E	SP	SAFETY FENCE	200 LF		
005E	6030000000-E	1630	SILT EXCAVATION	440 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	200 SY		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
005E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	50 SY		
0057	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
005E	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
005E	6087000000-E	1660	MOWING	0.5 ACR		
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006C	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0064	6111000000-E	SP	IMPERVIOUS DIKE	60 LF		
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		

***** BEGIN SCHEDULE AA *****
***** (3 ALTERNATES) *****

0067	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	112 LF		
AA1						

*** OR ***

006E	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	112 LF		
AA2						

*** OR ***

006E	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (30", 0.079")	112 LF		
AA3						

***** END SCHEDULE AA *****

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
007C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 56.25-L-)	Lump Sum	L.S.	
0071	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,090 CY		
0072	8156000000-E	SP	CONCRETE WEARING SURFACE	5,011 SF		
0073	8161000000-E	420	GROOVING BRIDGE FLOORS	5,969 SF		
0074	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	58.8 CY		
007E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 56.25-L-)	Lump Sum	L.S.	
0076	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,776 LB		
0077	8364000000-E	450	HP12X53 STEEL PILES	675 LF		
007E	8387000000-E	450	PP 18 X 0.50 GALVANIZED STEEL PILES	560 LF		
007E	8503000000-E	460	CONCRETE BARRIER RAIL	304.67 LF		
008C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	270 TON		
0081	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	301 SY		
0082	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0083	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0084	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,828 LF		

Contract No: C201427

County: Catawba

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General