

Project Special Provisions
Utility Construction

For this project, add the following project special provision to the Standard Specifications for Roads and Structures July 2006 as follows:

DESCRIPTION:

Temporarily loosening the connection between the existing aerial waterline and the pier beneath.

CONSTRUCTION REQUIREMENTS:


The existing bolts and connections on all the existing piers which the existing six (6) inch ductile iron water line is resting shall be loosened to accommodate any possible lateral movement of the piers. This lateral movement could occur due to the proposed fill's compaction to the existing and natural unstabilized and saturated soil. Any nuts or bolts to be replaced shall be replaced in kind. The loosening of these connections shall occur before any earthwork is performed in this vicinity. The resetting of these connections shall be at least one week after the earthwork is complete in order to allow any movement to occur.

MEASUREMENT AND PAYMENT

Payment will be made under:

Pay Item
Pier Adjustments

Pay Unit
Lump Sum



PROJECT: B-4088
COUNTY: Craven

PROJECT SPECIAL PROVISIONS

Utility

UTILITIES BY OTHERS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A. Tideland EMC - Power Distribution
- B. Embarq - Telephone

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

A) Tri-County - Power Distribution

- 1) See Utilities by Others Plans.

B) Embarq - Telephone

- 2) See Utilities by Others Plans.

NOTE: All other utilities shall remain in place and will be adjusted as necessary