

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0003	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0004	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	500 TON		
0006	0106000000-E	230	BORROW EXCAVATION	5,230 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	60 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	100 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	8 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0013	0345000000-E	310	24" SIDE DRAIN PIPE	48 LF		
0014	0995000000-E	340	PIPE REMOVAL	40 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	175 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	290 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	255 TON		
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	30 TON		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	425 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0031	3360000000-E	863	REMOVE EXISTING GUARDRAIL	487.5 LF		
0032	3628000000-E	876	RIP RAP, CLASS I	70 TON		
0033	3649000000-E	876	RIP RAP, CLASS B	170 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	610 SY		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	124 SF		
0036	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128 SF		
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0038	4430000000-N	1130	DRUMS	20 EA		
0039	4435000000-N	1135	CONES	20 EA		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0040	4445000000-E	1145	BARRICADES (TYPE III)	50 LF		
0041	4450000000-N	1150	FLAGGER	600 HR		
0042	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0043	4485000000-E	1170	PORTABLE CONCRETE BARRIER	70 LF		
0044	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,040 LF		
0045	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	50 LF		
0046	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0048	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	240 TON		
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
0050	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0053	6029000000-E	SP	SAFETY FENCE	300 LF		
0054	6030000000-E	1630	SILT EXCAVATION	520 CY		
0055	6036000000-E	1631	MATTING FOR EROSION CONTROL	425 SY		
0056	6069000000-E	1638	STILLING BASINS	170 CY		
0057	6071030000-E	SP	COIR FIBER BAFFLES	155 LF		
0058	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0059	6087000000-E	1660	MOWING	0.5 ACR		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0060	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0064	6111000000-E	SP	IMPERVIOUS DIKE	350 LF		
0065	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0066	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0067	7060000000-E	1705	SIGNAL CABLE	1,350 LF		
0068	7108000000-E	1705	VEHICLE SIGNAL HEAD (12", 1 SECTION)	2 EA		
0069	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	4 EA		
0070	7264000000-E	1710	MESSENGER CABLE (3/8")	285 LF		
0071	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,150 LF		
0072	7360000000-N	1720	WOOD POLE	4 EA		
0073	7372000000-N	1721	GUY ASSEMBLY	6 EA		
0074	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0075	7420000000-E	1722	2" RISER WITH WEATHERHEAD	3 EA		
0076	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	276 LF		
0077	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	395 LF		
0078	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0079	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0080	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	1 EA		
CULVERT ITEMS						
0081	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+75.00 -L-)	Lump Sum	L.S.	
0082	8126000000-N	414	CULVERT EXCAVATION, STA ***** (14+75.00 -L-)	Lump Sum	L.S.	
0083	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	168 TON		
0084	8196000000-E	420	CLASS A CONCRETE (CULVERT)	240 CY		
0085	8245000000-E	425	REINFORCING STEEL (CULVERT)	42,122 LB		
1132/Feb28/Q72951.25/D370767130000/E85			Total Amount Of Bid For Entire Project :			

Contract No: C201502

County: McDowell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General