

County : Edgcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 21.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	30 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
000E	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL, CLASS III	100 CY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20.3 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	88 LF		
001E	0995000000-E	340	PIPE REMOVAL	29 LF		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	300 TON		
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	411 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	13 TON		

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2000000000-N	806	RIGHT OF WAY MARKERS	17 EA		
001E	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
002C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	81 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	550 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003C	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0031	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0032	3649000000-E	876	RIP RAP, CLASS B	2 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	410 SY		
0034	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	18.75 SF		
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	40 LF		

County : Edgcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0037	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	11 EA		
0038	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	1 EA		
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	353 SF		
0040	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	76 SF		
0042	4430000000-N	1130	DRUMS	27 EA		
0043	4435000000-N	1135	CONES	20 EA		
0044	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0045	4450000000-N	1150	FLAGGER	80 HR		
0046	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,760 LF		
0047	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	26 EA		
0048	5326000000-E	1510	10" WATER LINE	501 LF		
0049	5871600000-E	1550	TRENCHLESS INSTALLATION OF 10" IN SOIL	394 LF		
0050	5871610000-E	1550	TRENCHLESS INSTALLATION OF 10" NOT IN SOIL	100 LF		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	1,125 LF		
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75 TON		

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	35 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
006C	6029000000-E	SP	SAFETY FENCE	250 LF		
0061	6030000000-E	1630	SILT EXCAVATION	315 CY		
0062	6036000000-E	1631	MATTING FOR EROSION CONTROL	175 SY		
006E	6037000000-E	SP	COIR FIBER MAT	20 SY		
0064	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
006E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150 SY		
006E	6071030000-E	SP	COIR FIBER BAFFLES	40 LF		
0067	6071050000-E	SP	*** SKIMMER (2")	3 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
006E	6087000000-E	1660	MOWING	0.5 ACR		
007C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
007E	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0077	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 21.50 -L-)	Lump Sum	L.S.	
007E	8112730000-N	SP	PDA TESTING	1 EA		
007E	8112740000-N	SP	PDA ASSISTANCE	1 EA		
008C	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	800 CY		
0081	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	47.2 CY		
0082	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 21.50 -L-)	Lump Sum	L.S.	
0083	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,810 LB		
0084	8364000000-E	450	HP12X53 STEEL PILES	720 LF		
008E	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	600 LF		
008E	8393000000-N	450	PILE REDRIVES	6 EA		
0087	8503000000-E	460	CONCRETE BARRIER RAIL	265 LF		
008E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	305 TON		
008E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	345 SY		
009C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,590 LF		

1121/Mar29/Q27281.1/D411563660000/E91

Total Amount Of Bid For Entire Project :

Contract No: C201547

County: Edgecombe

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General