

County : Edgemcombe, Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	2,100 CY		
000E	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20 + 32.50)	Lump Sum	L.S.	
000E	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (29 + 15.00)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	4,000 CY		
000E	0106000000-E	230	BORROW EXCAVATION	31,100 CY		
000E	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	4 EA		
001C	0134000000-E	240	DRAINAGE DITCH EXCAVATION	180 CY		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	7,550 SY		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	13,400 CY		
0013	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	3,000 SY		
0014	0199000000-E	SP	TEMPORARY SHORING	3,000 SF		
001E	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VI)	1,200 TON		
001E	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	62 TON		
0017	0344000000-E	310	18" SIDE DRAIN PIPE	140 LF		
001E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	72 LF		

County : Edgcombe, Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	64 LF		
0020	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	112 LF		
0021	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	190 LF		
0022	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0023	0980000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, INSTALLED BY BORING & JACKING (18", 0.500")	132 LF		
0024	0995000000-E	340	PIPE REMOVAL	156 LF		
0025	0996000000-N	350	PIPE CLEAN-OUT	3 EA		
0026	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0027	1121000000-E	520	AGGREGATE BASE COURSE	400 TON		
0028	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0029	1330000000-E	607	INCIDENTAL MILLING	350 SY		
0030	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,790 TON		
0031	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,990 TON		
0032	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,590 TON		
0033	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	171 TON		
0034	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	96 TON		
0035	2000000000-N	806	RIGHT OF WAY MARKERS	23 EA		

County : Edgecombe, Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0037	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
003E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
003E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
004C	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0041	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0042	2253000000-E	840	PIPE COLLARS	1.105 CY		
0043	2264000000-E	840	PIPE PLUGS	0.13 CY		
0044	2275000000-E	SP	FLOWABLE FILL	55 CY		
004E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
004E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1 LF		
0047	2354200000-N	840	FRAME WITH GRATE, STD 840.24	1 EA		
004E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	9 EA		
004E	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	1 EA		
005C	2556000000-E	846	SHOULDER BERM GUTTER	225 LF		
0051	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0052	3030000000-E	862	STEEL BM GUARDRAIL	2,150 LF		
0053	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0054	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		

County : Edgemcombe, Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0056	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0057	3360000000-E	863	REMOVE EXISTING GUARDRAIL	570 LF		
005E	3635000000-E	876	PLAIN RIP RAP, CLASS II	2,300 TON		
0059	3649000000-E	876	PLAIN RIP RAP, CLASS B	13 TON		
006C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,071 SY		
0061	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0062	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	151 LF		
0063	4082000000-E	903	SUPPORTS, WOOD	36 LF		
0064	4096000000-N	904	SIGN ERECTION, TYPE D	5 EA		
006E	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0066	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	1 EA		
0067	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	2 EA		
006E	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	1 EA		
0069	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	18 EA		
007C	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	4 EA		
0071	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0072	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	104 SF		

County : Edgecombe, Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	192 SF		
0074	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0075	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0076	4430000000-N	1130	DRUMS	129 EA		
0077	4435000000-N	1135	CONES	100 EA		
0078	4446100000-E	SP	BARRICADES (TYPE III)	48 LF		
0079	4450000000-N	1150	FLAGGER	160 HR		
0080	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0081	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	3 EA		
0082	4485000000-E	1170	PORTABLE CONCRETE BARRIER	246 LF		
0083	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	463 LF		
0084	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	1,606 LF		
0085	4615000000-E	1205	REMOVABLE TAPE PAVEMENT MARKING LINES (4")	1,852 LF		
0086	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	194 EA		
0087	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,474 LF		
0088	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	7,039 LF		
0089	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	76 LF		
0090	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	1 EA		

County : Edgecombe, Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,095 LF		
0092	4847000000-E	SP	POLYUREA PAVEMENT MARKING LINES (4")	1,852 LF		
0093	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	97 EA		
0094	6000000000-E	1605	TEMPORARY SILT FENCE	5,725 LF		
009E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
009E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	375 TON		
0097	6012000000-E	1610	SEDIMENT CONTROL STONE	465 TON		
009E	6015000000-E	1615	TEMPORARY MULCHING	8 ACR		
009E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300 LB		
010C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0101	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0102	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0103	6029000000-E	SP	SAFETY FENCE	4,000 LF		
0104	6030000000-E	1630	SILT EXCAVATION	1,870 CY		
010E	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,500 SY		
010E	6042000000-E	1632	1/4" HARDWARE CLOTH	220 LF		
0107	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
010E	6084000000-E	1660	SEEDING & MULCHING	9.5 ACR		

County : Edgecombe, Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	6087000000-E	1660	MOWING	5 ACR		
0110	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0111	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0112	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200 LB		
0113	6108000000-E	1665	FERTILIZER TOPDRESSING	7.25 TON		
0114	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0115	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		
STRUCTURE ITEMS						
0116	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20 + 32.50 -L-)	Lump Sum	L.S.	
0117	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20 + 32.50 -L-)	Lump Sum	L.S.	
0118	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (29 + 15.00 -L-)	Lump Sum	L.S.	
0119	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	83.97 LF		
0120	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	49.7 LF		
0121	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	87.65 LF		
0122	8113000000-N	SP	SID INSPECTION	2 EA		
0123	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		

County : Edgecombe, Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,630 CY		
0125	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	15,678 SF		
0126	8161000000-E	420	GROOVING BRIDGE FLOORS	16,822 SF		
0127	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	208.6 CY		
012E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20 + 32.50 -L-)	Lump Sum	L.S.	
012S	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (29 + 15.00 -L-)	Lump Sum	L.S.	
013C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	47,258 LB		
0131	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,400 LB		
0132	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	1,347.5 LF		
0133	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	197,900 LS		
0134	8364000000-E	450	HP12X53 STEEL PILES	1,210 LF		
013E	8384000000-E	450	HP14X73 STEEL PILES	630 LF		
0136	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (29 + 15.00 -L-)	Lump Sum	L.S.	
0137	8503000000-E	460	CONCRETE BARRIER RAIL	725 LF		
013E	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	928 TON		
013S	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,030 SY		
014C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Edgecombe, Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0141	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1129/Apr09/Q432804.905/D581904520000/E141

Total Amount Of Bid For Entire Project :

C201794 (B-3453)
COUNTIES: EDGECOMBE-HALIFAX

2/16/99

Contract No: C201794
Counties: Edgecombe-Halifax

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General