

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+25.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0007	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	56 LF		
0008	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	28 LF		
0009	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
001C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	610 TON		
0011	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	390 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	525 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	77 TON		
0014	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0015	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0016	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0017	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2556000000-E	846	SHOULDER BERM GUTTER	60 LF		
001E	3030000000-E	862	STEEL BM GUARDRAIL	625 LF		
002C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0021	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0022	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
002E	3566000000-E	867	WOVEN WIRE FENCE RESET	310 LF		
0024	3574000000-E	867	GENERIC FENCING ITEM 2-STRAND ELECTRIC FENCE RESET	50 LF		
002E	3649000000-E	876	RIP RAP, CLASS B	68 TON		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	927 SY		
0027	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
002E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	14.6 SF		
002E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	67 LF		
003C	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0031	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	7 EA		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	684 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	174 SF		
0034	4445000000-E	1145	BARRICADES (TYPE III)	128 LF		
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,900 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,900 LF		
0037	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (1)	800 LF		
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	15 EA		
0039	6000000000-E	1605	TEMPORARY SILT FENCE	430 LF		
004C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	175 TON		
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	325 TON		
0043	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	125 LF		
0047	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
004E	6029000000-E	SP	SAFETY FENCE	300 LF		
0049	6030000000-E	1630	SILT EXCAVATION	840 CY		
005C	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,600 SY		
0051	6037000000-E	SP	COIR FIBER MAT	30 SY		
0052	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	927 SY		
0053	6042000000-E	1632	1/4" HARDWARE CLOTH	375 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
005E	6071030000-E	SP	COIR FIBER BAFFLES	225 LF		
005E	6071050000-E	SP	*** SKIMMER (2")	4 EA		
0057	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
005E	6087000000-E	1660	MOWING	2 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0063	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		

**STRUCTURE ITEMS**

006E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (19 + 25.00 -L-)	Lump Sum	L.S.	
0067	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19 + 25.00 -L-)	Lump Sum	L.S.	
006E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	55.68 LF		
006E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	27 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	53.4 LF		
0071	8113000000-N	SP	SID INSPECTION	1 EA		
0072	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0073	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	650 CY		
0074	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	7,850 SF		
007E	8161000000-E	420	GROOVING BRIDGE FLOORS	7,482 SF		
007E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	90.3 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19 + 25.00 -L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	26,454 LB		
007E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,582 LB		
008C	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	786 LF		
0081	8364000000-E	450	HP12X53 STEEL PILES	350 LF		
0082	8503000000-E	460	CONCRETE BARRIER RAIL	396.67 LF		
0083	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	716 TON		
0084	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	794 SY		
008E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

**Contract No: C201637**

**County: Johnston**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General