


Project: U-3401
County: RANDOLPH

PROJECT SPECIAL PROVISIONS
Utility Construction



I. GENERAL CONSTRUCTION REQUIREMENTS:

Specifications:

REMOVE EXISTING GATE VALVE AND VALVE BOX:

Existing gate valve and valve box shall be permanently removed and stockpiled. Contractor shall contact the owner to pick up the existing valve and valve box.

The quantity of valves removed and accepted will be measured and paid for at the contract unit price each for "Remove Existing Valve and Valve Box". Such price and payment will be full compensation for all labor, excavation, removal of meter and box, stockpiling, backfilling, and incidentals necessary to complete the work as required.

04/05/2007

County: Randolph
Project: U-3401PROJECT SPECIAL PROVISIONS

Utility

UTILITIES BY OTHERS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) EMBARQ - TELEPHONE
- B) PIEDMONT-NATURAL GAS
- C) RANDOLPH EMC-POWER

The conflicting facilities of these concerns will be adjusted prior to the date of availability unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

A) Embarq

They will complete the pole removal and their proposed under ground fiber optic line by June 1st, 2007, except at the proposed culvert location. Contractor shall give Embarq three (3) weeks notice, before they start working on the box culvert at station 30+25 on the -Y- Line, in order for Embarq to suspend their line during the culvert's construction.

See Utilities by Others Plans for details.

B) Randolph EMC

They will remove all the light poles by July 31st, 2007 and new poles will not be set until the completion of the roadway project. The contractor shall give EMC three (3) weeks notice, before they start working on the retaining wall (Station 17+48 to Sta. 19+50) on the Y- Line, in order for Randolph EMC to place conduit in the footings. Once the retaining wall is complete, Randolph EMC will need 10 days to complete their work.

See Utilities By others plans for details.

C) Piedmont Natural Gas

Will adjust their facility under the proposed drainage as necessary and they require two weeks notice and one week to make the adjustment at each location.

Contractor shall give Piedmont Natural Gas three (3) weeks notice before they start working on the box culvert at station 30+25 on the -Y- line, in order for Piedmont Natural Gas to adjust their line during the culvert's construction.

See Utilities By others plans for details.