

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20 + 35.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	700 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	960 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	750 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	51 TON		
0011	0345000000-E	310	24" SIDE DRAIN PIPE	36 LF		
0012	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	160 LF		
0013	0973100000-E	330	*** WELDED STEEL PIPE IN SOIL (15")	64 LF		
0014	0995000000-E	340	PIPE REMOVAL	55 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	1,805 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,350 TON		
0018	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,105 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,305 TON		
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	110 TON		
0021	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	74 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	6 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
003C	2209000000-E	838	ENDWALLS	2 CY		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	5 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0034	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
003E	3030000000-E	862	STEEL BM GUARDRAIL	787.5 LF		
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
003E	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
004C	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	2 EA		
0041	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0042	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,048 LF		
0043	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	325 LF		
0044	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (CAT-1)	1 EA		
004E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (TYPE III)	4 EA		
004E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	5 EA		
0047	3628000000-E	876	RIP RAP, CLASS I	25 TON		
004E	3635000000-E	876	RIP RAP, CLASS II	900 TON		
004E	3649000000-E	876	RIP RAP, CLASS B	5 TON		
005C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,590 SY		
0051	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0052	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	13.3 SF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	26	SF	
0054	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	136	LF	
005E	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
005E	4102000000-N	904	SIGN ERECTION, TYPE E	4	EA	
0057	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	1	EA	
005E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6	EA	
005E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	1	EA	
006C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	260	SF	
0061	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128	SF	
0062	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	52	SF	
0063	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1	EA	
0064	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	1	EA	
006E	4430000000-N	1130	DRUMS	136	EA	
006E	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
0067	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1	EA	
006E	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	1	EA	
006E	4480000000-N	1165	TMIA	1	EA	
007C	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	83	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,710	LF	
0072	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	408	LF	
0073	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	1	EA	
0074	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (4)	385	LF	
0075	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	13,894	LF	
0076	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	60	LF	
0077	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,202	LF	
0078	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	17	EA	
0079	6000000000-E	1605	TEMPORARY SILT FENCE	1,950	LF	
008C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150	TON	
0081	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	230	TON	
0082	6012000000-E	1610	SEDIMENT CONTROL STONE	375	TON	
0083	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0084	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0085	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0086	6024000000-E	1622	TEMPORARY SLOPE DRAINS	150	LF	
0087	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	6029000000-E	SP	SAFETY FENCE	350 LF		
008E	6030000000-E	1630	SILT EXCAVATION	1,150 CY		
009C	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500 SY		
0091	6037000000-E	SP	COIR FIBER MAT	20 SY		
0092	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,015 SY		
009E	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
0094	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
009E	6071030000-E	SP	COIR FIBER BAFFLES	160 LF		
009E	6071050000-E	SP	*** SKIMMER (2-1/2")	2 EA		
0097	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
009E	6087000000-E	1660	MOWING	1 ACR		
009E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
010C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0101	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0102	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
010E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0104	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
010E	6123000000-E	1670	REFORESTATION	0.88 ACR		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
0106 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	284	LF	
*** OR ***						
0107 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	148	LF	
0108 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	136	LF	
*** OR ***						
0109 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	148	LF	
0110 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	136	LF	
***** END SCHEDULE AA *****						
<b>STRUCTURE ITEMS</b>						
0111	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (20+35.50-L-)	Lump Sum	L.S.	
0112	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20+35.50-L-)	Lump Sum	L.S.	
0113	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+35.50-L-)	Lump Sum	L.S.	
0114	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SOIL	135	LF	
0115	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	60	LF	
0116	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	90	LF	
0117	8113000000-N	SP	SID INSPECTION	6	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
011E	8114000000-N	SP	SPT TESTING	6 EA		
011E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
012C	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,310 CY		
0121	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	10,008 SF		
0122	8161000000-E	420	GROOVING BRIDGE FLOORS	10,317 SF		
0123	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	136.9 CY		
0124	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20 + 35.50-L-)	Lump Sum	L.S.	
0125	8217000000-E	425	REINFORCING STEEL (BRIDGE)	33,850 LB		
0126	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,062 LB		
0127	8259000000-E	430	36" PRESTRESSED CONCRETE GIRDERS	1,333.33 LF		
012E	8364000000-E	450	HP12X53 STEEL PILES	520 LF		
0129	8503000000-E	460	CONCRETE BARRIER RAIL	337.83 LF		
013C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	390 TON		
0131	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	435 SY		
0132	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0133	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0958/Mar30/Q108320.24/D574717300000/E133

Total Amount Of Bid For Entire Project :



**Contract No: C201546**

**County: Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General