

County : Currituck

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0001000000-E | 200 | CLEARING & GRUBBING .. ACRE(S) | Lump Sum | L.S. | |
| 0003 | 0008000000-E | 200 | SUPPLEMENTARY CLEARING & GRUBBING | 1 ACR | | |
| 0004 | 0022000000-E | 225 | UNCLASSIFIED EXCAVATION | 16,862 CY | | |
| 0005 | 0036000000-E | 225 | UNDERCUT EXCAVATION | 2,215 CY | | |
| 0006 | 0156000000-E | 250 | REMOVAL OF EXISTING ASPHALT PAVEMENT | 1,190 SY | | |
| 0007 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 3,625 CY | | |
| 0008 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 3,865 SY | | |
| 0009 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 812 TON | | |
| 001C | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 2,160 LF | | |
| 0011 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 552 LF | | |
| 0012 | 0378000000-E | 310 | 24" RC PIPE CULVERTS, CLASS III | 488 LF | | |
| 0013 | 0384000000-E | 310 | 30" RC PIPE CULVERTS, CLASS III | 160 LF | | |
| 0014 | 0396000000-E | 310 | 42" RC PIPE CULVERTS, CLASS III | 228 LF | | |
| 0015 | 0995000000-E | 340 | PIPE REMOVAL | 772 LF | | |
| 001E | 1011000000-N | 500 | FINE GRADING | Lump Sum | L.S. | |
| 0017 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 375 TON | | |
| 001E | 1245000000-E | SP | SHOULDER RECONSTRUCTION | 6.4 SMI | | |

County : Currituck

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0019 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 4,030 TON | | |
| 0020 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 1,340 TON | | |
| 0021 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 4,510 TON | | |
| 0022 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 510 TON | | |
| 0023 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 110 TON | | |
| 0024 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 3 EA | | |
| 0025 | 2364000000-N | 840 | FRAME WITH TWO GRATES, STD 840.16 | 1 EA | | |
| 0026 | 2612000000-E | 848 | 6" CONCRETE DRIVEWAY | 255 SY | | |
| 0027 | 4589000000-N | SP | GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL | Lump Sum | L.S. | |
| 0028 | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 33,816 LF | | |
| 0029 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 21,135 LF | | |
| 0030 | 4725000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) | 10 EA | | |
| 0031 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 54,951 LF | | |
| 0032 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 220 EA | | |
| 0033 | 5325600000-E | 1510 | 6" WATER LINE | 173 LF | | |
| 0034 | 5325800000-E | 1510 | 8" WATER LINE | 230 LF | | |
| 0035 | 5326000000-E | 1510 | 10" WATER LINE | 65 LF | | |

County : Currituck

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---------------------------------------|----------|-----------|--------|
| 0036 | 5326200000-E | 1510 | 12" WATER LINE | 16,468 | LF | |
| 0037 | 5540000000-E | 1515 | 6" VALVE | 3 | EA | |
| 003E | 5546000000-E | 1515 | 8" VALVE | 3 | EA | |
| 003E | 5552000000-E | 1515 | 10" VALVE | 1 | EA | |
| 004C | 5558000000-E | 1515 | 12" VALVE | 18 | EA | |
| 0041 | 5571800000-E | 1515 | 8" TAPPING VALVE | 4 | EA | |
| 0042 | 5648000000-N | 1515 | RELOCATE WATER METER | 15 | EA | |
| 0043 | 5649000000-N | 1515 | RECONNECT WATER METER | 50 | EA | |
| 0044 | 5666000000-E | 1515 | FIRE HYDRANT | 1 | EA | |
| 004E | 5672000000-N | 1515 | RELOCATE FIRE HYDRANT | 6 | EA | |
| 004E | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,440 | LF | |
| 0047 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 75 | TON | |
| 004E | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 505 | TON | |
| 004E | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 175 | TON | |
| 005C | 6015000000-E | 1615 | TEMPORARY MULCHING | 18.5 | ACR | |
| 0051 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 650 | LB | |
| 0052 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 2.75 | TON | |
| 0053 | 6030000000-E | 1630 | SILT EXCAVATION | 1,755 | CY | |
| 0054 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 3,000 | SY | |
| 005E | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 20 | LF | |

County : Currituck

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|-------------------------------|----------|-----------|--------|
| 0056 | 6070000000-N | SP | SPECIAL STILLING BASINS | 1 | | EA |
| 0057 | 6084000000-E | 1660 | SEEDING & MULCHING | 17.5 | | ACR |
| 0058 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 200 | | LB |
| 0059 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.5 | | TON |
| 0060 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 450 | | LB |
| 0061 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 13 | | TON |

0805/May11/Q179566.65/D21915150000/E61

Total Amount Of Bid For Entire Project :

2/16/99
Z-13

Contract No: C201078

County: Currituck

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)