

TEMPORARY PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM QUANTITY BREAKDOWN	TOTAL QUANTITY
TEMPORARY PAVEMENT MARKINGS			
PAINT(24") TEMPORARY PAVEMENT MARKING			
P4	WHITE STOPBAR (2X)	144 LF	
			TOTAL 144 LF
PAINT(4")			
PA	WHITE EDGELINE (2X)	31044 LF	
PD	2 FT. WHITE MINISKIP (2X)	99 LF	
PI	YELLOW DOUBLE CENTER (2X)	31892 LF	
			TOTAL 63035 LF
PAINT(8")			
PR	WHITE GORELINE (2X)	1354 LF	
PS	WHITE DIAGONAL (2X)	594 LF	
PV	YELLOW DIAGONAL (2X)	98 LF	
			TOTAL 2046 LF
PAINT MARKING SYMBOLS			
QA	LEFT TURN ARROW (2X)	10 EA	
QB	RIGHT TURN ARROW (2X)	2 EA	
QC	STRAIGHT ARROW (2X)	4 EA	
QE	COMBO.STRAIGHT/RIGHT (2X)	6 EA	
			TOTAL 22 EA
MARKERS			
TEMPORARY RAISED PAVEMENT MARKERS			
MH	YELLOW & YELLOW	29 EA	
MI	CRYSTAL & RED	30 EA	
			TOTAL 59 EA

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM QUANTITY BREAKDOWN	TOTAL QUANTITY
FINAL PAVEMENT MARKINGS			
POLYUREA (24") Highly Reflective Elements			
V2	WHITE STOPBAR	71 LF	
			TOTAL 71 LF
POLYUREA (4") Highly Reflective Elements			
VA	WHITE EDGELINE	14153 LF	
VC	10 FT. WHITE SKIP	94 LF	
VD	2 FT. WHITE MINISKIP	135 LF	
VE	WHITE SOLID LANE LINE	352 LF	
VI	YELLOW DOUBLE CENTER	16162 LF	
			TOTAL 30896 LF
POLYUREA (8") Highly Reflective Elements			
VP	WHITE GORELINE	1316 LF	
VQ	WHITE DIAGONAL	436 LF	
VT	YELLOW DIAGONAL	597 LF	
			TOTAL 2349 LF
POLYUREA PAVEMENT MARKING SYMBOL Highly Reflective Elements			
WA	LEFT TURN ARROW	11 EA	
WB	RIGHT TURN ARROW	4 EA	
WC	STRAIGHT ARROW	8 EA	
WE	COMBO STRAIGHT/RIGHT	5 EA	
			TOTAL 28 EA
MARKERS			
SNOWPLOWABLE RAISED PAVEMENT MARKERS			
ME	YELLOW & YELLOW	127 EA	
MF	CRYSTAL & RED	84 EA	
			TOTAL 211 EA

25-MAY-2007 10:06
 \\dot\adferoo\T01\p\proj\projects-b\0682\traffic\trafficcontrol\pmp\0682.pmp-pmp.lcgn
 rmgarratt AT WZTC2229

APPROVED: <i>Jessica D. Kuse</i> DATE: 5/29/07	PAVEMENT MARKING SCHEDULES	
	SCALE: NONE	
	DATE: 10/06	
	DWG. BY: RMG	
	DESIGN BY: RMG	
REVIEWED BY: JDK	REVISIONS	

