

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+27.50)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	110 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	17,700 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,700 CY		
0008	0199000000-E	SP	TEMPORARY SHORING	600 SF		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	80 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	36 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	72 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	76 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0015	0995000000-E	340	PIPE REMOVAL	68 LF		
0016	1077000000-E	SP	#57 STONE	75 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	980 TON		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	445 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	72 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	28 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	135 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	105 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	600 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	18 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	332 LF		
0031	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	255 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	700 LF		
0033	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (3)	750 LF		
0038	3635000000-E	876	RIP RAP, CLASS II	50 TON		
0039	3642000000-E	876	RIP RAP, CLASS A	30 TON		
0040	3649000000-E	876	RIP RAP, CLASS B	25 TON		
0041	3651000000-E	SP	BOULDERS	50 TON		
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,290 SY		
0043	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	559 SF		
0045	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128 SF		
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	138 SF		
0047	4430000000-N	1130	DRUMS	30 EA		
0048	4435000000-N	1135	CONES	30 EA		
0049	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0050	4450000000-N	1150	FLAGGER	64 HR		
0051	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	60 EA		
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,600 LF		
0053	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD BEADS)	4,800 LF		
0054	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	60 EA		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	5325800000-E	1510	8" WATER LINE	1,302		LF
0056	5648000000-N	1515	RELOCATE WATER METER	1		EA
0057	5649000000-N	1515	RECONNECT WATER METER	1		EA
0058	5672000000-N	1515	RELOCATE FIRE HYDRANT	1		EA
0059	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	175		LF
0060	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	175		LF
0061	6000000000-E	1605	TEMPORARY SILT FENCE	2,200		LF
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75		TON
0063	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	355		TON
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	485		TON
0065	6015000000-E	1615	TEMPORARY MULCHING	4.5		ACR
0066	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150		LB
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75		TON
0068	6024000000-E	1622	TEMPORARY SLOPE DRAINS	310		LF
0069	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3		EA
0070	6029000000-E	SP	SAFETY FENCE	1,750		LF
0071	6030000000-E	1630	SILT EXCAVATION	1,140		CY
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,200		SY
0073	6037000000-E	SP	COIR FIBER MAT	175		SY

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0075	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0076	6071030000-E	SP	COIR FIBER BAFFLES	160 LF		
0077	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0078	6084000000-E	1660	SEEDING & MULCHING	5.5 ACR		
0079	6087000000-E	1660	MOWING	2.5 ACR		
0080	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0081	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0082	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0083	6108000000-E	1665	FERTILIZER TOPDRESSING	4 TON		
0084	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0085	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0086	6123000000-E	1670	REFORESTATION	0.1 ACR		
0087	6126000000-E	SP	STREAMBANK REFORESTATION	0.4 ACR		
STRUCTURE ITEMS						
0088	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16+27.50-L)	Lump Sum	L.S.	
0089	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+27.50-L)	Lump Sum	L.S.	
0090	8096000000-E	SP	PILE EXCAVATION IN SOIL	10 LF		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	140 LF		
0092	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SOIL	58.6 LF		
0093	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	25 LF		
0094	8113000000-N	SP	SID INSPECTION	2 EA		
0095	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0096	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	6,071 SF		
0097	8161000000-E	420	GROOVING BRIDGE FLOORS	5,675 SF		
0098	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	152.8 CY		
0099	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+27.50-L-)	Lump Sum	L.S.	
0100	8217000000-E	425	REINFORCING STEEL (BRIDGE)	29,286 LB		
0101	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,157 LB		
0102	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	716.21 LF		
0103	8364000000-E	450	HP12X53 STEEL PILES	420 LF		
0104	8503000000-E	460	CONCRETE BARRIER RAIL	365.19 LF		
0105	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,222 TON		
0106	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,358 SY		
0107	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0108	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

Contract No: C201468

County: Caldwell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General