

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	600 CY		
0003	0170000000-E	SP	REMOVAL OF EXISTING CONCRETE PAVEMENT SLABS	484 SY		
0004	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,800 SY		
0005	0255000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS IV	1,200 TON		
0006	0264000000-E	SP	GENERIC GRADING ITEM SHOULDER GRADING	5 SMI		
0007	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	500,000 LB		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	177,900 SY		
0009	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (9-1/2")	1,400 SY		
0010	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	320 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	24,940 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	14,780 TON		
0013	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	1,340 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,190 TON		
0015	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	970 TON		
0016	1567000000-E	SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28	970 TON		
0017	1839110000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE B	18,590 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	531,050	SY	
0019	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	285,000	LF	
0020	1847000000-E	710	***** PORT CEM CONC PAVEMENT, THROUGH LANES (WITH DOWELS) (9-1/2")	484	SY	
0021	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	632	SF	
0022	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	2,088	SF	
0023	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	16	SF	
0024	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	12	EA	
0025	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	16	EA	
0026	4430000000-N	1130	DRUMS	2,200	EA	
0027	4445000000-E	1145	BARRICADES (TYPE III)	16	LF	
0028	4480000000-N	1165	TMIA	8	EA	
0029	4510000000-N	SP	POLICE	2,000	HR	
0030	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,832	LF	
0031	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (IV)	3,369	LF	
0032	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	291,456	LF	
0033	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	26,400	LF	
0034	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	15	EA	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	291,456 LF		
0036	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)	26,400 LF		
0037	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (HIGHLY REFLECTIVE ELEMENTS)	15 EA		
0038	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	254,960 LF		
0039	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	4,800 LF		
0040	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	5,333 EA		
0041	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0923/Jun14/Q2476049.0/D120986850000/E41			Total Amount Of Bid For Entire Project :			

**Contract No: C201798**

**County: Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General