

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,160 CY		
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (31+51.06)	Lump Sum	L.S.	
0006	0036000000-E	225	UNDERCUT EXCAVATION	5,500 CY		
0007	0106000000-E	230	BORROW EXCAVATION	7,250 CY		
0008	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	4 EA		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,350 SY		
0010	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	780 SY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	700 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	4,900 SY		
0013	0255000000-E	SP	GENERIC GRADING ITEM LIGHT WEIGHT AGGREGATE	3,850 TON		
0014	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	220 TON		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	808 LF		
0016	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	112 LF		
0017	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	72 LF		
0018	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	68 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0995000000-E	340	PIPE REMOVAL	192 LF		
0020	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0021	1121000000-E	520	AGGREGATE BASE COURSE	1,190 TON		
0022	1220000000-E	545	INCIDENTAL STONE BASE	10 TON		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	710 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	700 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	720 TON		
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	110 TON		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0028	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0029	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0030	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0031	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0032	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0034	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	7 EA		
0035	2556000000-E	846	SHOULDER BERM GUTTER	280 LF		
0036	2612000000-E	848	6" CONCRETE DRIVEWAY	35 SY		
0037	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	675 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3030000000-E	862	STEEL BM GUARDRAIL	425 LF		
0039	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0040	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0041	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
0042	3435000000-N	SP	GENERIC GUARDRAIL ITEM IMPACT ATTENUATOR UNIT, TYPE TL-2	2 EA		
0043	3649000000-E	876	RIP RAP, CLASS B	45 TON		
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	212 SY		
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	300 SF		
0046	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	100 SF		
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	60 SF		
0048	4430000000-N	1130	DRUMS	20 EA		
0049	4435000000-N	1135	CONES	20 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	100 LF		
0051	4455000000-N	1150	FLAGGER	20 MD		
0052	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,400 LF		
0053	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,400 LF		
0054	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (3)	1,220 LF		
0055	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	40 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	5325200000-E	1510	2" WATER LINE	18 LF		
0057	5326200000-E	1510	12" WATER LINE	1,059 LF		
0058	5326600000-E	1510	16" WATER LINE	1,417 LF		
0059	5558000000-E	1515	12" VALVE	2 EA		
0060	5648000000-N	1515	RELOCATE WATER METER	2 EA		
0061	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0062	5801000000-E	1530	ABANDON 8" UTILITY PIPE	500 LF		
0063	5871900000-E	1550	TRENCHLESS INSTALLATION OF 16" IN SOIL	319 LF		
0064	5871910000-E	1550	TRENCHLESS INSTALLATION OF 16" NOT IN SOIL	100 LF		
0065	6000000000-E	1605	TEMPORARY SILT FENCE	3,300 LF		
0066	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0067	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	165 TON		
0068	6012000000-E	1610	SEDIMENT CONTROL STONE	150 TON		
0069	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0070	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0071	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0072	6024000000-E	1622	TEMPORARY SLOPE DRAINS	75 LF		
0073	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0074	6029000000-E	SP	SAFETY FENCE	300 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6030000000-E	1630	SILT EXCAVATION	375 CY		
0076	6036000000-E	1631	MATTING FOR EROSION CONTROL	600 SY		
0077	6037000000-E	SP	COIR FIBER MAT	10 SY		
0078	6042000000-E	1632	1/4" HARDWARE CLOTH	550 LF		
0079	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	115 SY		
0080	6071030000-E	SP	COIR FIBER BAFFLES	50 LF		
0081	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0082	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0083	6087000000-E	1660	MOWING	1.5 ACR		
0084	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0085	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0086	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0087	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0088	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0089	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
WALL ITEMS						
0090	8847000000-E	SP	GENERIC RETAINING WALL ITEM TIEBACK STEEL SHEET PILE RETAINING WALLS	26,868 SF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0091	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (30+00.00-L-)	Lump Sum	L.S.	
0092	8112730000-N	SP	PDA TESTING	1 EA		
0093	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0094	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (30+00.00-L-)	Lump Sum	L.S.	
0095	8156000000-E	SP	CONCRETE WEARING SURFACE	9,727 SF		
0096	8161000000-E	420	GROOVING BRIDGE FLOORS	10,199 SF		
0097	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	73.1 CY		
0098	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (30+00.00-L-)	Lump Sum	L.S.	
0099	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	15,791 LB		
0100	8364000000-E	450	HP12X53 STEEL PILES	1,085 LF		
0101	8386000000-E	450	PP 18 X 0.50 STEEL PILES	1,680 LF		
0102	8392000000-N	450	PIPE PILE PLATES	28 EA		
0103	8393000000-N	450	PILE REDRIVES	23 EA		
0104	8503000000-E	460	CONCRETE BARRIER RAIL	599.8 LF		
0105	8590000000-E	876	RIP RAP, CLASS ** (I)	203 TON		
0106	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	225 SY		
0107	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0108	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	3,592.5 LF		

1549/Jul10/Q124444.85/D481070460000/E109

Total Amount Of Bid For Entire Project :

Contract No: C201641

County: Currituck

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General