

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	16,862 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	2,215 CY		
0006	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,190 SY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	3,625 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	3,865 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	812 TON		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,160 LF		
0011	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	552 LF		
0012	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	488 LF		
0013	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	160 LF		
0014	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	228 LF		
0015	0995000000-E	340	PIPE REMOVAL	772 LF		
0016	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0017	1220000000-E	545	INCIDENTAL STONE BASE	375 TON		
0018	1245000000-E	SP	SHOULDER RECONSTRUCTION	6.4 SMI		
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,030 TON		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,340 TON		
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,510 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	510 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	110 TON		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0025	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0026	2612000000-E	848	6" CONCRETE DRIVEWAY	255 SY		
0027	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	935 SY		
0028	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0029	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	33,816 LF		
0030	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	21,135 LF		
0031	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	10 EA		
0032	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	54,951 LF		
0033	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	220 EA		
0034	5325600000-E	1510	6" WATER LINE	173 LF		
0035	5325800000-E	1510	8" WATER LINE	230 LF		
0036	5326000000-E	1510	10" WATER LINE	65 LF		
0037	5326200000-E	1510	12" WATER LINE	16,468 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	5540000000-E	1515	6" VALVE	3 EA		
0039	5546000000-E	1515	8" VALVE	3 EA		
0040	5552000000-E	1515	10" VALVE	1 EA		
0041	5558000000-E	1515	12" VALVE	18 EA		
0042	5571800000-E	1515	8" TAPPING VALVE	4 EA		
0043	5648000000-N	1515	RELOCATE WATER METER	15 EA		
0044	5649000000-N	1515	RECONNECT WATER METER	50 EA		
0045	5666000000-E	1515	FIRE HYDRANT	1 EA		
0046	5672000000-N	1515	RELOCATE FIRE HYDRANT	6 EA		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	1,440 LF		
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	275 TON		
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	505 TON		
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	220 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	18.5 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	650 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.75 TON		
0054	6029000000-E	SP	SAFETY FENCE	1,700 LF		
0055	6030000000-E	1630	SILT EXCAVATION	1,755 CY		
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,000 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6070000000-N	SP	SPECIAL STILLING BASINS	3 EA		
0059	6071030000-E	SP	COIR FIBER BAFFLES	2,300 LF		
0060	6084000000-E	1660	SEEDING & MULCHING	17.5 ACR		
0061	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0062	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0063	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	450 LB		
0064	6108000000-E	1665	FERTILIZER TOPDRESSING	13 TON		
0065	6114000000-N	SP	SPECIALIZED HAND MOWING	10 HR		
0066	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15 EA		
0938/Jul13/Q184773.65/D247138530000/E66			Total Amount Of Bid For Entire Project :			

2/16/99
Z-13

Contract No: C201078

County: Currituck

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)