

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	92,500 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	4,335 CY		
0008	0141000000-E	240	BERM DITCH CONSTRUCTION	210 LF		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,000 SY		
0010	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	500 SY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	170 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	220 LF		
0015	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	176 LF		
0016	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	240 LF		
0017	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	188 LF		
0018	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	164 LF		
0019	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	8 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0974000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, (UNDER RR) (48", 0.625")	80 LF		
0021	0995000000-E	340	PIPE REMOVAL	244 LF		
0022	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0023	1110000000-E	510	STABILIZER AGGREGATE	200 TON		
0024	1121000000-E	520	AGGREGATE BASE COURSE	7,100 TON		
0025	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0026	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,400 TON		
0027	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,300 TON		
0028	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,400 TON		
0029	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	600 TON		
0030	2000000000-N	806	RIGHT OF WAY MARKERS	20 EA		
0031	2209000000-E	838	ENDWALLS	13 CY		
0032	2220000000-E	838	REINFORCED ENDWALLS	5.1 CY		
0033	2264000000-E	840	PIPE PLUGS	0.25 CY		
0034	2275000000-E	SP	FLOWABLE FILL	6 CY		
0035	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	16 EA		
0036	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3.5 LF		
0037	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	3 EA		
0038	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0040	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
0041	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0042	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	3,360 LF		
0043	2556000000-E	846	SHOULDER BERM GUTTER	740 LF		
0044	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	320 LF		
0045	2619000000-E	850	4" CONCRETE PAVED DITCH	11 SY		
0046	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	250 SY		
0047	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	245 LF		
0048	3030000000-E	862	STEEL BM GUARDRAIL	950 LF		
0049	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	150 LF		
0050	3090000000-N	862	TRIPLE CORRUGATED GUARDRAIL TERMINAL SECTIONS	8 EA		
0051	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0052	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0053	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0054	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77 (B-77)	1 EA		
0055	3628000000-E	876	RIP RAP, CLASS I	415 TON		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	3635000000-E	876	RIP RAP, CLASS II	400	TON	
0057	3649000000-E	876	RIP RAP, CLASS B	1,971	TON	
0058	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	7,075	SY	
0059	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	218.9	SF	
0060	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	16.6	SF	
0061	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	617	LF	
0062	4102000000-N	904	SIGN ERECTION, TYPE E	32	EA	
0063	4108000000-N	904	SIGN ERECTION, TYPE F	4	EA	
0064	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	5	EA	
0065	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	4	EA	
0066	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	595	SF	
0067	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	234	SF	
0068	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119	SF	
0069	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0070	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
0071	4430000000-N	1130	DRUMS	58	EA	
0072	4435000000-N	1135	CONES	100	EA	
0073	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0074	4480000000-N	1165	TMIA	1	EA	

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	33 EA		
0076	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	10,148 LF		
0077	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	6,761 LF		
0078	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	197 LF		
0079	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	180 LF		
0080	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	668 LF		
0081	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	16 EA		
0082	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	73 EA		
0083	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	500 LF		
0084	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	115 LF		
0085	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	3 EA		
0086	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	772 LF		
0087	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	5 EA		
0088	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	323 EA		
0089	4915000000-E	1264	7' U-CHANNEL POSTS	12 EA		
0090	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	12 EA		
0091	6000000000-E	1605	TEMPORARY SILT FENCE	1,855 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0093	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	235 TON		
0094	6012000000-E	1610	SEDIMENT CONTROL STONE	290 TON		
0095	6015000000-E	1615	TEMPORARY MULCHING	18.5 ACR		
0096	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	700 LB		
0097	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.75 TON		
0098	6030000000-E	1630	SILT EXCAVATION	470 CY		
0099	6033000000-E	1631	SYNTHETIC ROVING	310 SY		
0100	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,518 SY		
0101	6042000000-E	1632	1/4" HARDWARE CLOTH	260 LF		
0102	6071030000-E	SP	COIR FIBER BAFFLES	165 LF		
0103	6084000000-E	1660	SEEDING & MULCHING	18 ACR		
0104	6087000000-E	1660	MOWING	11 ACR		
0105	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0106	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0107	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	450 LB		
0108	6108000000-E	1665	FERTILIZER TOPDRESSING	13.25 TON		
0109	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0110	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0111	7060000000-E	1705	SIGNAL CABLE	2,310 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0112	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	17 EA		
0113	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0114	7288000000-E	1715	PAVED TRENCHING (*****) (2, 2")	690 LF		
0115	7300000000-E	1715	UNPAVED TRENCHING (*****) (2, 2")	2,270 LF		
0116	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2") 215' (1 conduit, 3 inch) 125' 1 ct, 4in)	740 LF		
0117	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	18 EA		
0118	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	3 EA		
0119	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,510 LF		
0120	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2) 460' (18-4 pair)	4,220 LF		
0121	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	7 EA		
0122	7613000000-N	SP	SOIL TEST	7 EA		
0123	7614100000-E	SP	DRILLED PIER FOUNDATION	56 CY		
0124	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	7 EA		
0125	7636000000-N	1745	SIGN FOR SIGNALS	1 EA		
0126	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0127	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
0128	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	13 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0129	7901000000-N	1753	CABINET BASE EXTENDER	2	EA	
0130	8802010000-E	SP	SOIL NAIL RETAINING WALLS	1,280	SF	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0131	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	596	LF	
AA1						
*** OR ***						
0132	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	460	LF	
AA2						
0133	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	136	LF	
AA2						
*** OR ***						
0134	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	460	LF	
AA3						
0135	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	136	LF	
AA3						
***** END SCHEDULE AA *****						
0136	1231000000-E	560	SHOULDER BORROW	1,500	CY	
1009/Aug16/Q189448.55/D517120240000/E135			Total Amount Of Bid For Entire Project :			

Contract No: C201642

County: Durham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General