

County : Johnston

| Line #               | Item Number  | Sec # | Description   | Quantity     | Unit Cost | Amount |
|----------------------|--------------|-------|---|--------------|-----------|--------|
| <b>ROADWAY ITEMS</b> |              |       |   |              |           |        |
| 0001                 | 0000100000-N | 800   | MOBILIZATION  | Lump Sum     | L.S.      |        |
| 0002                 | 0001000000-E | 200   | CLEARING & GRUBBING .. ACRE(S)  | Lump Sum     | L.S.      |        |
| 0003                 | 0008000000-E | 200   | SUPPLEMENTARY CLEARING & GRUB-<br>BING  | 1<br>ACR     |           |        |
| 0004                 | 0022000000-E | 225   | UNCLASSIFIED EXCAVATION   | 1,800<br>CY  |           |        |
| 0005                 | 0036000000-E | 225   | UNDERCUT EXCAVATION   | 1,300<br>CY  |           |        |
| 0006                 | 0080000000-E | SP    | CLASS IV SUBGRADE STABILIZA-<br>TION  | 2,400<br>TON |           |        |
| 0007                 | 0106000000-E | 230   | BORROW EXCAVATION   | 2,800<br>CY  |           |        |
| 0008                 | 0134000000-E | 240   | DRAINAGE DITCH EXCAVATION   | 1,200<br>CY  |           |        |
| 0009                 | 0156000000-E | 250   | REMOVAL OF EXISTING ASPHALT<br>PAVEMENT   | 1,400<br>SY  |           |        |
| 0010                 | 0196000000-E | 270   | FABRIC FOR SOIL STABILIZATION   | 3,600<br>SY  |           |        |
| 0011                 | 0318000000-E | 300   | FOUNDATION CONDITIONING MATE-<br>RIAL, MINOR STRS   | 420<br>TON   |           |        |
| 0012                 | 0396000000-E | 310   | 42" RC PIPE CULVERTS, CLASS<br>III  | 828<br>LF    |           |        |
| 0013                 | 0402000000-E | 310   | 48" RC PIPE CULVERTS, CLASS<br>III  | 248<br>LF    |           |        |
| 0014                 | 0408000000-E | 310   | 54" RC PIPE CULVERTS, CLASS<br>III  | 164<br>LF    |           |        |
| 0015                 | 0648000000-E | SP    | *** SADDLE BRANCH CONNECTOR<br>(18")  | 1<br>EA      |           |        |
| 0016                 | 0714000000-E | 310   | 18" BIT COAT CS PIPE CULVERTS,<br>TYPE B 0.064" THICK                                       | 4<br>LF      |           |        |
| 0017                 | 0908000000-E | 310   | **** X **** BIT COAT CS PIPE<br>ARCH CULVERTS, TYPE B *****<br>THICK<br>(95" X 67", 0.109") | 112<br>LF    |           |        |

County : Johnston

| Line # | Item Number  | Sec # | Description  | Quantity     | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 001E   | 0995000000-E | 340   | PIPE REMOVAL   | 704<br>LF    |           |        |
| 001E   | 1011000000-N | 500   | FINE GRADING   | Lump Sum     | L.S.      |        |
| 002C   | 1220000000-E | 545   | INCIDENTAL STONE BASE  | 100<br>TON   |           |        |
| 0021   | 1308000000-E | 607   | MILLING ASPHALT PAVEMENT, ****<br>TO ***** DEPTH<br>(1" TO 4") | 1,100<br>SY  |           |        |
| 0022   | 1489000000-E | 610   | ASPHALT CONC BASE COURSE, TYPE<br>B25.0B                       | 1,800<br>TON |           |        |
| 0023   | 1498000000-E | 610   | ASPHALT CONC INTERMEDIATE<br>COURSE, TYPE I19.0B               | 1,600<br>TON |           |        |
| 0024   | 1519000000-E | 610   | ASPHALT CONC SURFACE COURSE,<br>TYPE S9.5B                     | 1,900<br>TON |           |        |
| 0025   | 1560000000-E | 620   | ASPHALT BINDER FOR PLANT MIX,<br>GRADE PG 64-22                | 270<br>TON   |           |        |
| 0026   | 1693000000-E | 654   | ASPHALT PLANT MIX, PAVEMENT<br>REPAIR                          | 250<br>TON   |           |        |
| 0027   | 2209000000-E | 838   | ENDWALLS   | 4.5<br>CY    |           |        |
| 002E   | 2220000000-E | 838   | REINFORCED ENDWALLS  | 17.4<br>CY   |           |        |
| 0029   | 2253000000-E | 840   | PIPE COLLARS   | 1<br>CY      |           |        |
| 003C   | 2264000000-E | 840   | PIPE PLUGS   | 1<br>CY      |           |        |
| 0031   | 2286000000-N | 840   | MASONRY DRAINAGE STRUCTURES                                    | 52<br>EA     |           |        |
| 0032   | 2297000000-E | 840   | MASONRY DRAINAGE STRUCTURES                                    | 25.2<br>CY   |           |        |
| 0033   | 2308000000-E | 840   | MASONRY DRAINAGE STRUCTURES                                    | 20<br>LF     |           |        |
| 0034   | 2364000000-N | 840   | FRAME WITH TWO GRATES, STD<br>840.16                           | 6<br>EA      |           |        |
| 003E   | 2366000000-N | 840   | FRAME WITH TWO GRATES, STD<br>840.24                           | 5<br>EA      |           |        |

County : Johnston

| Line # | Item Number  | Sec # | Description  | Quantity    | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 003E   | 2374000000-N | 840   | FRAME WITH GRATE & HOOD, STD<br>840.03, TYPE **<br>(E)             | 4<br>EA     |           |        |
| 0037   | 2374000000-N | 840   | FRAME WITH GRATE & HOOD, STD<br>840.03, TYPE **<br>(F)             | 14<br>EA    |           |        |
| 003E   | 2374000000-N | 840   | FRAME WITH GRATE & HOOD, STD<br>840.03, TYPE **<br>(G)             | 8<br>EA     |           |        |
| 003E   | 2396000000-N | 840   | FRAME WITH COVER, STD 840.54                                       | 9<br>EA     |           |        |
| 004C   | 2407000000-N | 840   | STEEL FRAME WITH TWO GRATES,<br>STD 840.37                         | 7<br>EA     |           |        |
| 0041   | 2474000000-N | SP    | GENERIC DRAINAGE ITEM<br>WET DETENTION POND                        | Lump Sum    | L.S.      |        |
| 0042   | 2549000000-E | 846   | 2'-6" CONCRETE CURB & GUTTER                                       | 3,300<br>LF |           |        |
| 0043   | 2591000000-E | 848   | 4" CONCRETE SIDEWALK   | 1,000<br>SY |           |        |
| 0044   | 2605000000-N | 848   | CONCRETE WHEELCHAIR RAMPS  | 7<br>EA     |           |        |
| 004E   | 2612000000-E | 848   | 6" CONCRETE DRIVEWAY   | 250<br>SY   |           |        |
| 004E   | 2830000000-N | 858   | ADJUSTMENT OF MANHOLES   | 9<br>EA     |           |        |
| 0047   | 2845000000-N | 858   | ADJUSTMENT OF METER BOXES OR<br>VALVE BOXES                        | 22<br>EA    |           |        |
| 004E   | 3536000000-E | 866   | CHAIN LINK FENCE, 48" FABRIC                                       | 500<br>LF   |           |        |
| 004E   | 3542000000-E | 866   | METAL LINE POSTS FOR 48" CHAIN<br>LINK FENCE                       | 44<br>EA    |           |        |
| 005C   | 3548000000-E | 866   | METAL TERMINAL POSTS FOR 48"<br>CHAIN LINK FENCE                   | 4<br>EA     |           |        |
| 0051   | 3551000000-E | 866   | METAL GATE POSTS FOR *** CHAIN<br>LINK FENCE, SINGLE GATE<br>(48") | 2<br>EA     |           |        |

County : Johnston

| Line # | Item Number  | Sec # | Description   | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------|-----------|--------|
| 0052   | 3564000000-E | 866   | SINGLE GATES, *** HIGH, ***<br>WIDE, *** OPENING<br>(48", 10', 10') | 1        | EA        |        |
| 0053   | 3649000000-E | 876   | RIP RAP, CLASS B  | 40       | TON       |        |
| 0054   | 3656000000-E | 876   | FILTER FABRIC FOR DRAINAGE  | 565      | SY        |        |
| 005E   | 4025000000-E | 901   | CONTRACTOR FURNISHED, TYPE ***<br>SIGN<br>(E)                       | 42.5     | SF        |        |
| 005E   | 4025000000-E | 901   | CONTRACTOR FURNISHED, TYPE ***<br>SIGN<br>(F)                       | 34.75    | SF        |        |
| 0057   | 4072000000-E | 903   | SUPPORTS, 3-LB STEEL U-CHANNEL                                      | 201      | LF        |        |
| 005E   | 4102000000-N | 904   | SIGN ERECTION, TYPE E   | 8        | EA        |        |
| 005E   | 4108000000-N | 904   | SIGN ERECTION, TYPE F   | 2        | EA        |        |
| 006C   | 4116100000-N | 904   | SIGN ERECTION, RELOCATE, TYPE<br>**** (GROUND MOUNTED)<br>(E)       | 1        | EA        |        |
| 0061   | 4116100000-N | 904   | SIGN ERECTION, RELOCATE, TYPE<br>**** (GROUND MOUNTED)<br>(F)       | 1        | EA        |        |
| 0062   | 4155000000-N | 907   | DISPOSAL OF SIGN SYSTEM, U-<br>CHANNEL                              | 10       | EA        |        |
| 0063   | 4158000000-N | 907   | DISPOSAL OF SIGN SYSTEM, WOOD                                       | 2        | EA        |        |
| 0064   | 4192000000-N | 907   | DISPOSAL OF SUPPORT, U-CHANNEL                                      | 2        | EA        |        |
| 006E   | 4400000000-E | 1110  | WORK ZONE SIGNS (STATIONARY)  | 622      | SF        |        |
| 006E   | 4405000000-E | 1110  | WORK ZONE SIGNS (PORTABLE)  | 96       | SF        |        |
| 0067   | 4410000000-E | 1110  | WORK ZONE SIGNS (BARRICADE<br>MOUNTED)                              | 248      | SF        |        |
| 006E   | 4430000000-N | 1130  | DRUMS   | 58       | EA        |        |

County : Johnston

| Line # | Item Number  | Sec # | Description  | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0069   | 4445000000-E | 1145  | BARRICADES (TYPE III)                                | 136      | LF        |        |
| 007C   | 4455000000-N | 1150  | FLAGGER  | 90       | MD        |        |
| 0071   | 4650000000-N | 1251  | TEMPORARY RAISED PAVEMENT MARKERS                    | 85       | EA        |        |
| 0072   | 4685000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)   | 215      | LF        |        |
| 0073   | 4686000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)  | 4,923    | LF        |        |
| 0074   | 4710000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 84       | LF        |        |
| 007E   | 4725000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)      | 23       | EA        |        |
| 0076   | 4810000000-E | 1205  | PAINT PAVEMENT MARKING LINES (4")                    | 11,772   | LF        |        |
| 0077   | 4835000000-E | 1205  | PAINT PAVEMENT MARKING LINES (24")                   | 195      | LF        |        |
| 007E   | 4845000000-N | 1205  | PAINT PAVEMENT MARKING SYMBOL                        | 4        | EA        |        |
| 0079   | 4850000000-E | 1205  | REMOVAL OF PAVEMENT MARKING LINES (4")               | 5,409    | LF        |        |
| 008C   | 4900000000-N | 1251  | PERMANENT RAISED PAVEMENT MARKERS                    | 174      | EA        |        |
| 0081   | 5325200000-E | 1510  | 2" WATER LINE  | 22       | LF        |        |
| 0082   | 5325300000-E | 1510  | 3" WATER LINE  | 168      | LF        |        |
| 0083   | 5325600000-E | 1510  | 6" WATER LINE  | 568      | LF        |        |
| 0084   | 5325800000-E | 1510  | 8" WATER LINE  | 20       | LF        |        |
| 008E   | 5534000000-E | 1515  | *** VALVE (3")                                       | 1        | EA        |        |
| 008E   | 5540000000-E | 1515  | 6" VALVE   | 2        | EA        |        |

County : Johnston

| Line # | Item Number  | Sec # | Description                                   | Quantity     | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0087   | 5571600000-E | 1515  | 6" TAPPING VALVE                              | 1<br>EA      |           |        |
| 008E   | 5648000000-N | 1515  | RELOCATE WATER METER                          | 12<br>EA     |           |        |
| 008E   | 5666000000-E | 1515  | FIRE HYDRANT                                  | 1<br>EA      |           |        |
| 009C   | 5672000000-N | 1515  | RELOCATE FIRE HYDRANT                         | 1<br>EA      |           |        |
| 0091   | 5691300000-E | 1520  | 8" SANITARY GRAVITY SEWER                     | 504<br>LF    |           |        |
| 0092   | 5709300000-E | 1520  | 6" FORCE MAIN SEWER                           | 140<br>LF    |           |        |
| 009E   | 5775000000-E | 1525  | 4' DIA UTILITY MANHOLE                        | 6<br>EA      |           |        |
| 0094   | 5781000000-E | 1525  | UTILITY MANHOLE WALL, 4' DIA                  | 10<br>LF     |           |        |
| 009E   | 5801000000-E | 1530  | ABANDON 8" UTILITY PIPE                       | 433<br>LF    |           |        |
| 009E   | 6000000000-E | 1605  | TEMPORARY SILT FENCE                          | 2,060<br>LF  |           |        |
| 0097   | 6006000000-E | 1610  | STONE FOR EROSION CONTROL,<br>CLASS A         | 1,295<br>TON |           |        |
| 009E   | 6009000000-E | 1610  | STONE FOR EROSION CONTROL,<br>CLASS B         | 715<br>TON   |           |        |
| 009E   | 6012000000-E | 1610  | SEDIMENT CONTROL STONE                        | 1,390<br>TON |           |        |
| 010C   | 6015000000-E | 1615  | TEMPORARY MULCHING                            | 4<br>ACR     |           |        |
| 0101   | 6018000000-E | 1620  | SEED FOR TEMPORARY SEEDING                    | 150<br>LB    |           |        |
| 0102   | 6021000000-E | 1620  | FERTILIZER FOR TEMPORARY SEED-<br>ING         | 0.75<br>TON  |           |        |
| 010E   | 6024000000-E | 1622  | TEMPORARY SLOPE DRAINS                        | 50<br>LF     |           |        |
| 0104   | 6027000000-N | 1622  | INLET PROTECTION AT TEMPORARY<br>SLOPE DRAINS | 2<br>EA      |           |        |
| 010E   | 6029000000-E | SP    | SAFETY FENCE                                  | 250<br>LF    |           |        |

County : Johnston

| Line # | Item Number  | Sec # | Description                             | Quantity    | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 010E   | 6030000000-E | 1630  | SILT EXCAVATION                         | 3,515<br>CY |           |        |
| 0107   | 6036000000-E | 1631  | MATTING FOR EROSION CONTROL             | 1,110<br>SY |           |        |
| 010E   | 6037000000-E | SP    | COIR FIBER MAT                          | 20<br>SY    |           |        |
| 010E   | 6070000000-N | SP    | SPECIAL STILLING BASINS                 | 4<br>EA     |           |        |
| 011C   | 6071030000-E | SP    | COIR FIBER BAFFLES                      | 465<br>LF   |           |        |
| 0111   | 6071050000-E | SP    | *** SKIMMER<br>(1-1/2")                 | 2<br>EA     |           |        |
| 0112   | 6071050000-E | SP    | *** SKIMMER<br>(2")                     | 1<br>EA     |           |        |
| 011E   | 6084000000-E | 1660  | SEEDING & MULCHING                      | 4.5<br>ACR  |           |        |
| 0114   | 6087000000-E | 1660  | MOWING                                  | 2.5<br>ACR  |           |        |
| 011E   | 6090000000-E | 1661  | SEED FOR REPAIR SEEDING                 | 50<br>LB    |           |        |
| 011E   | 6093000000-E | 1661  | FERTILIZER FOR REPAIR SEEDING           | 0.25<br>TON |           |        |
| 0117   | 6096000000-E | 1662  | SEED FOR SUPPLEMENTAL SEEDING           | 100<br>LB   |           |        |
| 011E   | 6108000000-E | 1665  | FERTILIZER TOPDRESSING                  | 3.25<br>TON |           |        |
| 011E   | 6111000000-E | SP    | IMPERVIOUS DIKE                         | 350<br>LF   |           |        |
| 012C   | 6114000000-N | SP    | SPECIALIZED HAND MOWING                 | 2<br>HR     |           |        |
| 0121   | 6117000000-N | SP    | RESPONSE FOR EROSION CONTROL            | 18<br>EA    |           |        |
| 0122   | 6123000000-E | 1670  | REFORESTATION                           | 0.1<br>ACR  |           |        |
| 012E   | 7060000000-E | 1705  | SIGNAL CABLE                            | 1,710<br>LF |           |        |
| 0124   | 7120000000-E | 1705  | VEHICLE SIGNAL HEAD (12", 3<br>SECTION) | 20<br>EA    |           |        |

County : Johnston

| Line # | Item Number  | Sec # | Description                          | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--------------------------------------|----------|-----------|--------|
| 012E   | 7144000000-E | 1705  | VEHICLE SIGNAL HEAD (12", 5 SECTION) | 3        | EA        |        |
| 012E   | 7264000000-E | 1710  | MESSENGER CABLE (3/8")               | 50       | LF        |        |
| 0127   | 7300000000-E | 1715  | UNPAVED TRENCHING (*****)<br>(1, 2") | 300      | LF        |        |
| 012E   | 7301000000-E | 1715  | DIRECTIONAL DRILL (*****)<br>(2, 2") | 100      | LF        |        |
| 012E   | 7324000000-N | 1716  | JUNCTION BOX (STANDARD SIZE)         | 5        | EA        |        |
| 013C   | 7360000000-N | 1720  | WOOD POLE                            | 2        | EA        |        |
| 0131   | 7372000000-N | 1721  | GUY ASSEMBLY                         | 2        | EA        |        |
| 0132   | 7432000000-E | 1722  | 2" RISER WITH HEAT SHRINK TUBING     | 2        | EA        |        |
| 013E   | 7444000000-E | 1725  | INDUCTIVE LOOP SAWCUT                | 920      | LF        |        |
| 0134   | 7456000000-E | 1726  | LEAD-IN CABLE (*****)<br>(18-2)      | 480      | LF        |        |
| 013E   | 7552000000-N | 1731  | INTERCONNECT CENTER                  | 3        | EA        |        |
| 013E   | 7575142000-N | SP    | 900MHZ WIRELESS RADIO SYSTEM         | 3        | EA        |        |
| 0137   | 7588000000-N | SP    | METAL POLE WITH SINGLE MAST ARM      | 1        | EA        |        |
| 013E   | 7590000000-N | SP    | METAL POLE WITH DUAL MAST ARM        | 1        | EA        |        |
| 013E   | 7613000000-N | SP    | SOIL TEST                            | 2        | EA        |        |
| 014C   | 7614100000-E | SP    | DRILLED PIER FOUNDATION              | 16       | CY        |        |
| 0141   | 7631000000-N | SP    | MAST ARM WITH METAL POLE DE-SIGN     | 2        | EA        |        |
| 0142   | 7684000000-N | 1750  | SIGNAL CABINET FOUNDATION            | 1        | EA        |        |



County : Johnston

| Line #  | Item Number         | Sec # | Description  | Quantity | Unit Cost | Amount |
|---|---------------------|-------|--|----------|-----------|--------|
| 0143  | 7756000000-N        | 1751  | CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED) | 1        | EA        |        |
| 0144  | 7780000000-N        | 1751  | DETECTOR CARD (TYPE 2070L)                         | 3        | EA        |        |
| 0145  | 7901000000-N        | 1753  | CABINET BASE EXTENDER                              | 1        | EA        |        |
| ***** BEGIN SCHEDULE AA *****<br>***** ( 3 ALTERNATES ) ***** |                     |       |  |          |           |        |
| 0146  | 0360000000-E<br>AA1 | 310   | 12" RC PIPE CULVERTS, CLASS III                    | 36       | LF        |        |
| 0147  | 0366000000-E<br>AA1 | 310   | 15" RC PIPE CULVERTS, CLASS III                    | 1,456    | LF        |        |
| 0148  | 0372000000-E<br>AA1 | 310   | 18" RC PIPE CULVERTS, CLASS III                    | 816      | LF        |        |
| 0149  | 0378000000-E<br>AA1 | 310   | 24" RC PIPE CULVERTS, CLASS III                    | 72       | LF        |        |
| 0150  | 0384000000-E<br>AA1 | 310   | 30" RC PIPE CULVERTS, CLASS III                    | 216      | LF        |        |
| *** OR ***  |                     |       |  |          |           |        |
| 0151  | 0366000000-E<br>AA2 | 310   | 15" RC PIPE CULVERTS, CLASS III                    | 1,000    | LF        |        |
| 0152  | 0372000000-E<br>AA2 | 310   | 18" RC PIPE CULVERTS, CLASS III                    | 588      | LF        |        |
| 0153  | 0378000000-E<br>AA2 | 310   | 24" RC PIPE CULVERTS, CLASS III                    | 36       | LF        |        |
| 0154  | 0384000000-E<br>AA2 | 310   | 30" RC PIPE CULVERTS, CLASS III                    | 180      | LF        |        |
| 0155  | 0536000000-E<br>AA2 | SP    | **** HDPE PIPE CULVERTS (12")                      | 36       | LF        |        |
| 0156  | 0536000000-E<br>AA2 | SP    | **** HDPE PIPE CULVERTS (15")                      | 456      | LF        |        |
| 0157  | 0536000000-E<br>AA2 | SP    | **** HDPE PIPE CULVERTS (18")                      | 228      | LF        |        |

County : Johnston

| Line #      | Item Number  | Sec # | Description  | Quantity    | Unit Cost | Amount |
|-------------|--------------|-------|--|-------------|-----------|--------|
| 015E<br>AA2 | 0536000000-E | SP    | **** HDPE PIPE CULVERTS<br>(24")   | 36<br>LF    |           |        |
| 015E<br>AA2 | 0536000000-E | SP    | **** HDPE PIPE CULVERTS<br>(30")   | 36<br>LF    |           |        |
| *** OR ***  |              |       |  |             |           |        |
| 016C<br>AA3 | 0366000000-E | 310   | 15" RC PIPE CULVERTS, CLASS<br>III   | 1,000<br>LF |           |        |
| 0161<br>AA3 | 0372000000-E | 310   | 18" RC PIPE CULVERTS, CLASS<br>III   | 588<br>LF   |           |        |
| 0162<br>AA3 | 0378000000-E | 310   | 24" RC PIPE CULVERTS, CLASS<br>III   | 36<br>LF    |           |        |
| 016E<br>AA3 | 0384000000-E | 310   | 30" RC PIPE CULVERTS, CLASS<br>III   | 180<br>LF   |           |        |
| 0164<br>AA3 | 0540000000-E | SP    | **** ALUMINIZED CORRUGATED<br>STEEL PIPE CULVERTS, *****<br>THICK<br>(12", 0.064") | 36<br>LF    |           |        |
| 016E<br>AA3 | 0540000000-E | SP    | **** ALUMINIZED CORRUGATED<br>STEEL PIPE CULVERTS, *****<br>THICK<br>(15", 0.064") | 456<br>LF   |           |        |
| 016E<br>AA3 | 0540000000-E | SP    | **** ALUMINIZED CORRUGATED<br>STEEL PIPE CULVERTS, *****<br>THICK<br>(18", 0.064") | 228<br>LF   |           |        |
| 0167<br>AA3 | 0540000000-E | SP    | **** ALUMINIZED CORRUGATED<br>STEEL PIPE CULVERTS, *****<br>THICK<br>(24", 0.064") | 36<br>LF    |           |        |
| 016E<br>AA3 | 0540000000-E | SP    | **** ALUMINIZED CORRUGATED<br>STEEL PIPE CULVERTS, *****<br>THICK<br>(30", 0.079") | 36<br>LF    |           |        |

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

1350/Jul16/Q79232.7/D637542772000/E168

Total Amount Of Bid For Entire Project :

**Contract No: C201297**

**County: Johnston**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General