

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	5,200 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14 + 26.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,200 TON		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	275 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	18 TON		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	36 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0014	1121000000-E	520	AGGREGATE BASE COURSE	102 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0016	1275000000-E	600	PRIME COAT	100 GAL		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	185 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	360 TON		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	32 TON		
002C	2000000000-N	806	RIGHT OF WAY MARKERS	20 EA		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	120 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	90 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
003C	2556000000-E	846	SHOULDER BERM GUTTER	190 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	400 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0033	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	300 LF		
0036	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	100 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
003E	3635000000-E	876	RIP RAP, CLASS II	3 TON		
003E	3649000000-E	876	RIP RAP, CLASS B	2 TON		
004C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	524 SY		
0041	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	181 SF		
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	170 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
004E	4430000000-N	1130	DRUMS	27 EA		
004E	4435000000-N	1135	CONES	27 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	30 LF		
004E	4450000000-N	1150	FLAGGER	400 HR		
004E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
005C	4485000000-E	1170	PORTABLE CONCRETE BARRIER	260 LF		
0051	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	170 LF		
0052	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	64 EA		
0053	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	288 LF		
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,464 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	44 LF		
0056	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	288 LF		
0057	6000000000-E	1605	TEMPORARY SILT FENCE	865 LF		
0058	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0059	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	175 TON		
0060	6012000000-E	1610	SEDIMENT CONTROL STONE	255 TON		
0061	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0062	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0063	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	35 LF		
0065	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0066	6029000000-E	SP	SAFETY FENCE	500 LF		
0067	6030000000-E	1630	SILT EXCAVATION	750 CY		
0068	6036000000-E	1631	MATTING FOR EROSION CONTROL	700 SY		
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0070	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0071	6071030000-E	SP	COIR FIBER BAFFLES	175 LF		
0072	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0073	6087000000-E	1660	MOWING	1 ACR		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
007E	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
008C	6123000000-E	1670	REFORESTATION	0.25 ACR		
0081	7060000000-E	1705	SIGNAL CABLE	720 LF		
0082	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	4 EA		
008E	7252000000-E	1710	MESSENGER CABLE (1/4")	600 LF		
0084	7264000000-E	1710	MESSENGER CABLE (3/8")	80 LF		
008E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	120 LF		
008E	7360000000-N	1720	WOOD POLE	7 EA		
0087	7372000000-N	1721	GUY ASSEMBLY	6 EA		
008E	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
008E	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2 EA		
009C	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	270 LF		
0091	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	880 LF		
0092	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	1 EA		
***** BEGIN SCHEDULE AA ***** ***** ( 3 ALTERNATES ) *****						
0094 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	116 LF		
*** OR ***						
0095 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
*** OR ***						
0096 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	56 LF		
*** OR ***						
0097 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
*** OR ***						
0098 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	56 LF		
***** END SCHEDULE AA *****						
<b>WALL ITEMS</b>						
0099	8801000000-E	SP	MSE RETAINING WALL	1,100 SF		
<b>STRUCTURE ITEMS</b>						
0100	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14 + 26.50 -L-)	Lump Sum	L.S.	
0101	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14 + 26.50 -L-)	Lump Sum	L.S.	
0102	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	65.75 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	47 LF		
0104	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	80.62 LF		
0105	8113000000-N	SP	SID INSPECTION	3 EA		
0106	8115000000-N	SP	CROSSHOLE SONIC LOGGING	3 EA		
0107	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	2,500 CY		
0108	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,898 SF		
0109	8161000000-E	420	GROOVING BRIDGE FLOORS	3,826 SF		
0110	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	111.2 CY		
0111	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14 + 26.50 -L-)	Lump Sum	L.S.	
0112	8217000000-E	425	REINFORCING STEEL (BRIDGE)	25,728 LB		
0113	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,465 LB		
0114	8259000000-E	430	36" PRESTRESSED CONCRETE GIRDERS	460.82 LF		
0115	8364000000-E	450	HP12X53 STEEL PILES	210 LF		
0116	8391000000-N	450	STEEL PILE POINTS	6 EA		
0117	8503000000-E	460	CONCRETE BARRIER RAIL	234.47 LF		
0118	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	358 TON		
0119	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	397 SY		
0120	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0908/Jul11/Q74075.86/D574789810000/E121			Total Amount Of Bid For Entire Project :			



**Contract No: C201363**

**County: McDowell**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General