

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM ROADWAY CONSTRUCTION	Lump Sum	L.S.	
STRUCTURE ITEMS						
0003	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17 + 15.00-L-)	Lump Sum	L.S.	
0004	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0005	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17 + 15.00 -L-)	Lump Sum	L.S.	
0006	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17 + 15.00-L-)	Lump Sum	L.S.	
0007	8364000000-E	450	HP12X53 STEEL PILES	630 LF		
0008	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	700 LF		
0009	8393000000-N	450	PILE REDRIVES	16 EA		
0010	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	170 TON		
0011	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	
0012	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	
0802/Jul11/Q1524.0/D83759940000/E12			Total Amount Of Bid For Entire Project :			

Contract No: C 201499

County: Sampson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General