

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	23,250 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+73.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	50 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	65 CY		
0009	0141000000-E	240	BERM DITCH CONSTRUCTION	350 LF		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	90 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	48 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	132 LF		
0015	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	88 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0017	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0018	0995000000-E	340	PIPE REMOVAL	156 LF		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,225 TON		
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	640 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	95 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	23 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	9 EA		
0031	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	12 LF		
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0034	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0035	2556000000-E	846	SHOULDER BERM GUTTER	150 LF		
0036	2619000000-E	850	4" CONCRETE PAVED DITCH	15 SY		
0037	3030000000-E	862	STEEL BM GUARDRAIL	550 LF		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0039	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0040	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0041	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0042	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0043	3628000000-E	876	RIP RAP, CLASS I	70 TON		
0044	3635000000-E	876	RIP RAP, CLASS II	470 TON		
0045	3649000000-E	876	RIP RAP, CLASS B	6 TON		
0046	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,465 SY		
0047	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0048	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	375 SF		
0049	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0050	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	15,000 LF		
0052	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	47 EA		
0053	6000000000-E	1605	TEMPORARY SILT FENCE	2,465 LF		
0054	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	175 TON		
0055	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	740 TON		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6012000000-E	1610	SEDIMENT CONTROL STONE	720 TON		
0057	6015000000-E	1615	TEMPORARY MULCHING	7.5 ACR		
0058	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0059	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0060	6024000000-E	1622	TEMPORARY SLOPE DRAINS	80 LF		
0061	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0062	6029000000-E	SP	SAFETY FENCE	400 LF		
0063	6030000000-E	1630	SILT EXCAVATION	2,720 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,535 SY		
0065	6037000000-E	SP	COIR FIBER MAT	10 SY		
0066	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,005 SY		
0067	6042000000-E	1632	1/4" HARDWARE CLOTH	875 LF		
0068	6070000000-N	SP	SPECIAL STILLING BASINS	10 EA		
0069	6071030000-E	SP	COIR FIBER BAFFLES	575 LF		
0070	6071050000-E	SP	*** SKIMMER (2-1/2")	1 EA		
0071	6084000000-E	1660	SEEDING & MULCHING	8 ACR		
0072	6087000000-E	1660	MOWING	4.5 ACR		
0073	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0074	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0075	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175 LB		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6108000000-E	1665	FERTILIZER TOPDRESSING	5.75	TON	
0077	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0078	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
0079	6123000000-E	1670	REFORESTATION	0.1	ACR	

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
 \*\*\*\*\* ( 3 ALTERNATES ) \*\*\*\*\*

0080 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	336	LF	
0081 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	168	LF	

\*\*\* OR \*\*\*

0082 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	248	LF	
0083 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	76	LF	
0084 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	88	LF	
0085 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	92	LF	

\*\*\* OR \*\*\*

0086 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	248	LF	
0087 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	76	LF	
0088 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	88	LF	
0089 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	92	LF	

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0090	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (21+73.50 -L-)	Lump Sum	L.S.	
0091	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+73.50 -L-)	Lump Sum	L.S.	
0092	8096000000-E	SP	PILE EXCAVATION IN SOIL	7 LF		
0093	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	3 LF		
0094	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	29.8 LF		
0095	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	36 LF		
0096	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	18 LF		
0097	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	16 LF		
0098	8113000000-N	SP	SID INSPECTION	1 EA		
0099	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0100	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21+73.50 -L-)	Lump Sum	L.S.	
0101	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	6,796 SF		
0102	8161000000-E	420	GROOVING BRIDGE FLOORS	6,984 SF		
0103	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	110.4 CY		
0104	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+73.50 -L-)	Lump Sum	L.S.	
0105	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,760 LB		
0106	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,116 LB		

County : Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	764 LF		
0108	8364000000-E	450	HP12X53 STEEL PILES	360 LF		
0109	8503000000-E	460	CONCRETE BARRIER RAIL	385.77 LF		
0110	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,022 TON		
0111	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,135 SY		
0112	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0113	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0803/Jul11/Q107502.07/D468595540000/E113			Total Amount Of Bid For Entire Project :			

**Contract No: C201599**

**County: Vance**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General