

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (41+81.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0008	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	4 EA		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	9,000 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	5,700 SY		
0012	0234000000-E	SP	GENERIC GRADING ITEM DAM EMBANKMENT EARTH FILL	8,150 CY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	252 TON		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	596 LF		
0015	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	100 LF		
0016	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	76 LF		
0017	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	332 LF		
0018	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	200 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0528000000-E	310	*** RC PIPE ELBOWS, CLASS III (24")	2 EA		
0020	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	2.5 LF		
0021	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	216 LF		
0022	0660000000-E	310	*****BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (18", 0.064")	36 LF		
0023	0680000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE A ***** THICK (18", 0.064")	2 EA		
0024	0973100000-E	330	*** WELDED STEEL PIPE IN SOIL (42")	96 LF		
0025	0995000000-E	340	PIPE REMOVAL	475 LF		
0026	1110000000-E	510	STABILIZER AGGREGATE	1,000 TON		
0027	1121000000-E	520	AGGREGATE BASE COURSE	9,200 TON		
0028	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0029	1275000000-E	600	PRIME COAT	850 GAL		
0030	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,900 TON		
0031	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,800 TON		
0032	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,175 TON		
0033	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	71 TON		
0034	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	555 TON		
0035	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2022000000-E	815	SUBDRAIN EXCAVATION	520 CY		
0037	2033000000-E	815	SUBDRAIN FINE AGGREGATE	390 CY		
0038	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,300 LF		
0039	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	69 EA		
0040	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	5 EA		
0041	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	30 LF		
0042	2209000000-E	838	ENDWALLS	9 CY		
0043	2264000000-E	840	PIPE PLUGS	1 CY		
0044	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	16 EA		
0045	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	7 LF		
0046	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		
0047	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	9 EA		
0048	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0049	2473000000-N	SP	GENERIC DRAINAGE ITEM 16" NONPERFORATED PVC ELBOWS	1 EA		
0050	2473000000-N	SP	GENERIC DRAINAGE ITEM 48" PRECAST MANHOLE	1 EA		
0051	2473000000-N	SP	GENERIC DRAINAGE ITEM CAST IRON GATE (12")	1 EA		
0052	2473000000-N	SP	GENERIC DRAINAGE ITEM TRASH GUARD W/ANTI-VORTEX COVER	1 EA		
0053	2473000000-N	SP	GENERIC DRAINAGE ITEM TRASH RACK (30" X 30")	1 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	2484000000-E	SP	GENERIC DRAINAGE ITEM 16" NONPERFORATED PVC PIPE	20 LF		
0055	2484000000-E	SP	GENERIC DRAINAGE ITEM 6" NONPERFORATED PVC PIPE	500 LF		
0056	2495000000-E	SP	GENERIC DRAINAGE ITEM CONCRETE CLASS AA	14 CY		
0057	2495000000-E	SP	GENERIC DRAINAGE ITEM FINE AGGREGATE FILTER DIA- PHRAGM	31 CY		
0058	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	90 SY		
0059	3030000000-E	862	STEEL BM GUARDRAIL	500 LF		
0060	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0061	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0062	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0063	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0064	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0065	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	250 LF		
0066	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (TYPE III)	4 EA		
0067	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0068	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	3,200 LF		
0069	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	280 EA		
0070	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	40 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	3554000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, DOUBLE GATE (48")	2 EA		
0072	3557000000-E	866	ADDITIONAL BARBED WIRE	320 LF		
0073	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (48", 10', 20')	2 EA		
0074	3628000000-E	876	RIP RAP, CLASS I	71 TON		
0075	3635000000-E	876	RIP RAP, CLASS II	190 TON		
0076	3649000000-E	876	RIP RAP, CLASS B	850 TON		
0077	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	5,875 SY		
0078	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	44 SF		
0079	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	281.06 SF		
0080	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	38.75 SF		
0081	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	980 LF		
0082	4096000000-N	904	SIGN ERECTION, TYPE D	3 EA		
0083	4102000000-N	904	SIGN ERECTION, TYPE E	59 EA		
0084	4108000000-N	904	SIGN ERECTION, TYPE F	5 EA		
0085	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	2 EA		
0086	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
0087	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	1 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	41 EA		
0089	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	10 EA		
0090	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0091	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	351 SF		
0092	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	106 SF		
0093	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	126 SF		
0094	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0095	4430000000-N	1130	DRUMS	62 EA		
0096	4445000000-E	1145	BARRICADES (TYPE III)	320 LF		
0097	4450000000-N	1150	FLAGGER	1,600 HR		
0098	4480000000-N	1165	TMIA	1 EA		
0099	4510000000-N	SP	POLICE	32 HR		
0100	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	59 EA		
0101	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	63,035 LF		
0102	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,046 LF		
0103	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	144 LF		
0104	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	22 EA		
0105	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4" *****) (HIGHLY REFLECTIVE ELEMENTS)	30,896 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (HIGHLY REFLECTIVE ELEMENTS)	2,349 LF		
0107	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (HIGHLY REFLECTIVE ELEMENTS)	71 LF		
0108	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (HIGHLY REFLECTIVE ELEMENTS)	28 EA		
0109	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	211 EA		
0110	5325600000-E	1510	6" WATER LINE	739 LF		
0111	5325800000-E	1510	8" WATER LINE	44 LF		
0112	5326200000-E	1510	12" WATER LINE	873 LF		
0113	5540000000-E	1515	6" VALVE	4 EA		
0114	5546000000-E	1515	8" VALVE	2 EA		
0115	5558000000-E	1515	12" VALVE	2 EA		
0116	5606000000-E	1515	2" BLOW OFF	1 EA		
0117	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0118	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0119	5800000000-E	1530	ABANDON 6" UTILITY PIPE	754 LF		
0120	5801000000-E	1530	ABANDON 8" UTILITY PIPE	3,301 LF		
0121	5804000000-E	1530	ABANDON 12" UTILITY PIPE	856 LF		
0122	6000000000-E	1605	TEMPORARY SILT FENCE	9,700 LF		
0123	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	200 TON		
0124	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	405 TON		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0125	6012000000-E	1610	SEDIMENT CONTROL STONE	1,215 TON		
0126	6015000000-E	1615	TEMPORARY MULCHING	10 ACR		
0127	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	450 LB		
0128	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.75 TON		
0129	6024000000-E	1622	TEMPORARY SLOPE DRAINS	125 LF		
0130	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	8 EA		
0131	6029000000-E	SP	SAFETY FENCE	8,400 LF		
0132	6030000000-E	1630	SILT EXCAVATION	13,220 CY		
0133	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,800 SY		
0134	6037000000-E	SP	COIR FIBER MAT	25 SY		
0135	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	275 SY		
0136	6042000000-E	1632	1/4" HARDWARE CLOTH	1,000 LF		
0137	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	90 SY		
0138	6070000000-N	SP	SPECIAL STILLING BASINS	60 EA		
0139	6071030000-E	SP	COIR FIBER BAFFLES	575 LF		
0140	6071050000-E	SP	*** SKIMMER (2")	2 EA		
0141	6071050000-E	SP	*** SKIMMER (2-1/2")	2 EA		
0142	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
0143	6087000000-E	1660	MOWING	4.5 ACR		
0144	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		



Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0145	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0146	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200 LB		
0147	6108000000-E	1665	FERTILIZER TOPDRESSING	7.5 TON		
0148	6111000000-E	SP	IMPERVIOUS DIKE	175 LF		
0149	6114000000-N	SP	SPECIALIZED HAND MOWING	3.5 HR		
0150	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0151	6133000000-N	SP	GENERIC EROSION CONTROL ITEM DAM CONSTRUCTION DEWATERING	Lump Sum	L.S.	
0152	6135000000-E	SP	GENERIC EROSION CONTROL ITEM WETLAND GRASS PLANTING	2.9 ACR		
0153	6138000000-E	SP	GENERIC EROSION CONTROL ITEM DIVERSION CHANNEL	650 CY		
<b>WALL ITEMS</b>						
0154	8847000000-E	SP	GENERIC RETAINING WALL ITEM 22.6" SHEET PILE RETAINING WALLS (STEEL)	1,897 SF		
<b>STRUCTURE ITEMS</b>						
0155	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (47+08.03 -L-)	Lump Sum	L.S.	
0156	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (47+08.03 -L-)	Lump Sum	L.S.	
0157	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (47+08.03 -L-)	Lump Sum	L.S.	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0158	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (14,47+08.03 -L-)	Lump Sum	L.S.	
0159	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (16,47+08.03 -L-)	Lump Sum	L.S.	
0160	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (17,47+08.03 -L-)	Lump Sum	L.S.	
0161	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (18,47+08.03 -L-)	Lump Sum	L.S.	
0162	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (19,47+08.03 -L-)	Lump Sum	L.S.	
0163	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (20,47+08.03 -L-)	Lump Sum	L.S.	
0164	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (21,47+08.03 -L-)	Lump Sum	L.S.	
0165	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (22,47+08.03 -L-)	Lump Sum	L.S.	
0166	8108000000-E	SP	***_*** DIA DRILLED PIERS (5'-0")	2,368 LF		
0167	8108000000-E	SP	***_*** DIA DRILLED PIERS (6'-0")	2,107 LF		
0168	8111000000-E	SP	PERMANENT STEEL CASING FOR ***_*** DIA DRILLED PIER (5'-0")	660 LF		
0169	8111000000-E	SP	PERMANENT STEEL CASING FOR ***_*** DIA DRILLED PIER (6'-0")	720 LF		
0170	8112730000-N	SP	PDA TESTING	4 EA		
0171	8112740000-N	SP	PDA ASSISTANCE	11 EA		
0172	8113000000-N	SP	SID INSPECTION	46 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0173	8114000000-N	SP	SPT TESTING	46 EA		
0174	8115000000-N	SP	CROSSHOLE SONIC LOGGING	5 EA		
0175	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	3,236 CY		
0176	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	89,918 SF		
0177	8161000000-E	420	GROOVING BRIDGE FLOORS	77,110 SF		
0178	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	3,471.6 CY		
0179	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (47+08.03 -L-)	Lump Sum	L.S.	
0180	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,507,318 LB		
0181	8226000000-E	425	EPOXY COATED SPIRAL COLUMN RE- INFORCING STEEL (BRIDGE)	167,398 LB		
0182	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	1,607.513 LF		
0183	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	6,431.221 LF		
0184	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	41,100 LS		
0185	8364000000-E	450	HP12X53 STEEL PILES	6,010 LF		
0186	8384000000-E	450	HP14X73 STEEL PILES	1,920 LF		
0187	8393000000-N	450	PILE REDRIVES	52 EA		
0188	8475000000-E	460	TWO BAR METAL RAIL	5,105 LF		
0189	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	5,105 LF		
0190	8594000000-E	876	RIP RAP, CLASS B	445 TON		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0191	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	219 TON		
0192	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	736.8 SY		
0193	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0194	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0195	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (47+08.03 -L-)	Lump Sum	L.S.	
0196	8744000000-N	SP	SOLAR ARRAY SUPPORT PLATFORM	Lump Sum	L.S.	
0197	8860000000-N	SP	GENERIC STRUCTURE ITEM AXIAL LOAD TEST	Lump Sum	L.S.	
0198	8860000000-N	SP	GENERIC STRUCTURE ITEM POST-TENSIONING TENDONS	Lump Sum	L.S.	
0199	8867000000-E	SP	GENERIC STRUCTURE ITEM 4'-0" DIA DRILLED PIERS (DEMONSTRATION PIER)	81 LF		
0200	8867000000-E	SP	GENERIC STRUCTURE ITEM 78" POST-TENSIONED PRESTRESSED CONCRETE GIRDERS	2,088.2 LF		
0201	8867000000-E	SP	GENERIC STRUCTURE ITEM MESSENGER CABLE SYSTEM	2,860 LF		
0202	8897000000-N	SP	GENERIC STRUCTURE ITEM SONIC CALIPER TESTING	1 EA		
1509/Aug06/Q2146495.044/D952030570000/E202			Total Amount Of Bid For Entire Project :			

**Contract No: C201882**

**County: Brunswick**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General