

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000995000-E	SP	GENERIC MISCELLANEOUS ITEM EXCAVATION, HAULING, AND DISPOSAL OF CONTAMINATED SOIL	50 TON		
0004	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0005	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	18,000 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (32 + 18.000)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	2,166 CY		
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
001C	0106000000-E	230	BORROW EXCAVATION	132,400 CY		
0011	0134000000-E	240	DRAINAGE DITCH EXCAVATION	2,340 CY		
0012	0141000000-E	240	BERM DITCH CONSTRUCTION	290 LF		
0013	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	8,000 SY		
0014	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	2,350 SY		
001E	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	5,100 SY		
001E	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0017	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,000 SY		
001E	0199000000-E	SP	TEMPORARY SHORING	2,994 SF		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	540 TON		
002C	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	200 LF		
0021	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	320 LF		
0022	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	524 LF		
0023	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0024	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	8 EA		
002E	0973100000-E	330	*** WELDED STEEL PIPE IN SOIL (15")	248 LF		
002E	0995000000-E	340	PIPE REMOVAL	1,128 LF		
0027	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
002E	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
002E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	10,700 TON		
003C	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,100 TON		
0031	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	7,500 TON		
0032	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	700 TON		
0033	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,100 TON		
0034	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	700 TON		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	530 TON		
003E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,362 TON		
0037	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	42 TON		
003E	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	30 TON		
003E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	48 TON		
004C	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	2,940 LF		
0041	2000000000-N	806	RIGHT OF WAY MARKERS	50 EA		
0042	2022000000-E	815	SUBDRAIN EXCAVATION	448 CY		
0043	2033000000-E	815	SUBDRAIN FINE AGGREGATE	336 CY		
0044	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,000 LF		
0045	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	60 EA		
004E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		
0047	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	24 LF		
004E	2209000000-E	838	ENDWALLS	3.4 CY		
004E	2253000000-E	840	PIPE COLLARS	2.1 CY		
005C	2264000000-E	840	PIPE PLUGS	0.6 CY		
0051	2275000000-E	SP	FLOWABLE FILL	6.1 CY		
0052	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	57 EA		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	32.09	LF	
0054	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1	EA	
0055	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	6	EA	
0056	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	7	EA	
0057	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
005E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	6	EA	
0059	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	11	EA	
006C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	10	EA	
0061	2396000000-N	840	FRAME WITH COVER, STD 840.54	9	EA	
0062	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	2	EA	
0063	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	2,200	LF	
0064	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	4,500	LF	
006E	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,300	SY	
006E	2815000000-N	858	ADJUSTMENT OF DROP INLETS	3	EA	
0067	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	2	EA	
006E	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	1	EA	

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	3030000000-E	862	STEEL BM GUARDRAIL	2,600 LF		
0070	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0071	3060000000-E	862	STEEL BM GUARDRAIL, DOUBLE FACED	137.5 LF		
0072	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0073	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	5 EA		
0074	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0075	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0076	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,665 LF		
0077	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	375 LF		
0078	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	50 LF		
0079	3383000000-E	862	TEMPORARY STEEL BM GUARDRAIL, DOUBLE FACED	225 LF		
0080	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	1 EA		
0081	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	3 EA		
0082	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-83)	2 EA		
0083	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1 EA		
0084	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	3,800 LF		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	1,030 EA		
008E	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	40 EA		
0087	3557000000-E	866	ADDITIONAL BARBED WIRE	30 LF		
008E	3628000000-E	876	RIP RAP, CLASS I	255 TON		
008E	3649000000-E	876	RIP RAP, CLASS B	758 TON		
009C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,324 SY		
0091	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	4 CY		
0092	4057000000-E	SP	OVERHEAD FOOTING	21.94 CY		
0093	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	3,611 LB		
0094	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,317 LF		
009E	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	1 EA		
009E	4082000000-E	903	SUPPORTS, WOOD	75 LF		
0097	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (37+00 -Y2-WBL)	Lump Sum	L.S.	
009E	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (44+50 -Y2-WBL)	Lump Sum	L.S.	
009E	4096000000-N	904	SIGN ERECTION, TYPE D	6 EA		
010C	4102000000-N	904	SIGN ERECTION, TYPE E	25 EA		
0101	4108000000-N	904	SIGN ERECTION, TYPE F	12 EA		
0102	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (A)	5 EA		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	4109000000-N	904	SIGN ERECTION, TYPE *** (OVER-HEAD) (B)	2 EA		
0104	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	5 EA		
0105	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	1 EA		
0106	4114000000-N	904	SIGN ERECTION, MILEMARKERS	1 EA		
0107	4116000000-N	904	SIGN ERECTION, OVERLAY (GROUND MOUNTED)	3 EA		
0108	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	4 EA		
0109	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	8 EA		
011C	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (F)	2 EA		
0111	4116300000-N	904	SIGN ERECTION, LOGO TO PANEL	7 EA		
0112	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	4 EA		
0113	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	2 EA		
0114	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	71 EA		
011E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	3 EA		
0116	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	3 EA		
0117	4234000000-N	907	DISPOSAL OF SIGN, A OR B (OVERHEAD)	1 EA		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
011E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	617	SF	
011E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,196	SF	
012C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	224	SF	
0121	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4	EA	
0122	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	6	EA	
0123	4430000000-N	1130	DRUMS	331	EA	
0124	4435000000-N	1135	CONES	100	EA	
012E	4445000000-E	1145	BARRICADES (TYPE III)	160	LF	
012E	4450000000-N	1150	FLAGGER	3,200	HR	
0127	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
012E	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2	EA	
012E	4480000000-N	1165	TMIA	4	EA	
013C	4485000000-E	1170	PORTABLE CONCRETE BARRIER	470	LF	
0131	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	1,280	LF	
0132	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	460	LF	
013E	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	470	LF	
0134	4510000000-N	SP	POLICE	800	HR	
013E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	325	EA	
013E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	14,928	LF	

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0137	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,811 LF		
013E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,776 LF		
013S	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	460 LF		
014C	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	32 EA		
0141	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	76 EA		
0142	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	468 LF		
014S	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	936 LF		
0144	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (III)	7 EA		
014E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	49,425 LF		
014E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	5,936 LF		
0147	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	870 LF		
014E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	80 EA		
014S	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	110 EA		
015C	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	12,461 LF		
0151	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,026 LF		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0152	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	186	LF	
0153	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	34	EA	
0154	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	487	EA	
015E	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
015E	5325800000-E	1510	8" WATER LINE	1,102	LF	
0157	5326200000-E	1510	12" WATER LINE	120	LF	
015E	5546000000-E	1515	8" VALVE	2	EA	
015E	5648000000-N	1515	RELOCATE WATER METER	7	EA	
016C	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	
0161	5801000000-E	1530	ABANDON 8" UTILITY PIPE	1,200	LF	
0162	6000000000-E	1605	TEMPORARY SILT FENCE	3,500	LF	
0163	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	440	TON	
0164	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,030	TON	
016E	6012000000-E	1610	SEDIMENT CONTROL STONE	775	TON	
016E	6015000000-E	1615	TEMPORARY MULCHING	17.5	ACR	
0167	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	650	LB	
016E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.5	TON	
016E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	350	LF	
017C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0171	6030000000-E	1630	SILT EXCAVATION	7,700 CY		
0172	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,500 SY		
0173	6037000000-E	SP	COIR FIBER MAT	50 SY		
0174	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	750 SY		
017E	6042000000-E	1632	1/4" HARDWARE CLOTH	1,250 LF		
017E	6071030000-E	SP	COIR FIBER BAFFLES	760 LF		
0177	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
017E	6071050000-E	SP	*** SKIMMER (2-1/2")	3 EA		
017E	6071050000-E	SP	*** SKIMMER (4")	1 EA		
018C	6071050000-E	SP	*** SKIMMER (5")	1 EA		
0181	6084000000-E	1660	SEEDING & MULCHING	25.5 ACR		
0182	6087000000-E	1660	MOWING	10.5 ACR		
018E	6090000000-E	1661	SEED FOR REPAIR SEEDING	150 LB		
0184	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
018E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	425 LB		
018E	6108000000-E	1665	FERTILIZER TOPDRESSING	19 TON		
0187	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
018E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
018E	7060000000-E	1705	SIGNAL CABLE	5,580 LF		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
019C	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	40	EA	
0191	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	17	EA	
0192	7252000000-E	1710	MESSENGER CABLE (1/4")	2,263	LF	
0193	7264000000-E	1710	MESSENGER CABLE (3/8")	1,330	LF	
0194	7279000000-E	1715	TRACER WIRE	490	LF	
019E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 1")	1,920	LF	
019F	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	490	LF	
0197	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	21	EA	
019E	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	6	EA	
019E	7360000000-N	1720	WOOD POLE	14	EA	
020C	7372000000-N	1721	GUY ASSEMBLY	37	EA	
0201	7408000000-E	1722	1" RISER WITH WEATHERHEAD	5	EA	
0202	7420000000-E	1722	2" RISER WITH WEATHERHEAD	16	EA	
0203	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	3	EA	
0204	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,765	LF	
020E	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	6,930	LF	
020E	7456000000-E	1726	LEAD-IN CABLE (*****) (18-4)	805	LF	
0207	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	3,300	LF	

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
020E	7552000000-N	1731	INTERCONNECT CENTER	4 EA		
020E	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER, DROP & REPEAT	4 EA		
021C	7566000000-N	1733	DELINEATOR MARKER	6 EA		
0211	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORA- TION KIT	1 EA		
0212	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIV- ER	1 EA		
021E	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	3 EA		
0214	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	2,400 LF		
021E	7576000000-N	SP	METAL STRAIN SIGNAL POLE	16 EA		
021E	7613000000-N	SP	SOIL TEST	16 EA		
0217	7614100000-E	SP	DRILLED PIER FOUNDATION	96 CY		
021E	7636000000-N	1745	SIGN FOR SIGNALS	11 EA		
021E	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
022C	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
0221	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0222	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	16 EA		
022E	7901000000-N	1753	CABINET BASE EXTENDER	3 EA		
0224	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	1 EA		
022E	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS LIGHTNING ARRESTOR	1 EA		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
022E	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEM	1	EA	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0227 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,768	LF	
022E AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	944	LF	
022E AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,192	LF	
*** OR ***						
023C AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,488	LF	
0231 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	836	LF	
0232 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	812	LF	
023E AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	280	LF	
0234 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	108	LF	
023E AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	380	LF	
*** OR ***						
023E AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,488	LF	
0237 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	836	LF	
023E AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	812	LF	
023E AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	280	LF	

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
024C AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	108 LF		
0241 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	380 LF		
***** END SCHEDULE AA *****						
WALL ITEMS						
0242	8436000000-E	453	GRAVITY RETAINING WALLS	969 SF		
STRUCTURE ITEMS						
0243	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (32 + 25.27 -L-)	Lump Sum	L.S.	
0244	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (32 + 25.27 -L-)	Lump Sum	L.S.	
024E	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,530 CY		
024E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	24,500 SF		
0247	8161000000-E	420	GROOVING BRIDGE FLOORS	24,719 SF		
024E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	333.7 CY		
024E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (32 + 25.27 -L-)	Lump Sum	L.S.	
025C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	46,464 LB		
0251	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,833 LB		

County : Davie

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0252	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	1,046,847	LS	
0253	8364000000-E	450	HP12X53 STEEL PILES	9,040	LF	
0254	8482000000-E	460	THREE BAR METAL RAIL	447.88	LF	
025E	8531000000-E	462	4" SLOPE PROTECTION	1,181	SY	
0256	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0257	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
025E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1333/Aug10/Q1580052.11/D1085863327000/E258			Total Amount Of Bid For Entire Project :			

Contract No: C201303

County: Davie

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General